

LOCATION MAP
NTS

OWNER:
BUTTERFIELD REALTY LLC.
3102 RT 9 SUITE 2A
COLD SPRING, NY 10516
P:845 809 5969

CONSTRUCTION MANAGER:
UNICORN CONTRACTING CORP.
3102 RT 9 SUITE 2A
COLD SPRING, NY 10516
P:845 809 5969

CIVIL ENGINEER:
SITE DESIGN CONSULTANTS
251-F UNDERHILL AVENUE
YORKTOWN HEIGHTS, NY 10598
P: 914 962 4488

ARCHITECT:
THE SULLIVAN ARCHITECTURAL GROUP
11226 POST ROAD
FAIRFIELD , CT 06824
P: 203 254 8680

LANDSCAPE ARCHITECT:
BLADES & GOVEN LANDSCAPE ARCHITECTS
60 THORPE STREET
FAIRFIELD, CT 06824
P:203 254 8530

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

BUTTERFIELD REDEVELOPMENT PROJECT
1756 ROUTE 9D
COLD SPRING, NY

VILLAGE OF COLD SPRING
PUTNAM COUNTY, NEW YORK
June 9, 2015

NOTES:
1. COORDINATE ALL WATER & SEWER LOCATIONS, INSTALLATIONS & INSPECTIONS W/ Village Dept.
2. COORDINATE W/ NYS DOT.
3. INSPECTIONS, AS REQ'D FOR COMPLIANCE.
4. PROVIDE AS BUILTS INDICATING ACTUAL INSTALLATION & REVISIONS, AS APPROVED

Village of Cold Spring
Code Enforcement
Building & Fire Inspector
Approved ____
Approved as Noted ✓
Reason: see comments
Not Approved ____
Reason: ____
By: WS Date: 9.30.2015
All construction must be compliant with all applicable codes.
Approval does not waive compliance.
Ref. No.: 2015-09-009
OFFICE COPY

APPROVED BY RESOLUTION OF THE VILLAGE OF COLD SPRING PLANNING BOARD

Barney Molloy, Chairman	Date	Resolution No.

LIST OF DRAWINGS

SHEET NUMBER	DRAWING TITLE
G-1	NOTES
G-2	EROSION & SEDIMENT CONTROL NOTES
E-1	EASEMENT PLAN
C-101	SITE/ SUBDIVISION PLAN
C-102	EXISTING CONDITIONS & DEMOLITION PLAN
C-103	EROSION & SEDIMENT CONTROL PLAN
C-104	GRADING PLAN
C-105	UTILITY PLAN
C-106	GRADING & UTILITY PLAN
C-107	NYSDOT PERMIT & M.P.T PLAN
C-108	NYSDOT HDD BORING PLAN
C-109	SIGHT DISTANCE PLAN & PROFILE
L-401	LANDSCAPE PLAN
L-402	SIGHT LIGHTING PLAN
L-403	SITE LIGHTING INFORMATION
C-301	DRIVEWAY PROFILES
C-302	UTILITY PROFILES
C-303	STORM PROFILES
C-501	EROSION & SEDIMENT CONTROL DETAILS
C-502	SITE DETAILS
C-503	WATER UTILITY DETAILS
C-504	STORM-SANITARY DETAILS
C-505	CRYSTAL STREAM TECH. DETAILS
C-506	STORMWATER MANAGEMENT DETAILS
C-507	RAINWATER HARVESTING DETAILS
C-508	RETAINING WALL DETAILS
C-509	NYSDOT DETAILS

PREPARED BY:
Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.SiteDesignConsultants.com

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\SITEDESIGN\CONNEY FOLDER\FILES\25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\DACAD\14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REV 4.DWG

GENERAL NOTES:

1. THE ENGINEER WHOSE SEAL APPEARS HEREON IF NOT RETAINED FOR SUPERVISION OF CONSTRUCTION, IS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS THEREFROM.
2. THE ENGINEER SHALL NOT BE HELD RESPONSIBLE OR HELD ACCOUNTABLE FOR THE INTEGRITY OF ANY STRUCTURES CONSTRUCTED OR UNDER CONSTRUCTION PRIOR TO THE APPROVAL OF THE PLANS.
3. THE VILLAGE ENGINEER'S OFFICE AND WATER DISTRICT OFFICE IS TO BE NOTIFIED 24 HOURS BEFORE COMMENCING SITE CONSTRUCTION OR WATER MAIN CONNECTION.
4. ALL WORK IS TO BE IN ACCORDANCE WITH THE VILLAGE CODE OF PRACTICE AND SPECIFICATIONS.
5. ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY NOTIFIED OF ANY DISCREPANCIES.
6. ALL CHANGES MADE TO THE PLANS SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT.
7. ALL WRITTEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS.
8. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CALL IN A "CODE 753" PRIOR TO CONSTRUCTION OF UNDERGROUND UTILITY LOCATIONS.
9. SUBSTRUCTURES AND THEIR ENCROACHMENTS BELOW GRADE, IF ANY, ARE NOT SHOWN.
10. ANY PROPOSED ELECTRIC AND/OR TELEPHONE SERVICE LINES ARE TO BE PLACED UNDERGROUND.
11. THE DESIGN ENGINEER DISCLAIMS ANY LIABILITY FOR DAMAGE OR LOSS INCURRED DURING OR AFTER CONSTRUCTION.
12. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.

CONTRACTOR RESPONSIBILITIES:

1. ALL WORK ON THE PROJECT SHALL BE PERFORMED IN A WORKMAN LIKE MANNER AND SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE INDUSTRY. THE OWNER WILL BE THE SOLE JUDGE OF THE ACCEPTABILITY OF THE WORK. MATERIALS AND WORK DEEMED UNACCEPTABLE WILL BE REMOVED AND REDONE AT THE SOLE COST AND RESPONSIBILITY OF THE CONTRACTOR.
2. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGES DUE TO HIS ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEE, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY THE WORK UNDER A SEPARATE CONTRACT WITH THE CONTRACTOR.
3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROPERLY SHORE EXISTING UTILITIES IF REQUIRED BY CONSTRUCTION.
4. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE THE VILLAGE ENGINEER IN ADVANCE OF HIS WORK OR AS THE INSPECTOR DEEMS APPROPRIATE.
5. ALL CONDITIONS, LOCATIONS AND DIMENSIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR AND THE OWNER/ENGINEER NOTIFIED IN WRITING OF ANY DISCREPANCIES PRIOR TO THE START OF WORK. THE OWNER/ENGINEER WILL EVALUATE THE SITUATION AND MODIFY THE PLAN AS NECESSARY.
6. ALL CHANGES MADE TO THIS PLAN SHALL BE APPROVED BY THE ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS. ANY UNAUTHORIZED ALTERATION OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.
7. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THIS CONTRACT.
8. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY OF THE WORK UNDER A CONTRACT WITH THE CONTRACTOR.
9. THE CONTRACTOR SHALL VERIFY ALL SUBSTRUCTURES ENCOUNTERED DURING CONSTRUCTION.
10. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.

GENERAL CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL REQUEST A BENCH MARK FROM THE SURVEYOR IN THE SAME DATUM AS THE DESIGN PLANS.
2. FINISHED GRADES SHALL BE OF SUCH ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM BUILDINGS IN ALL DIRECTIONS.
3. CONSTRUCTION ACTIVITY SHALL BE LIMITED FROM 8:00 A.M. TO 6 P.M., AND NO CONSTRUCTION ACTIVITY SHALL OCCUR ON SUNDAYS OR LEGAL NEW YORK STATE HOLIDAYS. WHERE BLASTING IS NECESSARY, IT SHALL OCCUR FROM MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 A.M. AND 6:00 P.M. NO BLASTING SHALL OCCUR ON HOLIDAYS, SATURDAY OR SUNDAY. ALL BLASTING SHALL BE COMPLETED IN ACCORDANCE WITH ALL PERMITS ISSUED BY THE VILLAGE OF COLD SPRING AND OTHER REGULATING AGENCIES. ALL PRE-BLASTING PROCEDURES SHALL BE FOLLOWED INCLUDING SURVEYS OF STRUCTURES AND PREPARATION OF A PRE-BLASTING PLAN. BLASTING LEVELS SHALL BE MONITORED TO ASSURE COMPLIANCE WITH THE VILLAGE CODE. THE CONTRACTOR SHALL COMPLY WITH THE BLASTING MITIGATION PLAN PREPARED FOR THIS PROJECT.
4. ANY SOIL THAT IS UNSUITABLE FOR DEVELOPMENT OF BUILDINGS OR ROADWAYS SHALL BE REMOVED FROM AREAS TO BE DEVELOPED AND SHALL BE DISPOSED OF WITHIN THE SITE IN NEW EMBANKMENTS WHERE STRUCTURAL LOADING, I.E. A BUILDING OR ROADWAY, WILL NOT TAKE PLACE. WHEN CONSTRUCTION IS PROPOSED TO OCCUR IN SPECIFIC AREAS WHERE SOILS ARE OF QUESTIONABLE SUITABILITY, THE OWNER SHALL RETAIN A SOILS ENGINEERTO EVALUATEAND PREPARE A DESIGN FOR THE CONDITION.
5. NO TOPSOIL SHALL BE REMOVED FROM THE SITE, UNLESS DESIRED BY THE OWNER.
6. ROCK CUT STABILITY IS TO BE FIELD VERIFIED BY GEOTECHNICAL ENGINEER AND SHALL BE MODIFIED IF REQUIRED.
7. NO CRUSHING/PROCESSING IS PERMITTED ON THE SITE WITHOUT PRIOR APPROVAL BY THE VILLAGE OF COLD SPRING PLANNING BOARD.
8. ALL DEMOLITION DEBRIS SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN ACCORDANCE WITH NYS ICR 56, AND OTHER FEDERAL, STATE, OR LOCAL STANDARDS. THE CONTRACTOR SHALL OBTAIN AND ADHERE TO THE REQUIREMENTS OF NECESSARY PERMITS. IF NECESSARY THE REMOVAL SHALL BE DONE BY A CONTRACTOR LICENSED TO REMOVE AND DISPOSE OF VARIOUS REGULATED MATERIALS SUCH AS ASBESTOS, TANKS, MATERIALS CONTAINING LEAD, ETC.,
9. NYSDOT REQUIREMENTS: ALL WORK WITHIN THE NYSDOT R.O.W. REQUIRES A UTILITY AND /OR NON-UTILITY WORK PERMIT AND THE CONTRACTOR IS SUBJECT TO THE CONDITIONS STATED WITHIN THE PERMIT.

GENERAL STORM DRAINAGE & UTILITY NOTES

1. ALL UTILITIES, INCLUDING ELECTRIC LINES, TELEPHONE, WATER, SANITARY SEWER LINES, AND STORM SEWER LINES SHALL BE LOCATED UNDERGROUND AND SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE VILLAGE OF COLD SPRING AND THE UTILITY COMPANIES HAVING JURISDICTION.
2. LOCATION OF GAS AND WATER VALVES, ELECTRIC AND TELEPHONE POLES ARE TO BE DETERMINED BY PROPER AUTHORITIES AND APPROVED, AS TO LOCATION.
3. EACH BUILDING CONSTRUCTED HEREON SHALL BE OF SUCH AN ELEVATION THAT THE GROUND WILL SLOPE AWAY FROM IT IN ALL DIRECTIONS. IN THE EVENT THAT THIS IS NOT FEASIBLE, THE CONTRACTOR SHALL INSTALL TYPICAL YARD DRAINS AS REQUIRED AND CONNECT THEM TO THE STORM DRAINAGE SYSTEM OR AS DIRECTED BY THE PROJECT ENGINEER.
4. ROOF LEADERS AND FOOTING DRAINS SHALL EMPTY INTO THE STORM DRAINAGE SYSTEM OR DISCHARGE DIRECTLY TO STORMWATER MANAGEMENT SYSTEMS IF GRADES PERMIT. ALL ROOF AND FOOTING DRAINS WILL BE SLOPED TO HAVE POSITIVE PITCH. UNDER NO CIRCUMSTANCES SHALL THE DISCHARGE OF GROUND WATER OR STORM WATER, EITHER BY GRAVITY OR BY PUMPING, BE DISCHARGED TO ANY SANITARY SEWER SYSTEM.
5. ANY REVISIONS AND/OR ADDITIONS TO THE ROAD STORM DRAINAGE SYSTEMS CURRENTLY SHOWN ON THE PLANS WHICH ARE DEEMED NECESSARY DURING CONSTRUCTION MUST BE MADE BY THE CONTRACTOR AS REQUIRED BY THE VILLAGE AND SHALL BE SHOWN ON THE AS-BUILT DRAWINGS.
6. STORM DRAIN PIPING TO BE HIGH DENSITY POLYETHYLENE AS SHOWN ON THE CONSTRUCTION DRAWINGS. MINIMUM COVER TO BE 2' UNLESS OTHERWISE NOTED.
7. INTERCEPTOR DRAINS ARE TO BE INSTALLED WHERE REQUIRED BY THE VILLAGE OR PROJECT ENGINEER DURING ROAD CONSTRUCTION.
8. ALL EXISTING UNDERGROUND DRAINS ENCOUNTERED DURING CONSTRUCTION OF PROPOSED ROADS ARE TO BE CONNECTED TO PROPOSED DRAINAGE IMPROVEMENTS. CONNECTIONS TO BE APPROVED BY THE VILLAGE ENGINEER.
9. PRIOR TO FINAL APPROVAL AND OPERATION OF DRAINAGE SYSTEM, CONTRACTOR SHALL CLEAR ALL ACCUMULATED SEDIMENT AND/OR DEBRIS FROM DRAINAGE STRUCTURES, MANHOLES, CULVERTS, OUTLETS AND DRAIN INLETS. ENGINEER SHALL BE NOTIFIED FOR FINAL INSPECTION.
10. ALL STRUCTURES SHALL BE SET ONE INCH BELOW TOP COURSE OF PAVEMENT.
11. STREET OPENING PERMIT FROM THE VILLAGE OF COLD SPRING D.P.W. MAY BE REQUIRED FOR INSTALLATIONS IN PUBLIC ROADS.

WATERMAIN NOTES

I. DISTRIBUTION SYSTEM - WATERMAIN

A. GENERAL

THE CONTRACTOR SHALL PERFORM THE NECESSARY EXCAVATION, BACKFILLING, CLEARING, GRUBBING, SHEETING, SHORING, DO ALL SHAPING OF TRENCHES, PUMPING AND BAILING, LAYING AND JOINING OF ALL PIPES, PROTECT AND SUPPORT EXISTING STRUCTURES AND REPAIR THEM, IF DAMAGED, AND ALL ELSE NECESSARY TO COMPLETE THE WORK.

THE CONTRACTOR SHALL FURNISH ALL MATERIALS, EQUIPMENT, LABOR, AND TOOLS NECESSARY TO COMPLETE THE WORK IN A SAFE, NEAT, AND WORKMANLIKE MANNER.

B. SITE AND ACCESS CLEARING (WITHIN EASEMENTS)

THE CONTRACTOR SHALL CONFINE ALL CLEARING OPERATIONS TO WITHIN THE IMMEDIATE AREAS THAT ARE ESSENTIAL FOR CONSTRUCTION OF THE WORK.

C. STOCKPILING OF SUITABLE BACKFILL MATERIAL

THE CONTRACTOR SHALL BE PREPARED WHEN EXCAVATING THE TRENCH TO SEPARATE SUITABLE BACKFILL MATERIAL FROM UNSUITABLE MATERIAL FOR USE AS BACKFILL ADJACENT TO THE PIPE.

D. PROTECTION OF EXISTING STRUCTURES AND UTILITIES

SPECIAL PRECAUTIONS SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT OVERHEAD POWER LINES, WATERMAINS, GAS MAINS, ELECTRIC AND TELEPHONE CONDUITS, STORM AND SANITARY SEWERS, CULVERTS, BUILDINGS AND OTHER EXISTING STRUCTURES IN AND NEAR THE EXCAVATION. IN ALL CASES, WHETHER UNDERGROUND STRUCTURES HAVE OR HAVE NOT BEEN DELINEATED, THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE ACCEPTS NO RESPONSIBILITY FOR THEIR LOCATION. "UNDERGROUND UTILITIES" LOCATES EXISTING UNDERGROUND UTILITIES FREE OF CHARGE. THE PHONE NUMBER IS 1-800-862-7962.

GUTTERS, SEWERS, DRAINS AND DITCHES SHALL BE KEPT OPEN AT ALL TIMES FOR SURFACE DRAINAGE. NO DAMMING OR PONDING OF WATER IN GUTTERS OR OTHER WATERWAYS WILL BE PERMITTED EXCEPT WHERE STREAM CROSSINGS ARE NECESSARY AND THEN ONLY TO AN EXTENT WHICH THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHALL CONSIDER NECESSARY. THE CONTRACTOR SHALL NOT DIRECT ANY FLOW OF WATER ACROSS OR OVER PAVEMENTS EXCEPT THROUGH APPROVED PIPES OR PROPERLY CONSTRUCTED TROUGHS OF SUCH SIZES AND LENGTHS AS MAY BE REQUIRED, AND PLACE THE SAME AS DIRECTED. THE GRADING IN THE VICINITY OF TRENCHES SHALL BE CONTROLLED SO THAT THE GROUND SURFACE IS PROPERLY PITCHED TO PREVENT WATER RUNNING IN THE TRENCHING. THE CONTRACTOR SHALL NOT COMMENCE OPERATIONS INVOLVING ANY PUBLIC UTILITY BEFORE HAVING GIVEN WRITTEN NOTICE TO THE COMPANY OR OWNER, OR ITS AGENTS, AND SHALL COOPERATE WITH THE COMPANY'S OR OWNER'S FORCES IN PROTECTING AND PREVENTING DAMAGE TO THE PROPERTY.

THE CONTRACTOR WILL, AT HIS OWN EXPENSE, BE RESPONSIBLE FOR DIRECT OR INDIRECT DAMAGE THAT MAY BE DONE TO ANY UTILITY OR STRUCTURE IN THE PROSECUTION OF HIS WORK. THE LIABILITY OF THE CONTRACTOR IS ABSOLUTE AND IS NOT DEPENDENT UPON ANY QUESTIONS OF NEGLIGENCE ON HIS PART OR ON THE PART OF HIS AGENT, OR EMPLOYEES, AND THE NEGLECT OF THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE TO DIRECT THE CONTRACTOR TO TAKE ANY PARTICULAR PRECAUTION OR TO REFRAIN FROM DOING SUCH DAMAGE.

SHOULD THE POSITION OF ANY PIPE, CONDUIT, POLE OR OTHER STRUCTURES, ABOVE OR BELOW THE GROUND, BE SUCH AS TO REQUIRE ITS REMOVAL, REALIGNMENT, OR CHANSE DUE TO WORK TO BE DONE, REALIGNMENT OR CHANGE WILL BE DONE BY OR UNDER SUPERVISION OF THE OWNER OF THE OBSTRUCTIONS. THE CONTRACTOR SHALL UNCOVER AND SUSTAIN THE STRUCTURES, AFTER SUCH REALIGNMENT OR CHANGE.

THE CONTACTOR SHALL NOT INTERFERE WITH ANY PERSONS, OR WITH THE OWNER IN PROTECTING, REMOVING, CHANGING OR REPLACING THEIR PIPES, CONDUITS, POLES OR OTHER STRUCTURES; BUT HE SHALL SUFFER SAID PERSONS OR THE OWNER TO TAKE ALL SUCH MEASURES AS THEY MAY DEEM NECESSARY OR ADVISABLE FOR THE PURPOSE AFORESAID, AND THE CONTRACTOR SHALL THEREBY BE IN NO WAY RELIEVED OF ANY OF HIS RESPONSIBILITIES.

THE CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS WITH THE OWNER OF THE RESPECTIVE UTILITY PRIOR TO RELOCATION OR INTERRUPTION OF SERVICE. ALL WORK NECESSARY FOR THE RELOCATION SHALL BE PERFORMED BY THE CONTRACTOR, OR BY THE OWNER AT THE OWNER'S OPTION, AND TO THE SATISFACTION OF THE OWNER. WHERE SERVICE IS INTERRUPTED, THE CONTRACTOR SHALL COOPERATE IN RESTORING SERVICE PROMPTLY. ALL CHARGES FOR DAMAGES DONE TO UTILITIES SHALL BE PAID BY THE CONTRACTOR.

E. CONSTRUCTION OF ROAD RIGHT-OF-WAY

CONSTRUCTION IN THE ROAD RIGHT-OF-WAY SHALL AT ALL TIMES BE PERFORMED WITH MINIMUM DISTURBANCE TO TRAFFIC WITH SUFFICIENT BARRICADES AND DIRECTION. DETOURS CAN BE INSTITUTED WITH APPROVAL OF THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE, OR STATE, COUNTY, OR LOCAL AUTHORITIES. PAVEMENT SHALL BE CUT PRIOR TO REMOVAL. HOLES AND SETTLEMENTS IN THE TRENCHES SHALL BE IMMEDIATELY FILLED TO THE ORIGINAL GRADE ELEVATION WITH THE SPECIFIED MATERIALS.

F. EXCAVATION AND PREPARATION OF TRENCH

THE CONTRACTOR SHALL PROCEED WITH CAUTION IN THE EXCAVATION AND PREPARATION OF THE TRENCH SO THAT THE EXACT LOCATION OF UNDERGROUND STRUCTURES, BOTH KNOWN AND UNKNOWN, MAY BE DETERMINED. THE TRENCH SHALL BE EXCAVATED SO THAT THE PIPE CAN BE LAID TO THE ALIGNMENT AND DEPTH REQUIRED. MINIMUM DEPTH OF COVER FROM SURFACE GRADE TO TOP OF PIPE BARREL SHALL BE FOUR FEET (4'). NO TRENCH SHALL BE EXCAVATED MORE THAN FIVE HUNDRED LINEAL FEET (500 LF) IN ADVANCE OF PIPE LAYING UNLESS AUTHORIZED BY THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE TRENCH SHALL BE SO BRACED AND DRAINED THAT THE WORKMEN MAY WORK THEREIN SAFELY AND EFFICIENTLY. IT IS ESSENTIAL THAT THE DISCHARGE OF THE TRENCH DEWATERING PUMPS BE CONDUCTED TO NATURAL DRAINAGE CHANNELS OR DRAINS, AS IN ACCORDANCE WITH SITE REQUIREMENTS.

THE WIDTH OF THE TRENCH SHALL BE OF ADEQUATE SIZE TO PERMIT THE PIPE TO BE LAID AND JOINTED PROPERLY, BUT SHALL NOT EXCEED THE SUM OF TWENTY-FOUR INCHES(24") PLUS THE PIPE OUTSIDE DIAMETER, AND THE BACKFILL TO BE PLACED AND COMPACTED AS SPECIFIED.

LEDGE ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A CLEARANCE OF AT LEAST SIX INCHES (6") BELOW AND ON EACH SIDE OF ALL PIPES AND FITTINGS.

THE TRENCH SHALL BE EXCAVATED TO THE DEPTH REQUIRED SO AS TO PROVIDE A UNIFORM AND CONTINUOUS BEARING AND SUPPORT FOR THE PIPE ON SOLID AND UNDISTURBED GROUND AT EVERY POINT. WHERE THE BOTTOM OF THE TRENCH AT A SUBGRADE IS FOUND TO BE UNSTABLE, AS TO INCLUDE ASHES, CINDERS, ALL TYPES OF REFUSE, VEGETABLE OR OTHER ORGANIC MATERIAL OR LARGE PICES OF FRAGMENTS OR INORGANIC MATERIAL WHICH IN THE JUDGEMENT OF THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE SHOULD BE REMOVED, THE CONTRACTOR SHALL EXCAVATE AND REMOVE SUCH UNSUITABLE MATERIAL TO THE WIDTH AND DEPTH ORDERED BY THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE.

ANY PART OF THE BOTTOM OF THE TRENCH EXCAVATED BELOW THE SPECIFIED GRADE SHALL BE CORRECTED WITH APPROVED BEDDING MATERIAL SUCH AS THOROUGHLY COMPACTED CRUSHED STONE, GRAVEL, OR CONCRETE AS DIRECTED BY THE VILLAGE ENGINEER, WATER SUPERINTENDENT, OR AUTHORIZED REPRESENTATIVE. THE FINISHED SUBGRADE SHALL BE PREPARED ACCURATELY BY MEANS OF HAND TOOLS.

GENERAL WATER MAIN NOTES:

1. ALL PROPOSED WATERMAIN MATERIALS, CONSTRUCTION AND INSTALLATION SHALL CONFORM TO ALL APPLICABLE RULES AND REGULATIONS OF CHAPTER 130 OF THE VILLAGE OF COLD SPRING WATER DEPARTMENT AND THE PUTNAM COUNTY HEALTH DEPARTMENT STANDARDS AND SPECIFICATIONS.
2. THE RECORDS OF THE VILLAGE OF COLD SPRING INDICATE THAT THERE IS ADEQUATE WATER PRESSURE AND CAPACITY AS REQUIRED TO SERVE THIS PROJECT.
3. ALL BACKFLOW PREVENTION DEVICES ASSOCIATED WITH THE FIRE AND DOMESTIC SERVICES FOR EACH SERVICE CONNECTION SHALL BE LOCATED INTERNAL TO THE BUILDING AND SHALL REQUIRE SEPARATE APPROVAL BY THE PUTNAM COUNTY DEPARTMENT OF HEALTH.
4. ALL FIRE AND DOMESTIC SERVICE CONNECTIONS FROM THE PROPOSED WATER MAIN SHALL BE INSTALLED WITH WET TAPS AFTER THE CONTRACTOR HAS INSTALLED THE MAIN AND IT HAS BEEN APPROVED BY THE VILLAGE OF COLD SPRING WATER DEPARTMENT AND THE PUTNAM COUNTY DEPARTMENT OF HEALTH. ALL SERVICE CONNECTIONS SHALL BE METERED.
5. THE CONTRACTOR IS ADVISED THAT BEFORE HE CONNECTS TO THE EXISTING WATER SYSTEM, HE MUST ADVISE AND COORDINATE HIS OPERATIONS WITH THE VILLAGE OF COLD SPRING WATER DEPARTMENT'S SUPERINTENDENT. MEANS AND METHODS USED TO CONNECT TO THE EXISTING SERVICE SHALL BE APPROVED BY THE VILLAGE AND SHALL INCLUDE BUT NOT BE LIMITED TO WET TAPS OR OTHERWISE.
6. THE CONTRACTOR IS TO MAINTAIN CONSTANT FLOW AND PRESSURE IN ALL WATER MAINS AT ALL TIMES. IF THE NEED SHOULD ARISE THAT WATER SERVICE IS TO BE INTERRUPTED FOR A SHORT PERIOD, IT MUST BE COORDINATED WITH AND APPROVED BY THE ENGINEER AND THE VILLAGE OF COLD SPRING SUPERINTENDENT OF WATER.
7. WATER MAINS CROSSING HOUSE SEWERS, STORM SEWERS OR SANITARY SEWERS SHALL BE LAID TO PROVIDE A VERTICAL SEPARATION OF A MINIMUM OF 18" BETWEEN THE BOTTOM OF WATER MAIN AND TOP OF SEWER.
8. WATER MAINS PASSING UNDER HOUSE SEWERS, IN ADDITION, SHALL BE PROTECTED BY PROVIDING A VERTICAL SEPARATION OF 18" MINIMUM FROM THE BOTTOM OF THE SEWER TO THE TOP OF THE WATER MAIN AND ADEQUATE STRUCTURAL SUPPORT FOR THE SEWER TO PREVENT EXCESSIVE DEFLECTION OF THE JOINTS AND THE SEWER SETTLING AND BREAKING THE WATER MAIN. IN ADDITION THE LENGTH OF WATER PIPE IS TO BE CENTERED AT THE POINT OF CROSSING SO THAT THE JOINTS WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER. NO WATER MAIN SHALL PASS THROUGH OR COME IN CONTACT WITH ANY PART OF A SEWER OR SEWER MANHOLE.
9. THE COVER OVER THE TOP OF THE WATER MAIN SHALL BE A MINIMUM OF 4 FEET TO A MAXIMUM OF 5.5 FT.
10. WATER MAINS SHALL BE CLASS 52 DUCTILE IRON PIPES (DIP) TYTON JOINT TYPE AND FITTINGS SHALL BE FACTORY CEMENT LINED CLASS 52. ALL FITTINGS SHALL HAVE MECHANICAL JOINTS AND SHALL BE PRESSURE RATED AT 250 PSI. ALL NECESSARY JOINT MATERIALS SHALL BE FURNISHED. WATER MAINS SHALL BE INSTALLED IN ACCORDANCE WITH AWWA STANDARDS, LATEST REVISION.
11. ALL GATE VALVES SHALL BE MUELLER RESILIENT WEDGE (TURN LEFT OPEN) TYPE AND SHALL MEET AWWA STANDARDS, LATEST REVISION.
12. ALL SERVICE CONNECTIONS AND SMALL DIAMETER EXTENSIONS SHALL CONFORM TO THE LATEST EDITION OF AWWA C-151.
13. IF PIPE BENDS EXCEED 4° PER PIPE JOINT FILLINGS SHALL BE USED INCLUDING RETAINER GLANDS AND CONCRETE THRUST BLOCKS OR RODS SHALL BE USED AT ALL LOCATIONS WHERE FITTINGS ARE NECESSARY.
14. INSTALLATION AND TESTING OF THE WATER MAIN SHALL BE INSPECTED BY THE VILLAGE OF COLD SPRING AND PUTNAM COUNTY DEPARTMENT OF HEALTH. THE CONTRACTOR SHALL PROVIDE THE HEALTH DEPARTMENT A MINIMUM 48 HOURS NOTICE PRIOR TO ANY PRESSURE/LEAKAGE TESTS AND/OR DISINFECTION AND BACTERIOLOGICAL TESTS PERFORMED ON THE PROPOSED WATER MAIN. THE RESULTS OF THE ABOVE TESTS MUST BE ACCEPTED BY THE PCDOH PRIOR TO USE OF THE MAIN.
15. ASBUILT DRAWINGS SHALL SHOW DIMENSIONS BETWEEN ALL VALVE TURNING NUTS AND FINISH GRADE.
16. INSTALLATION, DISINFECTION AND TESTING TO BE WITNESSED AND CERTIFIED BY A LICENSED PROFESSIONAL ENGINEER OR VILLAGE OF COLD SPRING ENGINEER AND THE PUTNAM COUNTY DEPARTMENT OF HEALTH.
17. ALL HYDRANTS AND VALVES SHALL BE AS MANUFACTURED BY THE MUELLER COMPANY.
18. THE FINAL LOCATIONS OF FIRE HYDRANTS AND SIAMESE CONNECTIONS SHALL BE DETERMINED BY AND COORDINATED WITH THE VILLAGE OF COLD SPRING FIRE DEPARTMENT.
19. IF, DURING CONSTRUCTION, IT IS FOUND THAT THE REQUIRED SEPARATION OF WATER MAINS, SANITARY SEWERS, STORM SEWERS, AND BUILDING SEWERS CANNOT BE MET, THE DEVELOPER OR HIS AUTHORIZED REPRESENTATIVE SHALL CONTACT THE PUTNAM COUNTY DEPARTMENT OF HEALTH. APPROVAL BY THE PCDOH IS REQUIRED PRIOR TO ANY FIELD CHANGES THAT WILL AFFECT MINIMUM WATER/SEWER SEPARATION DISTANCES.
20. ALL TYPES OF INSTALLED PIPE SHALL BE PRESSURE TESTED AND LEAKAGE TESTED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-600.
21. ALL NEW, CLEANED OR REPAIRED WATER MAINS SHALL BE DISINFECTED AND BACTERIOLOGICAL TESTING PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF AWWA STANDARD C-651-05 (EXCEPT FOR SECTION 4.4.2 WHICH IS NOT APPROVABLE). THE SPECIFICATIONS INCLUDE DETAILED PROCEDURES FOR THE ADEQUATE FLUSHING, DISINFECTION, AND MICRO- BIOLOGICAL TESTING OF ALL WATER MAINS.
22. ROAD OPENINGS SHALL BE DONE IN ACCORDANCE WITH CONDITIONS OF PERMIT, AND COORDINATED WITH THE VILLAGE OF COLD SPRING.

SANITARY SEWER NOTES:

1. ALL WORK TO BE DONE IN ACCORDANCE WITH THE CODE OF THE VILLAGE OF COLD SPRING AND THE REGULATIONS OF THE PUTNAM COUNTY DEPARTMENT OF HEALTH.
2. THERE ARE NO WATER SUPPLY WELLS WITHIN 25 FT OF THE PROPOSED SANITARY SEWER.
3. SANITARY SEWERS ARE TO BE OF 8" RING-TIGHT PVC PLASTIC PIPE ASTM CLASS SDR-35 (OR HEAVIER IF REQUIRED BY THE VILLAGE CONSULTING ENGINEER DUE TO LOADING CONDITIONS). ALL PIPE TO BE MANUFACTURED BY JOHN MANSVILLE OR EQUAL.
4. SANITARY MANHOLES/CLEANOUT MANHOLES SHALL BE PRECAST CONCRETE. ALL WORK SHALL BE MANUFACTURED IN ACCORDANCE WITH APPROVED STANDARDS AND SHALL BE SPACED A MAXIMUM DISTANCE OF 300' ON STRAIGHT RUNS AND INSTALLED AT EVERY CHANGE IN ALIGNMENT. MANHOLE POSITIONING SHALL BE AS TO PREVENT THE ENTRANCE OF SURFACE WATER DURING STORMS. MANHOLE RIMS ARE TO BE WATER TIGHT IN AREAS SUBJECT TO POSSIBLE FLOODING CONDITIONS.
5. ALL BUILDING LATERALS TO BE INSTALLED BY PLUMBERS, LICENSED IN THE VILLAGE OF COLD SPRING ACCORDING TO THE REQUIREMENTS OF THE VILLAGE OF COLD SPRING.
6. A 6" MINIMUM BEDDING OF 3/4" CRUSHED STONE IS TO BE PLACED UNDER ALL SEWER LINES AND ALONG THE SIDES UP TO THE TOP TO PROVIDE FIRM SUPPORT.
7. SANITARY SEWER CONSTRUCTION SHALL MEET ALL SEWER CONSTRUCTION SPECIFICATIONS FOR THE VILLAGE OF COLD SPRING.
8. THE VILLAGE ENGINEER SHALL BE NOTIFIED 48 HOURS PRIOR TO THE START OF ANY WORK.
9. THE SANITARY SEWER MAIN SHALL BE LAID AT A MINIMUM SLOPE OF 0.5%.
10. ALL SEWERS SHALL BE LAID AT LEAST 10 FT HORIZONTALLY FROM ANY EXISTING OR PROPOSED WATER MAIN. THE DISTANCE SHALL BE MEASURED EDGE TO EDGE. IN CASES WHERE IT IS IMPRACTICAL TO MAINTAIN A 10 FOOT SEPARATION, THE PUTNAM COUNTY DEPARTMENT OF HEALTH MAY ALLOW DEVIATION ON A CASE-BY-CASE BASIS, IF SUPPORTED BY DATA FROM THE DESIGN ENGINEER.
11. HEAVY-DUTY WHITE FITTINGS AS MANUFACTURED BY GPK PRODUCTS, INC. OR APPROVED EQUAL, SHALL BE USED FOR THE CONSTRUCTION OF THE PVC SEWER SYSTEM.
12. MANHOLE STEPS SHALL BE CAST IRON NEENAH NO. R-1981-0 OR CAMPBELL FOUNDRY NO. 2588-1 OR POLYPROPYLENE COATED STEEL (SEE SPECIFICATIONS) OR APPROVED EQUAL.
13. UNLESS OTHERWISE SPECIFIED, SANITARY SEWER MANHOLES SHALL HAVE THE LETTERS "SEWER" CAST ON THE COVER.
14. MANHOLE COVERS AND STRUCTURES SHALL MEET OR EXCEED A.S.T.M. AND O.S.H.A. REQUIREMENTS AND MUST BE RATED FOR H-20 VEHICLE LOADING. MANHOLES MUST BE MIN. 48" DIAMETER.
15. ALL SANITARY STRUCTURES SHALL RECEIVE 2 MIL COATS OF BITUMINOUS MATERIAL "INERTOL NO. 49" KOPPERS SUPPER SERVICE BLACK OR APPROVED EQUAL, APPLIED IN ACCORDANCE WITH MANUFACTURE'S SPECIFICATIONS.
16. JOINING JOINTS TO CONFORM TO A.S.T.M. DESIGNATION C-443 LATEST REVISION. JOINTS TO BE MORTARED INSIDE AND OUT USING NON-SHRINKING MORTAR.
17. PRE-CAST MANHOLE SECTIONS TO BE IN ACCORDANCE WITH "PRE-CAST REINFORCED CONCRETE MANHOLE SECTIONS" A.S.T.M. DESIGNATION C-478, LATEST REVISION, MINIMUM COMPRESSIVE STRENGTH TO BE 4000 P.S.I.
18. WHERE SEWER MAIN IS TO BE INSTALLED 10' DEEP OR GREATER, PVC SDR-26 SHALL BE USED.
19. WHEN SEWER IS TO BE INSTALLED IN FILL MATERIAL, THE SUPPORTING FILL IS TO BE COMPACTED TO MINIMUM STANDARD PROCTOR DENSITY OF 95%, AND SHALL BE CERTIFIED TO THE VILLAGE.
20. WATER MAINS CROSSING HOUSE SEWERS, STORM

GENERAL EROSION CONTROL NOTES:

1. Contractor shall be responsible for compliance with all sediment and erosion control practices. The sediment and erosion control practices are to be installed prior to any major soil disturbances, and maintained until permanent protection is established. Road surface flows from the site should be dissipated with tracking pad or appropriate measures during adjacent road shoulder regrading. Contractor is responsible for the installation and maintenance of all soil erosion and sedimentation control devices throughout the course of construction. During construction the E&SC Monitor retained by the owner will provide inspections as per the requirements of the NYS DEC GP-0-10-00. The monitor will provide guidance to the Contractor where additional E&SC practices may need to be added or repairs/replacement of in-place practices are required. The Contractor shall adhere to and implement these suggested improvements.
2. Prior to commencement of work, an on-site pre-construction meeting will be held. This will be attended by the Project Owner, the Operator responsible for complying with the approved construction drawings including the E&SC Plan and Details, the Design Engineer, the Engineer or SWPPP Monitoring Professional responsible for E&SC monitoring during construction, Village representatives from the Engineering Consultant and Code Enforcement.
3. Catch basin inlet protection must be installed and operating at all times until tributary areas have been stabilized. When possible flows should be stabilized before reaching inlet protection structure. Timely maintenance of sediment control structures is the responsibility of the Contractor.
4. All structures shall be maintained in good working order at all times. The sediment level in all sediment traps shall be closely monitored and sediment removed promptly when maximum levels are reached or as ordered by the Engineer or SWPPP Monitoring. All sediment control structures shall be inspected on a regular basis, and after each heavy rain to insure proper operation as designed. An inspection schedule shall be set forth prior to the start of construction.
5. The locations and the installation times of the sediment capturing standards shall be as specified in these plans, as ordered by the Engineer or SWPPP Monitoring, and in accordance with the latest edition of the "New York Standards and Specifications for Erosion and Sediment Control" (NYSSESC).
6. All topsoil shall be placed in a stabilized stockpile for reuse on the site. All stockpile material required for final grading and stored on site shall be temporarily seeded and mulched within 7 days. Refer to soil stockpile details.
7. Any disturbed areas that will be left exposed more than 7 days and not subject to construction traffic, shall immediately receive temporary seeding. Mulch shall be used if the season prevents the establishment of a temporary cover. Disturbed areas shall not be limed and fertilized prior to temporary seeding.
8. All disturbed areas within 500 feet of an inhabited dwelling shall be wetted as necessary to provide dust control.
9. The contractor shall keep the roadways within the project clear of soil and debris and is responsible for any street cleaning necessary during the course of the project.
10. All sediment and erosion control measures shall be installed in accordance with current edition of NYSSESC.
11. All regraded areas must be stabilized appropriately prior to any rock blasting, cutting, and/or filling of soils. Special care should be taken during construction to insure stability during maintenance and integrity of control structures.
12. Any slopes graded at 3:1 or greater shall be stabilized with erosion blankets to be staked into place in accordance with the manufactures requirements. Erosion blankets may also be required at the discretion of Village officials, Engineer or SWPPP Monitoring. When stabilized blanket is utilized for channel stabilization, place all of the volume of seed mix prior to laying net, or as recommended by the manufacturer.
13. To prevent heavy construction equipment and trucks from tracking soil off-site, construct a pervious crushed stone pad. Locate and construct pads as detailed in these plans.
14. Contractor is responsible for controlling dust by sprinkling exposed soil areas periodically with water as required. Contractor to supply all equipment and water.
15. Contractor shall be responsible for construction inspections as per NYSDEC GP-0-10-001 and Village of Cold Spring Code.
16. Temporary Erosion and Sediment Control practices will remain in place until such time that the disturbed area for which such practice has achieved final stabilization. The Erosion and Sediment Control practices may not be removed until so depicted by the SWPPP Monitoring Professional or Village Representative.

CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-10-001, dated January 28, 2010, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor: _____

Name and Title (please print): _____

Signature of Contractor: _____

Company / Contracting Firm: _____

Name of Company: _____

Address of Company: _____

Telephone Number / Cell Number: _____

Site Information: _____

Address of Site: _____

_____

Today's Date: _____

OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): _____

Title: _____

Date: _____

Address: _____

Phone: _____

E-mail: _____

Signature: _____

MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES:

N.Y.S.D.E.C. GP-0-10-001 EXPOSURE RESTRICTIONS - States that any exposed earthwork shall be stabilized in accordance with the guidelines of this plan.

1. Trees and vegetation shall be protected at all times as shown on the detail drawing and as directed by the Engineer.
2. Care should be taken so as not to channel concentrated runoff through the areas of construction activity on the site.
3. Fill and site disturbances should not be created which causes water to pond off site or on adjacent properties.
4. Runoff from land disturbances shall not be discharged or have the potential to discharge off site without first being intercepted by a control structure, such as a sediment trap or silt fence. Sediment shall be removed before exceeding 50% of the retention structure's capacity.
5. For finished grading, adequate grade shall be provided so that water will not pond on lawns for more than 24 hours after rainfall, except in swale flow areas which may drain for as long as 48 hours after rainfall.
6. All swales and other areas of concentrated flow shall be properly stabilized with temporary control measures to prevent erosion and sediment travel. Surface flows over cut and fill areas shall be stabilized at all times.
7. All sites shall be stabilized with erosion control materials within 7 days of final grading.
8. Temporary sediment trapping devices shall be removed from the site within 30 days of final stabilization.

MAINTENANCE SCHEDULE:

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE	– – –	– – –	INSP.	INSP.	CLEAN/ REPLACE	REMOVE
STABILIZED CONST. ENTRANCE	CLEAN	– – –	– – –	– – –	REPLACE	REMOVE
INLET PROTECTION	– – –	INSP.	INSP.	CLEAN	REPLACE	REMOVE

MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:

The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:

Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events.

DEBRIS AND LITTER REMOVAL:

Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation.

STRUCTURAL REPAIR/REPLACEMENT:

Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

EROSION CONTROL:

Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures.

SEDIMENT REMOVAL:

Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor.

TOPSOIL:

Existing topsoil will be removed and stored in piles sufficiently as to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYSDOT):

1. The pH of the material shall be 5.5 to 7.6.
2. The organic content shall not be less than 2% or more than 70%.
3. Gradation:

SIEVE SIZE	% PASSING BY WGT.
2 INCH	100
1 INCH	85 TO 100
1/4 INCH	65 TO 100
NO. 200 MESH	20 TO 80

PERMANENT VEGETATIVE COVER:

1. Site preparation:
   - 1.1. Install erosion control measures.
   - 1.2. Scarify compacted soil areas.
   - 1.3. Lime as required to ph 6.5.
   - 1.4. Fertilize with 10-6-4 4 lbs/1,000 S.F.
   - 1.5. Incorporate amendments into soil with disc harrow.
2. Seed mixtures for use on swales and cut and fill areas.

MIXTURE		LBS./ACRE
ALT. A	KENTUCKY BLUE GRASS	20
	CREEPING RED FESCUE	28
	RYE GRASS OR REDTOP	5
ALT. B	CREEPING RED FESCUE	20
	REDTOP	2
	TALL FESCUE/SMOOTH BLOOMGRASS	20

3. SEEDING
   - 3.1. Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.
   - 3.2. Apply soil amendments and integrate into soil. Soil shall be scarified and de-compacted.
   - 3.3. Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated.
   - 3.4. Stabilize seeded areas in drainage swales.
   - 3.5. Irrigate to fully saturate soil layer, but not to dislodge planting soil.
   - 3.6. Seed between April 1st and May 15th or August 15th and October 15th.
   - 3.7. Seeding may occur May 15th and August 15th if adequate irrigation is provided.

TEMPORARY VEGETATIVE COVER:

SITE PREPARATION:

1. Install erosion control measures.
2. Scarify areas of compacted soil.
3. Fertilize with 10-10-10 at 400/acre.
4. Lime as required to ph 6.5.

SEED SPECIES:

MIXTURE	LBS./ACRE
Rapidly germinating annual ryegrass (or approved equal)	20
Perennial ryegrass	20
Cereal oats	36

SEEDING:
Same as permanent vegetative cover

CONSTRUCTION SEQUENCE:

Recommended Sequence of Construction

Use of erosion and sediment control structures and practices are important for maintaining site stability under runoff and during daily construction activities. The Construction Sequence should be staged with erosion and sediment controls, as follows, with all controls in place and implemented prior to respective infrastructure construction. As construction proceeds, the controls should be monitored, maintained and replaced as needed. Additional controls may be required as needed to address unforeseen situations.

Refer to The Construction Drawings for all plans and details which relate to the Construction Sequence. This Sequence should be followed in conjunction with all Plans, Notes, and the Stormwater Pollution Prevention Plan. Prior to the commencement of work, the Owner and General Contractor shall read and understand the Sequence for Construction. The Sequence shall be discussed at the time of the Pre-construction Meeting.

During construction of the project, the Contractor is responsible to coordinate all required inspections with various agencies and the Project Engineer.

Construction Sequence

General Sequence: The general sequence applies to the start of all Phases of the project. The requirements in such shall be applied as appropriate in that phase and shall be assumed in place prior to the start of the work outlined in the sequence for each Phase. The phases are delineated on the E&SC Plan.

1. Prior to the beginning of any site work the major features of the construction must be field staked by a licensed surveyor. These include the building, limits of disturbance, utility lines, and Stormwater practices.
2. Cut and clear trees within the phase limits as necessary for the areas to be disturbed. Install tree protective measure at marked locations on E&SC Plan.
3. Install all temporary erosion control measures as shown on the Erosion and Sediment Control Plan for the project's immediate disturbance areas. This shall include, but not limited to silt fence, stabilized construction entrances, diversion swales, sediment traps, construction fence, etc. This sequence must be followed to insure proper implementation of the Erosion and Sediment Control Plan (E&SC) and Stormwater Pollution Prevention Plan (SWPPP).
4. Prior to commencement of work, an on-site pre-construction meeting will be held. This will be attended by the Project Owner, the Operator responsible for complying with the approved construction drawings including the E&SC Plan and Details, the Design Engineer, the Engineer responsible for E&SC monitoring during construction, Village representatives from the Engineering Consultant and Code Enforcement.
5. Timbered trees and woodchips shall be temporarily stored in the stockpile and or staging area if necessary before being removed off-site. Woodchips may be used for mulch to stabilize disturbed areas. Woodchip mulch shall be applied at a minimum rate of 500 lbs. per 1000 SF (2" thick minimum).
6. Remove existing vegetative cover, cut and clear trees, grub, remove stumps and other surface features in the limit of construction only. Any disturbance that results from tree clearing and grubbing shall be immediately stabilized with woodchips mulch, hydro-mulch, or straw and seed. Timbered trees, wood chips, and stumps shall be removed off-site unless otherwise directed. As stated woodchips may be stockpiled for use as stabilizing ground cover. Demolish and/or remove existing features, i.e.: fence, concrete slab, asphalt etc., and dispose of or stockpile as required by the Owner. All construction debris shall be properly disposed of in accordance with all Federal, State, and Local requirements.

Standard Sequence Notes for All Phases

7. When grading the roadways, parking, and building pads for the Buildings begin moving the fill towards the location designated for each phase. Cut and fill of a certain phase shall meet the next phase boundary at a maximum slope of 2V:1H. For previous phases where grading is complete match to finish grade elevations. All compaction requirements shall be met within the fill sections. (This work shall include the commencement of the retaining walls around the proposed building construction.) Upon completion of the grading, temporary seed or hydro-mulch any embankments and install erosion control blankets where shown on the erosion and sediment control plan. During building and site construction, maintain and re-establish as required, erosion control and stabilization measures as required by the Site Plan and Details. Areas which are to remain undisturbed for more than 7 days shall be stabilized with temporary seeding or mulch.
8. A licensed surveyor must define the building, roadway, and parking locations. In addition the surveyor shall locate the utilities and stormwater management system.
9. Install or check condition of all temporary Erosion Control Measures as shown on the Erosion and Sediment Control Plan.
10. Begin preparation of the building site and excavation of the building foundation as well as construction of all retaining walls. Areas in which final grade is achieved shall be immediately stabilized with permanent vegetative cover. Permanent slopes of 3:1 or greater shall receive erosion blankets.
11. Begin construction of the foundation. Upon completion and after proper curing time is achieved, backfill the foundation and bring site to rough grade. Areas which are to remain undisturbed for more than 7 days shall be stabilized with temporary seeding or mulch.
12. Upon completion of each Phase the Contractor shall be required to stabilize disturbed soils in the event the disturbed area will remain not worked for greater than seven (7) days, at the direction of the Engineer of Record or permitting entity Inspector, and when significant precipitation is in the immediate forecast. All disturbed areas shall be temporarily stabilized with hydro-mulch or where appropriate woodchip. It is recommended that any grading that is at the finish stage will receive no further disturbance and that permanent stabilization such as topsoil, seed, mulching or blankets as per the Plan be installed. **The next phase cannot commence until these steps have been completed.**

The following phases are the general order for construction of the project and may be modified after approved by the supervising Engineer. The phasing is meant to minimize the amount of open disturbance. Under no circumstances shall multiple phases amounting to five (5) acres or greater be disturbed during the same period of time. In the event greater disturbance is necessary outside of the Phase lines shown on the Erosion and Sediment Control Plan, the Contractor shall coordinate with the Engineer of Record, and Municipality for an on-site meeting to discuss the alternative approach to the construction.

Protection of Beech Tree
Prior to any disturbance on the site, all protective measures for the 54" Beech tree shall be installed. No heavy equipment, excavation, or other work shall be performed in the protection zone that will in any damage the tree or root system. Any work to be done within this zone will follow the procedure outline in the Savatree tree assessment and protection plan located on sheet G-1. The contractor will be held solely responsible for any action which will result in damage to the tree.

Demolition and Site Preparation - The intent of this phase is to demolish and completely remove existing buildings, parking, utilities and other infrastructure and prepare the site for the new construction.

1. Once all erosion controls are in place begin demolition of the existing building and site infrastructure in preparation for new construction. All demolition debris shall be hauled off site and disposed of in accordance with all federal, state and local requirements.
2. The Surveyor shall stake-out the proposed access roads centerline, and buildings to be constructed as per the current phase.
3. Create access points by installing the stabilized construction entrances at the locations shown on the E&SC Plan as well as the staging area for the project trailer, employee vehicle parking, and construction vehicles and equipment as required. Establish areas to stockpile soil, materials, dumpsters and trees. The site safety fence, gate, and site signage shall be installed.

Construction of Buildings, Drives and Parking, Utility Infrastructure - The intent of this phase is to complete the construction of Buildings, the access driveway and parking for the site, and the landscape and hardscape included in the phase limits shown on the Erosion and Sediment Control Plan.

1. Implement the General Sequence notes 1 through 6 prior to continuing this phase.
2. Strip topsoil within the Phase I boundary and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped area topsoil. Contractor shall take every precaution feasible to reduce the amount of disturbed/exposed soils during construction.
3. Construct and install the temporary sediment traps in the locations as deemed necessary by the monitoring engineer. Install the temporary filtered outlet. Any disturbance that will not be further disturbed within 7 days shall be immediately stabilized with woodchips, hydro-mulch, or straw and seed.
4. Begin establishing the site grades for the roadways, parking, and buildings based on survey stakeout.
5. Once rough grades have been established the surveyor shall stakeout the underground utilities. Begin installing the sanitary sewer and sanitary sewer service to the proximity of the buildings connection point. Upon completion move to the watermain. Backfill as installation is complete and stabilize the area. If trenches are to be left open, place excavated material on the up-slope sides of the trench and protect and stabilize if it is to remain open for an extended period of 7 days or more. Where grading is final permanently seed or hydro-mulch the area.
6. Watermain are tested and deemed acceptable, install the water service to within proximity of the proposed building locations.
7. Begin excavation for the building being built in the initial phase. This can be done simultaneously to step 5. **Refer to Notes 7 through 11 under the General Sequence.**
8. Stake-out and begin installation of Rainwater Harvesting, Pre-treatment, subsurface infiltration and detention chambers, and associated structures and piping within in the locations shown on the plan.
9. When the subsurface units are installed the upstream drainage structures shall be blocked so as to not allow sediment laden water from reaching the subsurface chambers.
10. Backfill as installation is complete and stabilize the area. If trenches are to be left open, place excavated material on the up-slope sides of the trench and protect and stabilize if it is to remain open for an extended period of 7 days or more.
11. Upon completion of the subsurface chambers, begin installation of proposed bypass structure, outlet structure. Install storm sewer piping, catch basins and manholes, working downstream to upstream. During the installation of catch basins, install inlet protection and water bar as per E&SC Plan to assure that sediment laden water will not enter the storm system. Once the final grade above the system is achieved place final topsoil cover, begin placement of seed mix and erosion control blanket, or hydro-mulch. Refer to the landscape plan for the seed mix requirements.
    Note: No stormwater is permitted to enter the infiltration system from the upstream conveyance system and shall be blocked until the completion and stabilization of all phases tributary to the basin. An area shall be considered to have achieved final stabilization when it has a minimum uniform 80% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements.
12. Complete construction of the building, and remaining retaining walls within phase limits. Utilities must be lain and completed before the construction of retaining walls.
13. Stake-out the location of all other underground utilities and utility structures within this phase. Begin excavation and install said utilities.
14. During the Final Phase of building construction, finish grade, topsoil, rake, and seed all areas as required. Where required or recommended, hydro-mulch or install erosion control blankets.
15. Install final vegetation including sod and landscaping. Refer to Landscape Plans for location and identification of ground cover and plantings. Clear site of debris and all unwanted materials. Disposal shall be in accordance with all Federal, State, and Local requirements.

Continuation of Building - The intent of this phase is to complete the construction of the Buildings not completed in the initial phase, and the associated landscape and hardscape included in the particular phase. Additionally, all utility connections.

1. The Surveyor shall stake-out the proposed building.
2. Implement the General Sequence notes 1 through 6 prior to continuing this phase.
3. Strip topsoil within the Phase I boundary and place excavated topsoil within the identified stockpile locations. Any soils so deemed by the Design or Monitoring Engineer shall be stockpiled for future use as landscaped area topsoil. Contractor shall take every precaution feasible to reduce the amount of disturbed/exposed soils during construction.
4. Begin excavation for the building foundation for the Building and adjacent areas. **Refer to Notes 7 through 11 under the General Sequence.**
5. Complete construction of the building, and remaining retaining walls within phase limits. Utilities must be lain and completed before the construction of retaining walls.
6. Upon completion of this Phase the Contractor shall be required to stabilize disturbed soils in the event the disturbed area will remain not worked for greater than seven (7) days, at the direction of the Engineer of Record or permitting entity Inspector, and when significant precipitation is in the immediate forecast. All disturbed areas shall be temporarily stabilized with hydro-mulch or where appropriate woodchip. It is recommended that any grading that is at the finish stage will receive no further disturbance and that permanent stabilization such as topsoil, seed, mulching or blankets as per the Plan be installed.
7. Install all utility connections.
8. During the Final Phase of building construction, finish grade, topsoil, rake, and seed all areas as required. Where required or recommended, hydro-mulch or install erosion control blankets.
9. Install final vegetation including sod and landscaping. Refer to Landscape Plans for location and identification of ground cover and plantings. Clear site of debris and all unwanted materials. Disposal shall be in accordance with all Federal, State, and Local requirements.

Roadway and Parking Area Completion:

10. Stake out and install curbing as per Plan. Once curbing is completed. around catch basins, re-install inlet protection within catch basins. As curbing is complete, backfill with topsoil. Areas that are filled with topsoil are to be raked, seeded, and hay mulched.
11. Upon completion of the majority of the project infrastructure, install pavement binder course to the thickness and elevation as per the Construction Plans.

Final Site Stabilization and Completion of New Construction:

12. Upon completion of all Phases, the site shall be inspected by the SWPPP Monitoring Engineer and/or Village Inspector to determine completion of all work and permanent stabilization of the site. As each phase is at the completion stage install final asphalt surface.
13. Any areas deemed incomplete or not properly stabilized shall be done so to the satisfaction to the SWPPP Monitoring Engineer and Village Inspector.
14. Temporary Erosion and Sediment Control practices will remain in place until such time that the disturbed area for which such practice has achieved final stabilization. The Erosion and Sediment Control practices may not be removed until so directed by the SWPPP Monitoring Professional or Village Representative. The area where the sediment trap was located shall be filled, top soiled, seeded and mulched in accordance with the specifications within this plan.

Contact information during and after construction:

Paul Guillaro
Unicorn Contracting Corp.
3102 Rte 9 Suite 2A
Cold Spring, NY 10516
845-809-5969
15.

OFFICE COPY

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

PROJECT # 14-25

STATE OF NEW YORK — JOSEPH CARLO RITNA — LICENSED PROFESSIONAL ENGINEER — NO. 64431

Engineer: Joseph C. Ritna, P.E.
NYS Lic. No. 64431

Revisions:

No.	Date	Comments
1	12-2-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	3-11-15	Revised E&SC Notes
5	5-13-15	Revisions per comments from NYSDOT
6	3-23-15	Revisions per comments from B&L
7	4-22-15	Revisions per comments from PCDOH
8	4-22-15	Revisions per comments from 4-21-15 meeting

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

E&SC NOTES

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

Sheet G-2

C:\USERS\JLISTER\DROPBOX\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\C2-14-25 BUTTERFIELD REDEVELOPMENT 14-25 DETAILS UPDATED.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



NOTE:
1. REFER TO SUBDIVISION PLAT FOR METES AND BOUNDS OF PUBLIC AND PRIVATE UTILITY EASEMENTS.
2. THE OWNER OF LOT 4 SHALL OWN AND MAINTAIN ALL SANITARY SEWER AND WATER MAINS. A GENERAL ACCESS EASEMENT OVER THE SITE ROADS AND PARKING IS GRANTED TO THE VILLAGE SHOULD THE VILLAGE EVER NEED TO GAIN ACCESS TO THE SEWER AND WATER LINES.

NOTE:
1. *THIS IS NOT A SURVEY*, ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

OFFICE COPY

0 15 30 60
SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
NY Industrial Code Rule 753 requires no less than two days notice, but not more than ten days notice.
www.digsafelynewyork.com

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer:
Joseph C. Riina, P.E.
NYS Lic. No. 64451

Revisions:

No.	Date	Comments
1	12-5-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-24-15	Revisions per Applicant
5	3-13-15	Revisions per NYSDOT
6	3-23-15	Revisions per comments from B&L
7	4-22-15	Revisions per comments from PCDOH
8	4-23-15	Revisions per comments from ACOE meeting
9	6-9-15	Revisions per comments from NYSDOT

SCALE: 1" = 30'
DRAWN BY: EL
DATE: 10/22/14

EASEMENT PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

E-1

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\EL\STEREOSCTONEW\PROJECTS\25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\10-14-25 BUTTERFIELD REDEVELOPMENT\10-14-25 SITE PLAN REVISIONS.DWG



LOCATION MAP
NOT TO SCALE

SITE DATA:

OWNER / DEVELOPER:	BUTTERFIELD REALTY LLC 3102 ROUTE 9D COLD SPRING, NY 10516
PROJECT LOCATION:	1756 PAULDING AVENUE COLD SPRING, NEW YORK, 10516
EXISTING ZONE:	B-4A, MEDICAL AND HEALTH CARE FACILITY MIXED USED R-1, ONE FAMILY RESIDENCE DISTRICT
TOWN TAX MAP DATA:	SECTION 49.5, BLOCK 3, LOT 45
SITE AREA :	5.797 ACRES (252,517.32SF)
SEWAGE FACILITIES:	PUBLIC SEWERS
WATER FACILITIES:	PUBLIC WATER FACILITIES

PROJECT SUMMARY:

1. BUILDING 1, ***MUNICIPAL OFFICE BUILDING*** - 6,000 SF FOOTPRINT, WITH 15,000 SF TOTAL (FIRST FLOOR RETAIL NOT TO EXCEED 6,000SF)
2. BUILDING 2, ***RETAIL OFFICE BUILDING*** - 6,000 SF FOOTPRINT, WITH 16,000 SF TOTAL (FIRST FLOOR RETAIL NOT TO EXCEED 6,000SF)
3. BUILDINGS 3 - 6, ***SENIOR CONDOMINIUM*** - 55 UNITS \
4. LOTS 1,2, & 3 - THREE (3) SINGLE FAMILY HOMES

ZONING SCHEDULE: LOTS 1,2, &3

ZONING DISTRICT:	R-1, SINGLE FAMILY RESIDENTIAL				
DIMENSIONAL REGULATIONS:	REQUIRED	LOT 1 PROVIDED	LOT 2 PROVIDED	LOT 3 PROVIDED	VARIANCE REQUIRED
MINIMUM SIZE OF LOT:					
MINIMUM LOT AREA:	7,600 SF.	7,600 SF.	7,600 SF.	7,600 SF.	NONE
MINIMUM LOT WIDTH:	75 FT.	80 FT.	80 FT.	80 FT.	NONE
MINIMUM LOT DEPTH:	75 FT.	95 FT.	95 FT.	95 FT.	NONE
MINIMUM YARD DIMENSIONS:					
PRINCIPAL BUILDING:					
FRONT YARD SETBACK:	25 FT.	25+ FT.	25+ FT.	25+ FT.	NONE
REAR YARD SETBACK:	20 FT.	20+ FT.	20+ FT.	20+ FT.	NONE
ONE SIDE YARD SETBACK:	10 FT.	10+ FT.	10+ FT.	10+ FT.	NONE
COMBINED SIDE YARD SETBACK:	NONE	NONE	NONE	NONE	NONE
MAXIMUM % OF LOT TO BE OCCUPIED:					
PRINCIPAL BUILDING COVERAGE:	30% OF LOT AREA	26.6 % OF LOT AREA	26.6 % OF LOT AREA	26.6 % OF LOT AREA	NONE
MAXIMUM HEIGHT:					
PRINCIPAL BUILDING - FEET:	35 FEET	35FT MAX	35 FT MAX	35 FT MAX	NONE
PRINCIPAL BUILDING - STORIES:	2 1/2	2 1/2 MAX	2 1/2 MAX	2 1/2 MAX	NONE

ZONING SCHEDULE: MIXED USE LOT 4

ZONING DISTRICT:	B-4A DISTRICT, MEDICAL AND HEALTH CARE FACILITY MIXED USE		
DIMENSIONAL REGULATIONS:	REQUIRED	MIXED USE PROVIDED	VARIANCE REQUIRED
MINIMUM SIZE OF LOT:			
MINIMUM LOT AREA:	120,000 SF.	225,434 SF.	NONE
MINIMUM LOT WIDTH:	200 FT.	560 FT.	NONE
MINIMUM LOT DEPTH:	200 FT.	355 FT.	NONE
MINIMUM YARD DIMENSIONS:			
PRINCIPAL BUILDING:			
FRONT YARD SETBACK*	0 FT.	5 FT.	NONE
REAR YARD SETBACK:	10 FT.	29 FT.	NONE
ONE SIDE YARD SETBACK:	10 FT.	10+ FT.	NONE
COMBINED SIDE YARD SETBACK:	25 FT.	< 25 FT.	NONE
MAXIMUM % OF LOT TO BE OCCUPIED:			
PRINCIPAL BUILDING COVERAGE:	25% OF LOT AREA	23.4% OF LOT AREA	NONE
OPEN SPACE:	15 %	47 %	
MAXIMUM HEIGHT:			
PRINCIPAL BUILDING - FEET:	35 FEET	35 FT MAX	NONE
PRINCIPAL BUILDING - STORIES:	2 1/2	2 1/2 MAX	NONE

* FRONTAGE ON NYS HIGHWAY

Butterfield Parking Schedule

Building	Land Use	Parking Code Standard	Code Required Parking Spaces	Required parking spaces w/ full 20% reduction waiver applied	Conforming parking spaces provided	Total spaces provided, including non-confroming* * spaces
1	Retail (6,000 SF) -Ground Floor	1 Space per 150 SF	40	32	55	63
	Office (9,000 SF) -Upper 2nd and 3rd floor levels	1 Space per 300 SF	30	24		
2	Retail (6,000 SF) -Ground Floor	1 Space per 150 SF	40	32	59	67
	Office (10,000 SF) -Upper 2nd and 3rd floor levels	1 Space per 300 SF	33	27		
Lahey Pavilion	Existing	—	35	35*	35	35
3 - (25 units)	Senior Housing	1 space per unit	25	20	25	25
4,5, & 6 -(30 units)	Senior Housing	1 space per unit	30	24	33	38
Total Parking			**233**	**194**	**207 Represents a 11.2% reduction waiver applied**	**228**

* No parking reduction waiver taken for Lahey Pavillion.

** Non-conforming spaces consist of 5 Perpendicular Spaces @ 9' x 16' and 16 paralell spaces @ 7' x 21'

There is a total of 6 parking spaces provided for the 3 separate single-family homes (2 per lot), which is in full compliance with the code. These spaces are not included in the total count above.

LEGEND

- PROPERTY LINE / RIGHT OF WAY
- PROPOSED ROAD CENTERLINE
- PROPOSED CURB
- CONSERVATION EASEMENT LINE
- PROPOSED LIGHT POST
- PROPOSED TRAFFIC SIGN
- PROPOSED HANDICAP PARKING
- ADA ACCESSIBLE RAMP
- ADA ACCESSBILE ROUTES
- DIRECTIONAL ARROW



NOTE:
1. ***THIS IS NOT A SURVEY.*** ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

SAFE DIG
Before You Dig, Drill or Blast!
DIAL US TOLL FREE, 811 or 1-800-962-7962
NY Industrial Code Rule 753 requires no less than two (2) but not more than ten (10) business days notice.
www.digsafelynewyork.com

C:\USERS\EL\DESKTOP\NEW FOLDER\1756 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\D-14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REVS.DWG

PROJECT # 14-25

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

COPYRIGHT © 2010 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer:
STATE OF NEW YORK JOSEPH C. RITINA LICENSED PROFESSIONAL ENGINEER
Joseph C. Ritina, P.E.
NYS Lic. No. 64431

Revisions:

No.	Date	Comments
1	12-3-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	3-10-15	Revisions per comments from B&L
5	3-13-15	Revisions per comments from B&L
6	3-23-15	Revisions per comments from PCTOH
7	4-22-15	Revisions per comments from NYSDOT
8	5-20-15	Revisions per comments from Planning Board meeting
9	6-9-15	Revisions per comments from NYSDOT

SCALE: 1"= 30'
DRAWN BY: EL
DATE: 10/22/14

SITE /SUBDIVISION PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

C - 101

LEGEND

- EXISTING GRADING
- EXISTING SPOT GRADE
- PROPERTY LINE / RIGHT OF WAY
- EXISTING TREE TO BE PROTECTED
- EXISTING TREE TO BE REMOVED
- EXISTING TO BE REMOVED

EXISTING TREE TO BE REMOVED (TYP.)

EXISTING PAVEMENT AREA TO BE DEMOLISHED

TREE PROTECTION ZONE (TPZ)
EXISTING 54" Ø BEECH TREE TO BE PROTECTED DURING REMOVAL OF ASPHALT. EXTREME CARE SHALL BE TAKEN WHERE ASPHALT IS WITHIN IN DRIP LINE.PRIOR TO ANY DISTURBANCE ON THE SITE, ALL PROTECTIVE MEASURES FOR THE 54" BEECH TREE SHALL BE INSTALLED. NO HEAVY EQUIPMENT, EXCAVATION, OR OTHER WORK SHALL BE PERFORMED IN THE PROTECTION ZONE THAT WILL IN ANYWAY DAMAGE THE TREE OR ROOT SYSTEM. ANY WORK TO BE DONE WITHIN THIS ZONE WILL FOLLOW THE PROCEDURE OUTLINED IN THE SAVATREE TREE ASSESSMENT AND PROTECTION PLAN LOCATED ON SHEET G-1. THE FINAL LOCATION OF THE PROTECTIVE FENCING SHALL BE INSTALLED UNDER THE SUPERVISION OF THE ARBORIST.

APPROX. LOCATION OF 18" HDPE EXISTING DRAINAGE PIPE

APPROX. LOCATION OF ABANDONED 18" EXISTING DRAINAGE PIPE

EXISTING LAMP POST TO BE REMOVED

EXISTING UNDERGROUND FUEL TANK TO BE REMOVED

TREES TO BE PROTECTED (TYP)

TREES TO BE REMOVED (TYP)

EXISTING PAVED DRIVEWAY TO BE DEMOLISHED

EXISTING BUILDING TO BE DEMOLISHED

EXISTING SEWER SERVICE TO BE REMOVED AND CAPPED IF POSSIBLE BY MAIN IN COORDINATION WITH THE VILLAGE.

EXISTING PAVEMENT TO BE REMOVED

APPROXIMATE LOCATION OF EXISTING WATER SERVICE TO BE ABANDONED IN COORDINATION WITH THE VILLAGE D.P.W.

EXISTING VALVE TO BE CAPPED OFF AT CORP VALVE

EXISTING PAVEMENT AND CURB TO BE REMOVED

EXISTING PAVED DRIVEWAY TO EXTEND TO PROPERTY LINE AND BE REPAVED

LEGEND

TO BE REMOVED OR DEMOLISHED

NOTE:
1. IT SHOULD BE NOTED THAT THE DEMOLITION OF THE BUTTERFIELD HOSPITAL BUILDING WILL REQUIRE THE REMOVAL OF ASBESTOS. REFER TO NOTE #8 UNDER GENERAL CONSTRUCTION NOTES ON SHEET G-1.

NOTE:
1. *THIS IS NOT A SURVEY.* ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

OFFICE COPY

0 15 30 60
SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
(Or Included Code Rule 753 inquiries to be in from two working days notice, but not more than ten days notice.
www.digsafelynewyork.com

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2015 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer:
Joseph C. Riina, P.E.
NYS Lic. No. 064451

Revisions:

No.	Date	Comments
1	1-9-15	Revisions per comments from B&E.
2	1-9-15	Revisions per comments from B&E.
3	2-10-15	Revisions per comments from B&E.
4	2-11-15	Parking Added
5	3-13-15	Revisions per comments from NYSDOT.
6	3-23-15	Revisions per comments from B&E.
7	4-23-15	Revisions per comments from BCHOH.
8	4-24-15	Revisions per comments from 5/1/15 meeting.
9	6-9-15	Revisions per comments from NYSDOT.

SCALE: 1" = 30'
DRAWN BY: EL
DATE: 10/22/14

EXISTING CONDITIONS & DEMOLITION PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

C - 102

C:\USERS\EL\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REVISAL\COMPLETE\ENGINEERING\CAD\14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REVISED

CONTRACTOR CERTIFICATION STATEMENT

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-10-001, dated January 28, 2010, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor: _____

Name and Title (please print): _____

Signature of Contractor: _____

Company / Contracting Firm: _____

Name of Company: _____

Address of Company: _____

Telephone Number / Cell Number: _____

Site Information: _____

Address of Site: _____

_____

Today's Date: _____

OWNER / OPERATOR CERTIFICATION

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): _____

Title: _____

Date: _____

Address: _____

Phone: _____

E-mail: _____

Signature: _____

PROJECT DISTURBANCE SUMMARY

PHASE I: RESIDENTIAL LOTS

PHASE II: MAIN ENTRANCE OFF OF ROUTE 9D UP TO THE LAHEY PAVILION INCLUDING BUILDING 2

PHASE III: GATEWAY PARK AND THE REMAINING PROPOSED ROADWAY AND BUILDING 3

PHASE IV: BUILDINGS 4,5,& 6 WITH BUILDING 1

PROJECT DISTURBANCE

PHASE I: 0.727 ACRE

PHASE II: 1.322 ACRE

PHASE III: 2.907 ACRE

PHASE IV: 0.757 ACRE

LEGEND

- 222 — EXISTING GRADING
- ×222.8 — EXISTING SPOT GRADE
- 200 — PROPOSED GRADING
- +222.8 — PROPOSED SPOT GRADE
- PROPERTY LINE / RIGHT OF WAY
- PROPOSED TRAFFIC SIGN
- PROPOSED RETAINING WALLS
- SS — PROPOSED SOIL STOCKPILES
- CONCRETE WASHOUT PIT
- PROPOSED SILT FENCE
- PROPOSED CRUSHED STONE INLET PROTECTION
- W B — PROPOSED TEMPORARY WATER BAR
- PROPOSED STABILIZED CONSTRUCTION ENTRANCE
- PROPOSED LIMIT OF DISTURBANCE
- EB / PS — PROPOSED EROSION BLANKET / PERMANENT SEED
- VP — EXISTING TREE TO BE PROTECTED
- EXISTING TREE TO BE REMOVED
- PROPOSED TEMPORARY DIVERSION SWALE

PAULDING AVENUE

PROPOSED RESIDENCE BF = 151' FF = 161'

PROPOSED RESIDENCE BF = 151' FF = 161'

PROPOSED RESIDENCE BF = 151' FF = 159'

DECK

PHASE I

PHASE III

PHASE IV

TEMPORARY SEDIMENT TRAP #2

TEMPORARY DIVERSION SWALE

STOCKPILE AREA DURING PHASE I-III

TEMPORARY CONCRETE WASHOUT PIT (TYP)

TEMPORARY CONSTRUCTION TRAILER DURING CONSTRUCTION PHASING

STAGING AREA FOR CONSTRUCTION EQUIPMENT STORAGE TRAILERS AND WASTE CONTAINERS

TREE PROTECTION (TYP) 6' HIGH CHAIN LINK FENCE SUPPORTED ON GROUND WITH ALUMINUM OR CONCRETE FENCE POST BASE (SEE NOTES ON SHEET G-1)

BUILDING 4 & 5 SENIOR HOUSING W/ UNDERGROUND PARKING BF = 139' FF = 150.5'

RESIDENT COMMUNITY CENTER FF = 150.5'

PHASE IV

BUILDING 6 SENIOR HOUSING W/ UNDERGROUND PARKING BF = 127' FF = 148.5'

TEMPORARY SEDIMENT TRAP #3

TEMPORARY SEDIMENT TRAP #7

BUILDING 3 SENIOR HOUSING W/ UNDERGROUND PARKING BF = 136.5' FF = 150'

TEMPORARY SEDIMENT TRAP #1

INLET PROTECTION (TYP)

TEMPORARY SEDIMENT TRAP #6

TEMPORARY SEDIMENT TRAP #9

TEMPORARY CONCRETE WASHOUT PIT (TYP)

TEMPORARY SEDIMENT TRAP #11

PHASE III

SLOPE TO SWALE

ADJACENT PROPERTIES TO BE PROTECTED DURING CONSTRUCTION FROM ANY DISTURBANCES OF SOIL, TREES, STRUCTURES ETC. UNLESS CONSENT IS PROVIDED BY THE PROPERTY OWNER.

TEMPORARY SEDIMENT TRAP #5

LAHEY PAVILION EXISTING BUILDING FF = +138'

PHASE IV BUILDING 1 OFFICE-RETAIL BF = 132.25' FF = 142.25'

PROPOSED LIMIT OF DISTURBANCE/ PHASE LINE

TEMPORARY SEDIMENT TRAP #8

PROPOSED TEMPORARY ASPHALT WATER BAR

TEMPORARY SEDIMENT TRAP #4

TEMPORARY SEDIMENT TRAP #10

BUILDING 2 OFFICE-RETAIL BF = 125' FF = 136'

PROPOSED DRAIN INLET PROTECTION (TYP)

NOTE: THIS ENTRANCE SHALL NOT BE USED FOR CONSTRUCTION VEHICLES ENTERING OR EXITING THE SITE

PHASE II

CHESTNUT STREET

NEW YORK STATE ROUTE 9D

PROPOSED SILT FENCE (TYP)

PROPOSED STOCK PILE AREA FOR PHASE IV

PROPOSED WATER BAR (TYP)

PROPOSED LIMIT OF DISTURBANCE/ PHASE LINE

PROPOSED DRAIN INLET PROTECTION (TYP)

TEMPORARY SEDIMENT TRAP #12

PROPOSED TEMPORARY CONSTRUCTION ENTRANCE (TYP)

EXISTING ASPHALT TO REMAIN AT EXISTING ENTRANCES DURING CONSTRUCTION UNTIL NEW PAVEMENT IS TO BE INSTALLED (TYP)

EXISTING TREES TO REMAIN (TYP)

STABILIZE FINISH GRADE WITH SEDIMENT AND EROSION BLANKETS

TREE PROTECTION (TYP)

EXISTING TREES TO BE REMOVED PER SAVE A TREE RECOMMENDATIONS (TYP)

SEDIMENT TEMPORARY TRAP SIZING			
Trap #	Approximate size	Volume Required (cf)	Volume Provided (cf)
Trap #1	18 x 18 x 2.5	800	810
Trap #2	18 x 18 x 2.5	800	810
Trap #3	18 x 18 x 2.5	800	810
Trap #4	15 x 15 x 2.5	535	563
Trap #5	14 x 14x 2.5	401	490
Trap #6	14 x 14x 2.5	360	490
Trap #7	18 x 18 x 2.5	797	810
Trap #8	18 x 18 x 2.5	736	810
Trap #9	19 x 18 x 2.5	815	855
Trap #10	12 x 12 x 2.5	253	640
Trap #11	18 x 18 x 2.5	713	810
Trap #12	12 x 12 x 2.5	355	360

OFFICE COPY

0 15 30 60

SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
It's free and it's the law. Rule 753 requires no less than two full working days (but not more than ten days notice) before you begin excavation.
www.digalertnewyork.com

NOTE:
1. *THIS IS NOT A SURVEY.* ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\BJ STEREO\DOCUMENTS\CONVERTED FOR ARTRUK\2-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\C-103 SITE PLAN REV 4.DWG

PROJECT # 14-25

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

STATE OF NEW YORK · JOSEPH C. RITNA · LICENSED PROFESSIONAL ENGINEER · 083901

Engineer: Joseph C. Ritna, P.E.
NYS Lic. No. 64451

Revisions:

No.	Date	Comments
1	12-5-14	Revisions per comments from B&E
2	1-9-15	Revisions per comments from B&E
3	2-10-15	Revisions per comments from B&E
4	3-16-15	Revisions per NYSDOT
5	5-13-15	Revisions per comments from B&E
6	1-23-15	Revisions per comments from B&E
7	4-22-15	Revisions per comments from NYSDOT
8	4-22-15	Revisions per comments from NYSDOT meeting
9	6-9-15	Revisions per comments from NYSDOT

SCALE: 1" = 30'
DRAWN BY: EL
DATE: 10/22/14

EROSION & SEDIMENT CONTROL PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR

Butterfield Redevelopment Project
1756 NYS ROUTE 9D

Putnam County, New York
Village Of Cold Spring

C - 103

INSET A SCALE: 1"=20'



INSET B SCALE: 1"=20'





LEGEND

- 222 — EXISTING GRADING
- 200 — PROPOSED GRADING
- +222.8 — PROPOSED SPOT GRADE
- PROPERTY LINE / RIGHT OF WAY
- PROPOSED RETAINING WALLS

THE VERTICAL DATUM USED IS NAVD 88

NOTE:

1. *THIS IS NOT A SURVEY.* ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/ 0/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
NY Industrial Code Rule 753 requires no less than two working days notice, but not more than ten days notice.
www.digsafelynewyork.com

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4810 • Fax: (914) 962-7366
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

STATE OF NEW YORK — JOSEPH CARLO KLIMA — 100434 — Licensed Professional Engineer

Engineer: Joseph C. Klima, P.E.
NYS Lic. No. 64431

Revisions:

No.	Date	Comments
1	12-3-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	3-16-15	Revisions per comments from B&L
5	5-13-15	Revisions per comments from B&L
6	5-23-15	Revisions per comments from B&L
7	4-27-15	Revisions per comments from DCDOH meeting
8	4-27-15	Revisions per comments from NYSDOT
9	6-9-15	Revisions per comments from NYSDOT

SCALE: 1" = 30'

DRAWN BY: EL

DATE: 10/22/14

GRADING PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR

Butterfield Redevelopment Project

1756 NYS ROUTE 9D

Putnam County, New York

Village Of Cold Spring

C - 104

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\EL\STDESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\CAD-14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REV.6.DWG

DRAINAGE RIMS AND INVERTS

NODE	RIM	INV IN	INV OUT	DOWNSTREAM NODE	DOWNST REAM INV	L(FT)	S(%)	SIZE(in)
CB-1	141.15	---	136.46	CB-2	134.81	63	2.5	15
CB-2	139.05	134.81	134.55	CB-3	126.31	130	6.2	15
CB-3	129.34	126.31	125.55	CB-4	113.97	138	8.2	15
CB-4	117.91	114.55	113.72	Crystal Stream Unit 1	113.45	48	0.5	15
Crystal Stream Unit 1	121.44	113.45	113.3	Bypass 1	113.25	5	0.5	15
Bypass 1	121.70	113.25	113.0	DMH-1	112.92	11	0.5	12
DMH-1	121.02	112.92	112.67	Existing CB 2	112.31	68	0.5	12
CB-5	118.26	---	114.75	CB-4	114.55	18	1	15
Bypass 1	121.70	113.25	112.90	Infil. Sys. 1	112.86	8	0.5	15
DI-1	149.02	147.78	145.52	DI-2	145.17	67	0.5	15
DI-2	150.00	145.17	144.92	DMH-2	144.89	3	0.5	15
DMH-2	150.08	144.89	144.65	DMH-3	144.26	73	0.5	15
DMH-3	148.02	144.26	144.01	DMH-4	143.85	28	0.5	15
DMH-4	148.02	143.85	143.60	CB-11	139.60	177	2.2	15
CB-11	143.91	139.6	139.35	CB-12	139.26	16	0.5	15
CB-12	144.00	139.26	139.01	CB-13	135.75	82	3.8	15
CB-13	138.00	135.75	135.5	CB-14	131.62	89	4.2	15
CB-14	135.31	131.62	131.37	CB-15	131.28	16	0.5	15
CB-15	135.83	131.28	131.03	Crystal Stream Unit 3	130.71	58	0.5	15
Crystal Stream Unit 3	136.97	130.71	130.46	Bypass 3	130.41	4	0.5	15
Bypass 3	136.97	130.41	130.16	Infil. Sys. 3	130.13	4	0.5	15
Bypass 3	136.97	130.41	130.16	DMH-6	129.82	65	0.5	12
INFIL. SYS. 3	136.72	129.09	131.57	DMH-6	130.49	35	4.9	6
DMH-6	135.00	129.82	129.57	DMH-7	125.88	179	2.0	12
DMH-7	130.00	125.88	125.63	EXisting CB 4	125.54	15	0.5	12
R.W.H 2	134.86	---	133	CB-6	130.87	46	4.5	12
CB-6	134.02	130.87	130.62	CB-7	129.72	28	2.9	15
CB-7	133.95	129.72	129.47	CB-8	126.03	79	4.1	15
CB-8	130.01	126.03	125.78	CB-9	125.68	19	0.5	15
CB-9	130.04	125.68	125.43	Crystal Stream Unit 2A	125.38	6	0.5	15
Crystal stream Unit 2A	130.00	125.38	125.13	Bypass 2A	125.06	14	0.8	15
Bypass 2A	129.77	125.06	124.5	DMH-8	122.11	57	3.8	12
Bypass 2A	129.77	125.06	123.12	Infil. Sys. 2	123.05	3	0.5	15
DMH-8	127.46	122.11	121.86	DMH-5	119.02	108	2.5	12
CB-10	133.25	---	124.66	Crystal Stream Unit 2B	123.6	56	1.8	12
Crystal Stream Unit 2B	128.22	123.6	123.45	Bypass 2B	123.34	17	0.5	12
Bypass 2B	127.14	123.34	123.09	DMH-8	122.11	6	10.2	12
Bypass 2B	127.14	123.34	122.84	Infil. Sys. 2	123.05	3	0.5	15
DMH-8	127.46	122.11	121.86	DMH-5	119.02	108	2.5	12
R.W.H 1	132.35	---	130.00	DMH-5	118.97	75	14.7	12
DMH-5	122.88	118.97	118.72	Existing CB 3	118.41	35	0.83	12
DI-3	144.30	---	142.05	DAYLIGHT	137.65	89	4.9	6
DI-4	137.01	---	134.34	Crystal Stream Unit 3	130.71	31	11.7	12

Note:
This table does not reflect any invert elevations of roof drains or footing drains. Please refer to table "roof drains and footing drain inverts".

SEWER MANHOLE RIMS AND INVERTS

NODE	RIM	INV IN	INV OUT	DOWNSTREAM NODE	L(FT)	S(%)	SIZE(in)
SMH-1	143.32	---	135.09	SMH-2	181	4	8
SMH-2	133.55	127.57	127.57	SMH-3	75	4.2	8
SMH-3	128.92	124.40	124.05	SMH-4	87	1	8
SMH-4	128.00	123.10	123.10	SMH-5	161	0.6	8
SMH-5	130.34	122.13	122.13	SMH-6	171	6	8
SMH-6	116.77	111.80	111.80	SMH-7	83	2.4	8
SMH-7	116.32	109.72					

ROOF DRAINS AND FOOTING DRAIN INVERTS

UP STR. ID	INV. OUT	DOWN STR. ID	INV IN	L(FT)	S(%)	SIZE(in)
RD FROM RES. LOTS	149.02	DI-1	147.78	62	2.0	6
RD FROM RES. LOTS & BLDG. 6	148.24	DI-3	142.65	45	12.4	6
FD FROM BLDG 3	133.95	CB-7	132.94	50	2.0	6
RD FROM BLDG. 4&5	144.00	CB-12	143.00	28	3.6	6
FD FROM BLDG 6	135.83	CB-15	132.83	101	3.0	6
FD & RD FROM BLDG. 1	130.01	CB-8	126.03	20	19.4	6
RD FROM BLDG. 3	132.35	R.W.H.#2	131.50	25.00	4.5	6
RD FROM LAHEY & BLDG. 2	134.86	R.W.H.#1	130.50	27	20.0	6
RD FROM BLDG.2	122.00	BYPASS 1	113.27	45	19.4	6
FD FROM BLDG. 2	122.00	DMH-5	118.97	50	6.1	6

LEGEND

- EXISTING GRADING (222)
- EXISTING SPOT GRADE (×222.8)
- PROPOSED GRADING (200)
- PROPOSED SPOT GRADE (+222.8)
- PROPERTY LINE / RIGHT OF WAY
- PROPOSED RETAINING WALLS
- EXISTING WATER LINE (W)
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- EXISTING DRAINAGE INLET (C)
- EXISTING SANITARY LINE (S)
- PROPOSED SIAMESE CONNECTION
- PROPOSED SEWER CLEAN OUT
- PROPOSED DRAINAGE LINE
- PROPOSED CATCH BASIN
- PROPOSED DRAINAGE MANHOLE (D)
- PROPOSED FOOTING DRAIN (FD)
- PROPOSED ROOF DRAIN (RD)
- PROPOSED SEWER SERVICE CONNECTION (SS)
- PROPOSED WATER MAIN (W)
- PROPOSED 3" D.I.P. WATER SERVICE CONNECTION (WS)
- PROPOSED 6" D.I.P. FIRE SERVICE CONNECTION (FS)
- PROPOSED UTILITY CROSSING
- PROPOSED SANITARY MANHOLE AND LINE (S)
- PROPOSED LIGHT POST
- PROPOSED STONE OUTLET PROTECTION

EXISTING SEWER MH RIM = 158.3' INV. = 149.3'
PROPOSED 1" Ø COPPER WATER SERVICE FOR THE PROPOSED SINGLE FAMILY RESIDENCES (TYP)
EXISTING WATER SERVICE VALVE TO BE CAPPED
PROPOSED 4" Ø PVC SDR 35 SEWER SERVICE FOR PRIVATE RESIDENCES (TYP)
EXISTING FIRE HYDRANT
EXISTING 6" WATER MAIN
APPROX. LOCATIONEXISTING 18" DRAINAGE PIPE DISCHARGE
PROPOSED ENERGY DISSIPATOR AND GRASS LEVEL SPREADER L=15'
PROPOSED 20' WIDE UTILITY EASEMENT
PROPOSED 8" D.I.P. CL 52 WATER MAIN
PROPOSED 6" x 6" TAPPING SLEEVE, 6" x 6" REDUCER, AND 8" GATE VALVE
PROPOSED 10' WIDE PRIVATE DRAINAGE EASEMENT
NYOPLAST VERTICAL MAINTENANCE STRUCTURE WITH DIVERSION WEIR TO ISOLATOR ROW AND ACCESS COVER. WEIR INVERT TO BE SET EVEN WITH TOP OF ISOLATOR ROW
PROPOSED STAND PIPE (TYP)
PROPOSED HDPE END SECTION DRAINAGE PIPE DISCHARGE INTO GRASS SWALE LEADING TO BIO-RETENTION INV. = 137.65'
PROPOSED STONE OUTLET PROTECTION
CRYSTAL STREAM PRE-TREATMENT CHAMBER
PROPOSED RIP-RAP LINING ON BOTTOM AND SIDING OF THIS SECTION ON THIS GRASS SWALE
PROPOSED CONCRETE FLOW TURNING TRENCH DRAIN W/ OPEN ENDS AND ADA ACCESSIBLE GRATE INV. = 136.0
PROPOSED STONE OUTLET PROTECTION
PROPOSED INFILTRATOR SYSTEM #3 SC-740 CHAMBERS 44 CHAMBERS SYSTEM INV. = 129.09'
PROPOSED BIORETENTION ABOVE INFILTRATORS
EXISTING CB 5 RIM = 136.4' INV. A = 132.10' INV. B = 132.15'
PROPOSED 6" Ø HDPE OVERFLOW PIPE L=35' , S=4.9%
PROPOSED FOOTING DRAIN (TYP)
WATER MAIN CROSSING MAINTAIN 18" VERTICAL SEPARATION (TYP)
PROPOSED 8" X 6" REDUCER AND 6" GATE VALVE
PROPOSED FIRE HYDRANT
8" Ø CL-52 DIP WATER MAIN HYDRANT LEAD
PROPOSED 6" PVC SDR 35 PIPE SEWER SERVICE S= 1.0% MIN. (TYP)
CONNECT TO EXISTING CATCH BASIN 4 RIM = 129.42' INV. A = 122.9' INV. B = 124.0'
PROPOSED CLEAN OUT FOR 6" PVC SDR 35 PIPE (TYP)
PROPOSED 8" PVC SDR 35 SANITARY SEWER
PROPOSED INFILTRATOR SYSTEM # 2 SC-740 CHAMBERS 32 CHAMBERS REQUIRED SYSTEM INV. = 121.51'
HDPE OVERFLOW DISCHARGE PIPE FROM INFILTRATION SYSTEM
PROPOSED CRYSTAL STREAM PRETREATMENT CHAMBER
PROPOSED 20' WIDE UTILITY EASMENT
EXISTING SANITARY SEWER LINE TO BE REMOVED AND CAPPED AT EASEMENT R.O.W. IN COORDINATION WITH THE VILLAGE DPW POSSIBLE CAP WILL BE LOCATED AT MAIN.
PROPOSED DRAINAGE MANHOLE (TYP.)
PROPOSED DRAINAGE MANHOLE (TYP.) STA:3+65.06
PROPOSED CLEAN OUT (TYP)
6" HDPE ROOF DRAIN COLLECTOR PIPE
PROPOSED LIGHTING (SEE LIGHTING PLAN FOR DETAILS)
PROPOSED CATCH BASIN (TYP)
CONTROL VALVES TO INITIALIZE WELL SUPPLY TO BE ACUATED BY LEVEL INDICATORS IN RWH TANKS. CONTROLS SHALL BE LOCATED IN PUMP CHAMBER (TYP)
PROPOSED IRRIGATION WELL
EXISTING FIRE HYDRANT TO REMAIN
PROPOSED 8" D.I.P. CL 52 WATER MAIN
PROPOSED 8" x 8" TAPPING SLEEVE AND GATE VALVE
WATER MAIN CROSSING MAINTAIN 18" VERTICAL SEPARATION (TYP)
PROPOSED SUBSURFACE IRRIGATION PUMPING SYSTEM
EXISTING WATER MAIN
PROPOSED ROOF DRAIN TYP.
PROPOSED CATCH BASIN (TYP)
PROPOSED 6" D.I.P. FIRE SERVICE (TYP)
PROPOSED 3" D.I.P. DOMESTIC WATER SERVICE (TYP)
PROPOSED TOWN ACCESS/ UTILITY EASEMENT WITHIN CURB LINES AND SHALL BE INCLUSIVE OF EXISTING EASEMENT
HDPE DRAINAGE PIPE (TYP)
PROPOSED 6" PVC SDR 35 PIPE SEWER SERVICE S= 1.0% MIN. (TYP)
PROPOSED FOOTING DRAIN
PROPOSED CRYSTAL STREAM PRETREATMENT CHAMBER
EXISTING UTILITY EASEMENT
EXISTING FIRE HYDRANT
EXISTING WATER VAVLE RIM = 118.7' INVERT = 113.1'
EXISTING CB 1 RIM = 116.0' INV. A = 112.1' INV. B = 112.2' INV. C = 112.3'
APPROXIMATE LOCATION OF WATER MAIN AND MUST BE FIELD DETERMINED
PROPOSED SEWER MAIN IS REQUIRED BY NYSDOT TO BE INSTALLED VIA DIRECTIONAL BORE AS PER PLANS AND DETAILS APPROVED BY NYSDOT.
EXISTING SEWER MH RIM = 116.8' INV. = 106.2'
DOGHOUSE MANHOLE
EXISTING CB 2 RIM = 116.82' INV. A = 112.2' INV. B = 112.4' INV. C = 112.31'
SMH-7
10" INSPECTION / FLUSHING PORTS AS PER MANUFACTURERS SPECIFICATIONS (TYP)
PROPOSED INFILTRATOR SYSTEM #1 SC-740 CHAMBERS 32 CHAMBERS REQUIRED SYSTEM INV. = 111.32'
NYOPLAST VERTICAL MAINTENANCE STRUCTURE WITH DIVERSION WEIR TO ISOLATOR ROW AND ACCESS COVER. WEIR INVERT TO BE SET EVEN WITH TOP OF ISOLATOR ROW
HDPE 4" OVERFLOW DISCHARGE PIPE FROM INFILTRATION SYSTEM
EXISTING CB 3 RIM = 122..34' INV. A = 115.5' INV. B = 117.6'
POSSIBLE LOCATION OF GENERATOR PAD
HDPE OVERFLOW DISCHARGE PIPE FROM INFILTRATION SYSTEM
PROPOSED RAIN WATER HARVESTING #2 SYSTEM INV. = 131.0'
PROPOSED RAIN WATER HARVESTING #1 SYSTEM INV. = 128.0'
BUILDING 4 & 5 SENIOR HOUSING W/ UNDERGROUND PARKING BF = 139' FF = 150.5'
BUILDING 3 SENIOR HOUSING W/ UNDERGROUND PARKING BF = 138.5' FF = 150'
BUILDING 6 SENIOR HOUSING W/ UNDERGROUND PARKING BF = 140' FF = 149.5'
LAHEY PAVILION EXISTING BUILDING FF = +138'
BUILDING 2 OFFICE-RETAIL BF = 125' FF = 136'
BUILDING 1 OFFICE-RETAIL BF = 132.25' FF = 142.25'
RESIDENT COMMUNITY CENTER FF = 150.5'
PROPOSED RESIDENCE BF = 151' FF = 161'
PROPOSED RESIDENCE BF = 151' FF = 161'
PROPOSED RESIDENCE BF = 150' FF = 159'
CRYSTAL STREAM UNIT 1
CRYSTAL STREAM UNIT 2B
CRYSTAL STREAM UNIT 3
CRYSTAL STREAM UNIT 2A
BYPASS 1
BYPASS 2A
BYPASS 2B
BYPASS 3
PAULDING AVENUE
NEW YORK STATE ROUTE 9D
CHESTNUT STREET
UTILITY EASEMENT

IRRIGATION SYSTEM NOTE:
THE IRRIGATION WELL AND RAINWATER HARVESTING SYSTEM WILL NOT BE INTERCONNECTED TO THE DOMESTIC WATER SUPPLY SYSTEM AT ANY TIME NOR WILL THE WATER FROM THESE SYSTEMS BE USED FOR DOMESTIC CONSUMPTION.

NOTE: REFER TO DETAIL SHEETS C - 501 TO C - 508 FOR UTILITY DETAILS.

OFFICE COPY

0 15 30 60
SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
It's the law! Excavators must notify member companies of their intent to excavate at least two working days before, but not more than ten days notice.
www.digalertnynjct.com

NOTE:
1. *THIS IS NOT A SURVEY.* ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\JB\DESKTOP\NEW FOLDER\BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\14-25 BUTTERFIELD REDEVELOPMENT-14-25.MTP PLAN REV 4.DWG

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7586
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer: Joseph C. Ritna, P.E. NYS Lic. No. 64451

Revisions:

No	Date	Comments:
1	12-3-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-19-15	Parking Space comments from B&L
4	3-11-15	Revisions per comments from B&L
5	4-23-15	Revisions per comments from PCPDOH
6	4-27-15	Revisions per comments from NYSDOT
7	5-8-15	Revisions per comments from PCPDOH meeting
8	6-2-15	Revisions per comments from NYSDOT
9		

SCALE: 1" = 30'
DRAWN BY: EL
DATE: 10/22/14

UTILITY PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

C - 105

DRAINAGE RIMS AND INVERTS

NODE	RIM	INV IN	INV OUT	DOWNSTREAM NODE	DOWNST REAM INV	L(FT)	S(%)	SIZE(in)
CB-1	141.15	---	136.46	CB-2	134.81	63	2.5	15
CB-2	139.05	134.81	134.55	CB-3	126.31	130	6.2	15
CB-3	129.34	126.31	125.55	CB-4	113.97	138	8.2	15
CB-4	117.91	114.55	113.72	Crystal Stream Unit 1	113.45	48	0.5	15
Crystal Stream Unit 1	121.44	113.45	113.3	Bypass 1	113.25	5	0.5	15
Bypass 1	121.70	113.25	113.0	DMH-1	112.92	11	0.5	12
DMH-1	121.02	112.92	112.67	Existing CB 2	112.31	68	0.5	12
CB-5	118.26	---	114.75	CB-4	114.55	18	1	15
Bypass 1	121.70	113.25	112.90	Infil. Sys. 1	112.86	8	0.5	15
DI-1	149.02	147.78	145.52	DI-2	145.17	67	0.5	15
DI-2	150.00	145.17	144.92	DMH-2	144.89	3	0.5	15
DMH-2	150.08	144.89	144.65	DMH-3	144.26	73	0.5	15
DMH-3	148.02	144.26	144.01	DMH-4	143.85	28	0.5	15
DMH-4	148.02	143.85	143.60	CB-11	139.60	177	2.2	15
CB-11	143.91	139.6	139.35	CB-12	139.26	16	0.5	15
CB-12	144.00	139.26	139.01	CB-13	135.75	82	3.8	15
CB-13	138.00	135.75	135.5	CB-14	131.62	89	4.2	15
CB-14	135.31	131.62	131.37	CB-15	131.28	16	0.5	15
CB-15	135.83	131.28	131.03	Crystal Stream Unit 3	130.71	58	0.5	15
Crystal Stream Unit 3	136.97	130.71	130.46	Bypass 3	130.41	4	0.5	15
Bypass 3	136.97	130.41	130.16	Infil. Sys. 3	130.13	4	0.5	15
Bypass 3	136.97	130.41	130.16	DMH-6	129.82	65	0.5	12
INFIL. SYS. 3	136.72	129.09	131.57	DMH-6	130.49	35	4.9	6
DMH-6	135.00	129.82	129.57	DMH-7	125.88	179	2.0	12
DMH-7	130.00	125.88	125.63	EXisting CB 4	125.54	15	0.5	12
R.W.H 2	134.86	---	133	CB-6	130.87	46	4.5	12
CB-6	134.02	130.87	130.62	CB-7	129.72	28	2.9	15
CB-7	133.95	129.72	129.47	CB-8	126.03	79	4.1	15
CB-8	130.01	126.03	125.78	CB-9	125.68	19	0.5	15
CB-9	130.04	125.68	125.43	Crystal Stream Unit 2A	125.38	6	0.5	15
Crystal stream Unit 2A	130.00	125.38	125.13	Bypass 2A	125.06	14	0.8	15
Bypass 2A	129.77	125.06	124.5	DMH-8	122.11	57	3.8	12
Bypass 2A	129.77	125.06	123.12	Infil. Sys. 2	123.05	3	0.5	15
DMH-8	127.46	122.11	121.86	DMH-5	119.02	108	2.5	12
CB-10	133.25	---	124.66	Crystal Stream Unit 2B	123.6	56	1.8	12
Crystal Stream Unit 2B	128.22	123.6	123.45	Bypass 2B	123.34	17	0.5	12
Bypass 2B	127.14	123.34	123.09	DMH-8	122.11	6	10.2	12
Bypass 2B	127.14	123.34	122.84	Infil. Sys. 2	123.05	3	0.5	15
DMH-8	127.46	122.11	121.86	DMH-5	119.02	108	2.5	12
R.W.H 1	132.35	---	130.00	DMH-5	118.97	75	14.7	12
DMH-5	122.88	118.97	118.72	Existing CB 3	118.41	35	0.83	12
DI-3	144.30	---	142.05	DAYLIGHT	137.65	89	4.9	6
DI-4	137.01	---	134.34	Crystal Stream Unit 3	130.71	31	11.7	12

Note:
This table does not reflect any invert elevations of roof drains or footing drains. Please refer to table "roof drains and footing drain inverts".

SEWER MANHOLE RIMS AND INVERTS

NODE	RIM	INV IN	INV OUT	DOWNSTREAM NODE	L(FT)	S(%)	SIZE(in)
SMH-1	143.32	---	135.09	SMH-2	181	4	8
SMH-2	133.55	127.57	127.57	SMH-3	75	4.2	8
SMH-3	128.92	124.40	124.05	SMH-4	87	1	8
SMH-4	128.00	123.10	123.10	SMH-5	161	0.6	8
SMH-5	130.34	122.13	122.13	SMH-6	171	6	8
SMH-6	116.77	111.80	111.80	SMH-7	83	2.4	8
SMH-7	116.32	109.72					

ROOF DRAINS AND FOOTING DRAIN INVERTS

UP STR. ID	INV. OUT	DOWN STR. ID	INV IN	L(FT)	S(%)	SIZE(in)
RD FROM RES. LOTS	149.02	DI-1	147.78	62	2.0	6
RD FROM RES. LOTS & BLDG. 6	148.24	DI-3	142.65	45	12.4	6
FD FROM BLDG 3	133.95	CB-7	132.94	50	2.0	6
RD FROM BLDG. 4&5	144.00	CB-12	143.00	28	3.6	6
FD FROM BLDG 6	135.83	CB-15	132.83	101	3.0	6
FD & RD FROM BLDG. 1	130.01	CB-8	126.03	20	19.4	6
RD FROM BLDG. 3	132.35	R.W.H.#2	131.50	25.00	4.5	6
RD FROM LAHEY & BLDG. 2	134.86	R.W.H.#1	130.50	27	20.0	6
RD FROM BLDG.2	122.00	BYPASS 1	113.27	45	19.4	6
FD FROM BLDG. 2	122.00	DMH-5	118.97	50	6.1	6

LEGEND

- EXISTING GRADING
- EXISTING SPOT GRADE
- PROPOSED GRADING
- PROPOSED SPOT GRADE
- PROPERTY LINE / RIGHT OF WAY
- PROPOSED RETAINING WALLS
- EXISTING WATER LINE
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- EXISTING DRAINAGE INLET
- EXISTING SANITARY LINE
- PROPOSED SIEMESE CONNECTION
- PROPOSED GRASS LEVEL SPREADER
- PROPOSED DRAINAGE LINE
- PROPOSED CATCH BASIN
- PROPOSED DRAINAGE MANHOLE
- PROPOSED FOOTING DRAIN
- PROPOSED ROOF DRAIN
- PROPOSED SEWER SERVICE CONNECTION
- PROPOSED WATER MAIN
- PROPOSED 3" D.I.P. WATER SERVICE CONNECTION
- PROPOSED 6" D.I.P. WATER SERVICE CONNECTION
- PROPOSED UTILITY CROSSING
- PROPOSED SANITARY MANHOLE AND LINE
- PROPOSED LIGHT POST
- PROPOSED STONE OUTLET PROTECTION

EXISTING SEWER MH RIM = 158.5' INV. = 149.3'
PROPOSED 1" Ø COPPER WATER SERVICE FOR THE PROPOSED SINGLE FAMILY RESIDENCES (TYP)
EXISTING WATER SERVICE VALVE TO BE CAPPED
PROPOSED 4" Ø PVC SDR 35 SEWER SERVICE FOR PRIVATE RESIDENCES (TYP)
EXISTING FIRE HYDRANT
EXISTING 6" WATER MAIN
APPROX. LOCATIONEXISTING 18" DRAINAGE PIPE DISCHARGE
PROPOSED ENERGY DISSIPATOR AND GRASS LEVEL SPREADER L=15'
PROPOSED 20' WIDE UTILITY EASEMENT
PROPOSED 8" D.I.P. CL 52 WATER MAIN
PROPOSED 6" x 6" TAPPING SLEEVE, 6" x 6" REDUCER, AND 6" GATE VALVE
PROPOSED 10' WIDE PRIVATE DRAINAGE EASEMENT
NYOPLAST VERTICAL MAINTENANCE STRUCTURE WITH DIVERSION WEIR TO ISOLATOR ROW AND ACCESS COVER. WEIR INVERT TO BE SET EVEN WITH TOP OF ISOLATOR ROW
PROPOSED STAND PIPE (TYP)
PROPOSED HDPE END SECTION DRAINAGE PIPE DISCHARGE INTO GRASS SWALE LEADING TO BIO-RETENTION INV. = 137.65'
PROPOSED STONE OUTLET PROTECTION
CRYSTAL STREAM PRE-TREATMENT CHAMBER
PROPOSED RIP-RAP LINING ON BOTTOM AND SIDING OF THIS SECTION ON THIS GRASS SWALE
PROPOSED CONCRETE FLOW TURNING TRENCH DRAIN W/ OPEN ENDS AND ADA ACCESSIBLE GRATE INV. = 136.0
PROPOSED STONE OUTLET PROTECTION
PROPOSED INFILTRATOR SYSTEM #3 SC-740 CHAMBERS 44 CHAMBERS SYSTEM INV. = 129.09'
PROPOSED BIORETENTION ABOVE INFILTRATORS
EXISTING CB 5 RIM = 135.4' INV. A = 132.10' INV. B = 132.15'
PROPOSED 6" Ø HDPE OVERFLOW PIPE L=35', S=4.9%
PROPOSED FOOTING DRAIN (TYP)
WATER MAIN CROSSING MAINTAIN 18" VERTICAL SEPARATION (TYP)
PROPOSED 8" X 6" REDUCER AND 6" GATE VALVE
PROPOSED FIRE HYDRANT
8" Ø CL-52 DIP WATER MAIN HYDRANT LEAD
PROPOSED 6" PVC SDR 35 PIPE SEWER SERVICE S= 1.0% MIN. (TYP)
CONNECT TO EXISTING CATCH BASIN 4 RIM = 129.42' INV. A = 122.9' INV. B = 124.0'
PROPOSED CLEAN OUT FOR 6" PVC SDR 35 PIPE (TYP)
PROPOSED 8" PVC SDR 35 SANITARY SEWER
PROPOSED INFILTRATOR SYSTEM # 2 SC-740 CHAMBERS 32 CHAMBERS REQUIRED SYSTEM INV. = 121.51'
HDPE OVERFLOW DISCHARGE PIPE FROM INFILTRATION SYSTEM
PROPOSED CRYSTAL STREAM PRETREATMENT CHAMBER
PROPOSED 20' WIDE UTILITY EASMENT
EXISTING SANITARY SEWER LINE TO BE REMOVED AND CAPPED AT EASEMENT R.O.W. IN COORDINATION WITH THE VILLAGE DPW POSSIBLE CAP WILL BE LOCATED AT MAIN.
PROPOSED DRAINAGE MANHOLE (TYP.)
PROPOSED LIGHTING (SEE LIGHTING PLAN FOR DETAILS)
PROPOSED CATCH BASIN (TYP)
CONTROL VALVES TO INITIALIZE WELL SUPPLY TO BE ACUATED BY LEVEL INDICATORS IN RWH TANKS. CONTROLS SHALL BE LOCATED IN PUMP CHAMBER (TYP)
PROPOSED IRRIGATION WELL
EXISTING FIRE HYDRANT TO REMAIN
PROPOSED 8" D.I.P. CL 52 WATER MAIN
PROPOSED 8" x 8" TAPPING SLEEVE AND GATE VALVE
WATER MAIN CROSSING MAINTAIN 18" VERTICAL SEPARATION (TYP)
PROPOSED SUBSURFACE IRRIGATION PUMPING SYSTEM
EXISTING WATER MAIN
PROPOSED ROOF DRAIN TYP.
PROPOSED CATCH BASIN (TYP)
PROPOSED 6" D.I.P. FIRE SERVICE (TYP)
PROPOSED 3" D.I.P. DOMESTIC WATER SERVICE (TYP)
PROPOSED TOWN ACCESS/ UTILITY EASEMENT WITHIN CURB LINES AND SHALL BE INCLUSIVE OF EXISTING EASEMENT
HDPE DRAINAGE PIPE (TYP)
PROPOSED 6" PVC SDR 35 PIPE SEWER SERVICE S= 1.0% MIN. (TYP)
PROPOSED FOOTING DRAIN
PROPOSED CRYSTAL STREAM PRETREATMENT CHAMBER
EXISTING UTILITY EASEMENT
EXISTING FIRE HYDRANT
EXISTING WATER VAVLE
EXISTING CB 1 RIM = 118.0' INV. A = 112.1' INV. B = 112.2' INV. C = 112.3'
APPROXIMATE LOCATION OF WATER MAIN AND MUST BE FIELD DETERMINED
PROPOSED SEWER MAIN IS REQUIRED BY NYSDOT TO BE INSTALLED VIA DIRECTIONAL BORE AS PER PLANS AND DETAILS APPROVED BY NYSDOT.
EXISTING SEWER MH RIM = 116.8' INV. = 106.2'
DOGHOUSE MANHOLE
EXISTING CB 2 RIM = 116.82' INV. A = 112.2' INV. B = 112.4' INV. C = 112.31'
10" INSPECTION / FLUSHING PORTS AS PER MANUFACTURERS SPECIFICATIONS (TYP)
PROPOSED INFILTRATOR SYSTEM #1 SC-740 CHAMBERS 32 CHAMBERS REQUIRED SYSTEM INV. = 111.32'
NYOPLAST VERTICAL MAINTENANCE STRUCTURE WITH DIVERSION WEIR TO ISOLATOR ROW AND ACCESS COVER. WEIR INVERT TO BE SET EVEN WITH TOP OF ISOLATOR ROW
HDPE 4" OVERFLOW DISCHARGE PIPE FROM INFILTRATION SYSTEM
POSSIBLE LOCATION OF GENERATOR PAD
EXISTING CB 3 RIM = 122..34' INV. A = 115.5' INV. B = 117.8'
PROPOSED DRAINAGE MANHOLE (TYP.)

IRRIGATION SYSTEM NOTE:
THE IRRIGATION WELL AND RAINWATER HARVESTING SYSTEM WILL NOT BE INTERCONNECTED TO THE DOMESTIC WATER SUPPLY SYSTEM AT ANY TIME NOR WILL THE WATER FROM THESE SYSTEMS BE USED FOR DOMESTIC CONSUMPTION.

OFFICE COPY

0 15 30 60
SCALE: 1"=30'-0"

NOTE:
1. *THIS IS NOT A SURVEY.* ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

PROJECT # 14-25

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

STATE OF NEW YORK — JOSEPH C. RIINA — 076201 — LICENSED PROFESSIONAL ENGINEER

Engineer: Joseph C. Riina, P.E.
NYS Lic. No. 64451

Revisions:

No.	Date	Comments
1	8-28-14	Revisions per comments from B&E.
2	10-1-15	Revisions per comments from B&E.
3	2-10-15	Revisions per comments from B&E.
4	3-11-15	Revisions per comments from B&E.
5	3-11-15	Revisions per comments from B&E.
6	3-23-15	Revisions per comments from B&E.
7	4-24-15	Revisions per comments from PCPD JH meeting.
8	4-27-15	Revisions per comments from PCPD JH meeting.
9	4-6-15	Revisions per comments from NYSDOT

SCALE: 1" = 30'
DRAWN BY: EL
DATE: 10/22/14

GRADING AND UTILITY PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Putnam County, New York
Village Of Cold Spring

SAFE DIG
Before You Dig, Drill or Blast!
CALL US TOLL FREE 811 or 1-800-962-7962
It's the law! Excavators must call before no less than two working days or more than ten days notice, but not more than ten days notice.
www.digalertnewyork.com

C - 106



LOCATION MAP
NOT TO SCALE

SITE DATA:

OWNER / DEVELOPER:	BUTTERFIELD REALTY LLC 3102 ROUTE 9D COLD SPRING, NY 10516
PROJECT LOCATION:	1756 PAULDING AVENUE COLD SPRING, NEW YORK, 10516
EXISTING ZONE:	B-4A, MEDICAL AND HEALTH CARE FACILITY MIXED USED R-1, ONE FAMILY RESIDENCE DISTRICT
TOWN TAX MAP DATA:	SECTION 49.5, BLOCK 3, LOT 45
SITE AREA :	5.797 ACRES (252,517.32SF)
SEWAGE FACILITIES:	PUBLIC SEWERS
WATER FACILITIES:	PUBLIC WATER FACILITIES

PROJECT SUMMARY:

1. BUILDING 1, ***MUNICIPAL OFFICE BUILDING*** - 6,000 SF FOOTPRINT, WITH 15,000 SF TOTAL (FIRST FLOOR RETAIL NOT TO EXCEED 6,000SF)
2. BUILDING 2, ***RETAIL OFFICE BUILDING*** - 6,000 SF FOOTPRINT, WITH 16,000 SF TOTAL (FIRST FLOOR RETAIL NOT TO EXCEED 6,000SF)
3. BUILDINGS 3 - 6, ***SENIOR CONDOMINIUM*** - 55 UNITS \
4. LOTS 1,2, & 3 - THREE (3) SINGLE FAMILY HOMES

9D 8402 1080	PERMIT IS SOUGHT FOR A SITE WHICH IS AT THIS MILE MARKER.

POSTED SPEED LIMIT: 30 MPH

LEGEND

- PROPERTY LINE / RIGHT OF WAY
- PROPOSED ROAD CENTERLINE
- PROPOSED CURB
- CONSERVATION EASEMENT LINE
- WORK ZONE AREA TO CONFORM WITH NYSDOT STANDARD SHEET ISSUE 619-60



NYS DOT WORK ZONE TRAFFIC CONTROL NOTES:

1. During Work Zone traffic Control for adjoining work locations shall not conflict *or interfere with one another.* The use of the NYSDOT Standard sheet 619-60 shall be used.

NYS DOT GENERAL CONSTRUCTION AND MPT NOTES:

1. All construction in the State R.O.W. shall be done in accordance with the latest edition of the New York State Standard Specifications and the local NYSDOT Region Engineer.
2. No work in the State R.O.W. shall commence until issuance of a Highway Work Permit by the NYSDOT. All work shall be done in conformance to the latest edition of the "NYSDOT Policy and Standards for the Design of Entrances to State Highways" and the "Requirements for the Design and Construction of Underground Utility Installations within the State Highway Right-Of-Way".
3. Maintenance and Protection of Traffic is the responsibility of the permittee. Any subcontractors working for the permittee must have a copy of the Highway Work Permit and set of approved plans on the site at all times and must be familiar with the traffic control requirements. It is strongly advised that a "tailgate" safety meeting with each work crew be initiated before the start of work.
4. It is the Contractor's responsibility to maintain safe passage for vehicle and pedestrians at all times.
5. Temporary Traffic Control Devices shall be clean and reflective and furnished, installed and maintained in conformance with the latest edition of the National Manual on Uniform Traffic Control Devices (MUTCD) and the NYS Supplement as published by the US DOT Federal Highway Administration throughout the duration of work.
6. Appropriate safety equipment shall be worn and used by any worker inside the State ROW including hard hats, high-visibility reflective vests and apparel meeting ANSI 107-2004 Class II standards and STOP/SLOW paddles.
7. At the start of work on the project, all work zone traffic control devices shall appear in "acceptable" condition. These devices shall not be allowed to fall below the "marginal" condition at any time during the life of the project. Faded and deteriorated panels and non-standard legends are not acceptable.
8. Flagger signs are to be used only when a flagger is actually present and visible to the motorist. They shall be covered or removed at all other times. Stop/Slow paddles are required.
9. No low-mounted signs shall be permitted, except for flexible panels meeting the current specification requirements.
10. No lane closures shall be allowed during the hours of 6:30 a.m. to 9:30 a.m. and 3:30 p.m. to 6:30 p.m. or on Sundays and Holidays.
11. If steel plates are utilized to safeguard an excavation in any paved area the plates must be: (1) recessed and pinned into the pavement; or (2) pinned with temporary asphalt ramps (max. slope 1/2 inch per foot) feathered along all sides of the plate to meet existing grade of adjoining roadway. If plates are used during winter months, additional signage ("Raise Plow - Road Plates Ahead") must be installed.

GENERAL NOTES:

1. All construction to be done in accordance with construction specifications and regulations of the Village of Cold Spring.
2. All survey and topographical information has been taken from surveys prepared by BADEY & WATSON SURVEYING & ENGINEERING, P.C. dated 07/10/2014.
3. All trench openings in State right of ways shall be restored. All materials shall be provided and installed in accordance with applicable sections of the NYSDOT Standard Specifications.
4. Pavement and shoulder removal, if required, shall be done in a manner that provides for proper restoration of the replacement sections. Straight, vertical cuts of the pavement will be required.
5. Sheeling, as may be required for the work of this project, shall be installed in accordance with NYSDOT Standard Specifications for materials and repair.
6. Pavement that becomes undermined shall be cut back, removed and restored in kind or as approved by the Region.
7. Backfilling shall be governed by Section 203 - Excavation and Embankment of the NYSDOT Standard Specs. The backfill for excavated areas shall be compacted to an approved density with suitable material and the upper surface maintained flush with the original surface.
8. All work on the project shall be performed in a workman like manner and shall be in accordance with the standards of the industry. The owner will be the sole judge of the acceptability of the work. Materials and work deemed unacceptable will be removed and redone at the sole cost and responsibility of the contractor.
9. The Contractor shall be responsible to protect his work and will be held responsible for consequential damages due to his activities. The Contractor shall be responsible to the Owner for the acts and omissions of his employees, subcontractors and their agents and employees, and any other persons performing any the work under a separate contract with the Contractor.
10. The Contractor shall provide the Town with a minimum of 72 hours notice prior to construction.
11. It is the Contractor's responsibility to call in a "Code 53" a minimum of 2 days but not more than 10 days prior to any excavation or construction of underground utilities.
12. It is the contractor's responsibility to properly shore existing utilities & existing improvements if required by construction.
13. It shall be the Contractor's responsibility to notify the the Town Engineer in advance of his work or as the Engineer deems appropriate.
14. All conditions, locations and dimensions shall be field verified by the Contractor and the Owner/Engineer notified in writing of any discrepancies prior to the start of work. The Owner/Engineer will evaluate the situation and modify the plan as necessary.
15. The Contractor shall supervise and direct the work using his best skill and attention. He shall be solely responsible for all construction means, methods, techniques, sequences and procedures and for coordinating all portions of the work under this contract.
16. The Contractor shall verify all substructures encountered during construction.
17. The Contractor shall secure & pay for a builders risk policy to cover the period of construction. The Engineer & Owner shall be named as additional insured. All contractors employed at the site shall be covered by workman's compensation.
18. All changes made to the plans shall be approved by the Engineer and any such changes shall be filed as amendments to the original Town Permit.
19. All written dimensions on the drawings shall take precedence over any scaled dimensions.
20. The Engineer whose seal appears hereon has not been retained for supervision of construction, subsequently, he is not responsible for construction and therefore assumes no responsibility for construction practices, procedures, and results therefrom.
21. The design engineer disclaims any liability for damage or loss incurred during or after construction.
22. The Engineer shall not be held responsible or held accountable for the integrity of any structures constructed or under construction prior to the approval of the plans.



OFFICE COPY

NOTE:
1. *THIS IS NOT A SURVEY.* ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY BADEY & WATSON SURVEYING & ENGINEERING, P.C. DATED 07/10/14, LAST REVISED 07/10/14. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

0 15 30 60
SCALE: 1"=30'-0"

SAFE DIG
Before You Dig, Drill or Blast!
Call811 DIG-LESS TOLL-FREE, 811 or 1-800-962-7962
For Industrial Code Rule 753 inquiries no less than two working days before, but not more than ten days before.
www.digsafelynewyork.com

C:\USERS\EL\STEPSCHTOONE\MY DOCUMENTS\LDD\PROJECTS\BUTTERFIELD ROAD\LDD\PLOTTING\ENGINEERING\CONCEPT\14-25 BUTTERFIELD SERVER\DRAWING\14-25 SITE PLAN REV4.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 f2f OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

PROJECT # 14-25

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4485 - Fax (914) 962-7386
www.sitedesignconsultants.com

STATE OF NEW YORK — JOSEPH C. RIINA — LICENSED PROFESSIONAL ENGINEER
Engineer: Joseph C. Riina, P.E.
NYS Lic. No. 64431

Revisions:		
No.	Date	Comments:
1	2-19-15	Parkland Schedule
2	3-13-15	Revisions per NYSDOT
3	4-13-15	Revisions per comments from BAL
4	4-23-15	Revisions per comments from PCDOH
5	4-27-15	Revisions per comments from BCTODR meeting
6	6-9-15	Revisions per comments from NYSDOT

SCALE: 1" = 30'
DRAWN BY: EL
DATE: 2/17/15

NYSDOT PERMIT & M.P.T PLAN

SITE/SUBDIVISION PLAN PREPARED FOR:
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

C-107



NYS DOT HORIZONTAL DIRECTIONAL BORING LOCATION PLAN

SCALE: 1" = 20'



SANITARY SEWER PROFILE STATION 6+50 TO STATION 7+85.87 PROFILE

SCALE: VERT. 1" = 4'
HORIZ. 1" = 40'

NOTE:
1. INSTALLATION OF OF SANITARY SEWER PIPE USING TRENCHLESS METHODS. PLEASE REFER SANITARY SEWER NOTES.



HALF SECTION ISOMETRIC OF BORE

NOTE:
1. SEE SECTION "A-A" CARBON STEEL ADDITIONAL INFORMATION.

2. CARRIER PIPE FOR PRESSURE APPLICATIONS (WATER MAINS & FORCE MAINS) SHALL HAVE FACTORY RESTRAINED JOINTS. CARRIER PIPE FOR GRAVITY SEWER SHALL HAVE RESTRAINED JOINTS AND MAY USE RESTRAINING GASKETS SUCH AS FIELD LOK, SURE STOP 350 OR OTHER APPROVED GASKETS.

3. CARRIER PIPE SHALL BE CLASS 350 OR 250 FOR WATER, AND SHALL BE CLASS 50 FOR SEWER.

BORE SIZING CHART *			
CARRIER PIPE SIZE	MIN. CASING SIZE	ROADWAYS MIN. WALL THICKNESS	RAILROADS MIN. WALL THICKNESS
4"	10"	0.188"	0.188"
6"	12"	0.25"	0.281"
8"	16"	0.25"	0.281"
12"	24"	0.25"	0.375"
16"	30"	0.312"	0.469"
18"	30"	0.312"	0.469"
24"	36"	0.375"	0.532"
30"	42"	0.500"	0.625"
36"	48"	0.500"	0.688"

*CONTRACTOR MAY SUBSTITUTE A LARGER SIZE CASING PIPE HAVING THE MIN. WALL THICKNESS SHOWN FOR SEWER MAINS. ALL ADDITIONAL COSTS SHALL BE INCLUDED IN THE UNIT PRICE BID FOR BORING AND JACKING.



SECTION "A-A" CARBON STEEL CARRIER PIPE BRACE

1. INSTALLATION SHALL BE DRY BORE AND JACKING OF SMOOTH WALL STEEL PIPE. JETTING OR WET BORING WITH WATER SHALL NOT BE ALLOWED.
2. SEE BORE SIZING CHART FOR CARRIER PIPE SIZE AND STEEL CASING SIZE , MIN. DIA. AND WALL THICKNESS.
3. CASING PIPE SHALL BE IN ACCORDANCE WITH ASTM A-53, GRADE B WITH A MINIMUM YIELD STRENGTH OF 35,000 PSI
4. EACH END OF ENCASEMENT TO BE PLUGGED WITH BRICK. ALL VOIDS OUTSIDE THE CASING PIPE SHALL BE COMPLETELY FILLED WITH 1:3 PORTLAND CEMENT GROUT AT SUFFICIENT PRESSURE TO INSURE NO SETTLEMENT OF ROADWAY/ RAILROAD. METHOD OF GROUTING SHALL BE AS APPROVED BY THE PERMITTING AGENCY.
5. IT IS RECOMMENDED THAT THE BORE BE ACCOMPLISHED BEFORE PIPE CONSTRUCTION BEGINS.
6. THE BORING SHALL BE PERFORMED FROM "UPSTREAM" TO "DOWNSTREAM" DIRECTION MAINTAINING THE CRITICAL DOWNSTREAM INVERT ELEVATION. SHOULD THE BORE NOT BE ON GRADE, A REVISED PLAN SHALL BE SUBMITTED TO FAYPWC FOR APPROVAL.
7. THE BORING OPERATION SHALL BE CONDUCTED IN A MANNER THAT THE FLOW OF TRAFFIC IS NOT IMPEDED OR IN SUCH A MANNER SO AS NOT TO CREATE A HAZARD.
8. IF AN OBSTRUCTION IS ENCOUNTERED DURING THE BORING OPERATION, THE AUGER SHALL BE WITHDRAWN THE EXCESS CASING PIPE CUT-OFF, CAPPED AND THE INTERIOR AND EXTERIOR VOIDS SHALL BE COMPLETELY FILLED W/1:3 PORTLAND CEMENT GROUT UNDER PRESSURE. NO SEPARATE PAYMENT FOR UNSUCCESSFUL BORES.
9. CONTRACTOR SHALL FIELD ADJUST AND INSTALL PROPER PIPE BRACES TO ACCOMPLISH GRADE AND INVERTS AS SHOWN ON THE DRAWINGS.
10. A MANUAL CONTROL STEERING HEAD OR OTHER GUIDANCE SYSTEM IS RECOMMENDED FOR BORES 30" DIAM. AND/OR LARGER AND FOR BORES EXCEEDING 100' IN LENGTH OR AS SPECIFIED.
11. SUBCONTRACTORS SHALL ADHERE TO ALL PERMIT REQUIREMENTS AND SHALL PROVIDE APPROVED INSURANCE CERTIFICATES AS REQUIRED.
12. CONTRACTOR SHALL EXECUTE AND PERFORM ALL REQUIREMENTS AND CONDITIONS STIPULATED BY THE PERMITTING AGENCY.
13. SEE DWG M.6 SHEET 1 OF 2 FOR ADDITIONAL INFORMATION.
14. CARRIER PIPE FOR PRESSURE APPLICATIONS (WATER MAINS & FORCE MAINS) SHALL HAVE FACTORY RESTRAINED JOINTS. CARRIER PIPE FOR GRAVITY SEWER SHALL HAVE RESTRAINED JOINTS AND MAY USE RESTRAINING GASKETS SUCH AS FIELD LOK, SURE STOP 350 OR OTHER APPROVED GASKETS.

OFFICE COPY

R-12

NYS DOT HORIZONTAL DIRECTIONAL BORING DETAIL

NOT TO SCALE

NEW YORK STATE DEPARTMENT OF TRANSPORTATION (NYSDOT) STANDARD DIRECTIONAL BORING GENERAL PLAN NOTES

1. ROAD TO BE KEPT CLEAN OF MUD AND DEBRIS AT ALL TIMES.
2. ROADSIDE DRAINAGE TO BE MAINTAINED AT ALL TIMES.
3. MATERIALS, EQUIPMENT, AND VEHICLES ARE NOT TO BE STORED OR PARKED WITHIN THE NEW YORK STATE HIGHWAY RIGHT-OF-WAY.
4. MAINTENANCE AND PROTECTION OF TRAFFIC MUST COMPLY WITH THE CURRENT NATIONAL MUTCD WITH NYS SUPPLEMENT, SECTION 649 OF THE CURRENT NYSDOT STANDARD SPECIFICATIONS, THESE PLANS AND AS ORDERED BY NYSDOT ASSISTANT RESIDENT ENGINEER. ON NYSDOT CONSTRUCTION PROJECT, MAINTENANCE AND PROTECTION OF TRAFFIC MUST COMPLY WITH THESE PLANS AND BE IN ACCORDANCE WITH THE NYSDOT CONTRACT DOCUMENTS AS DEEMED NECESSARY BY THE NYS ENGINEER-IN-CHARGE.
5. NOTIFY THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION'S ASSISTANT RESIDENT ENGINEER AT THE APPROPRIATE NUMBER, AS NOTED BELOW, THREE (3) WORK DAYS PRIOR TO WORKING WITHIN THE THE STATE ROGHT-OF-WAY

   PUTNAM COUNTY - MAUREEN VICKNER TERBUSH (845) 437-3331

   THE PERMITTEE IS ADVISED THAT THE NYSDOT IS NOW REVIEWING THE NYSDOT PLANS FOR ROAD WORK ON THE SHOULDER ALONG NYS HIGHWAY ROUTE 9D. THE WORK ZONE AREAS ALONG ROUTE 9D WILL NOT IMPACT ANY LANE CLOSURES. INCIDENTS, CONFLICTING WORK ZONES OR OTHER OTHER UNPLANNED EVENTS THAT RENDER THE HIGHWAY UNAVAILABLE FOR THE CLOSURE MAY RESULT IN A SHORT-TERM DISAPPROVAL OF THE CLOSURE UNTIL THE SITUATION HAS BEEN RESOLVED.
6. NOTIFY THE NYSDOT SIGNAL MAINTENANCE FACILITY FIVE (5) DAYS PRIOR TO WORKING WITHIN THE 350' OF A SIGNALIZED INTERSECTION. NOTIFY DIG SAFELY NEW YORK TWO (2) DAYS PRIOR TO DIGGING, DRILLING OR BLASTING AT 811 FOR A UTILITY STAKE OUT
7. ALL MATERIALS WITHIN THE THE STATE RIGHT-OF-WAY MUST COMPLY WITH THE CURRENT NEW YORK STATE DEPARTMENT OF TRANSPORTATION SPECIFICATIONS ALONG WITH ANY APPROPRIATE CURRENT NYS DEPARTMENT OF TRANSPORTATION STANDARD SHEETS
8. QUALITY CONTROL OF ASPHALT CONCRETE SHALL MEET THE REQUIREMENTS OF SECTION 401 OF THE STANDARD SPECIFICATION. ALL ASPHALT PRODUCED AS PART OF SECTION 401 SHALL BE PAID AT A FINAL QUANTITY ADJUSTMENT FACTOR OF 1.0. ASPHALT COURSE DEPTHS SHOWN ON THE PLANS ARE COMPACTED DEPTHS.
9. NO NIGHT WORK SHALL BE ALLOWED UNLESS APPROVED PRIOR TO START OF PROJECT. ADDITIONAL MAINTENANCE AND PROTECTION OF TRAFFIC MAY BE REQUIRED INCLUDING THE ADDITION OF REFLECTIVE MATERIALS AND CLOTHING.
10. HAZARDOUS WASTE NOTIFICATION - THE PERMTTEE ACCEPTS THE RIGHT-OF-WAYOF THE STATE HIGHWAY IN ITS "AS IS" CONDITION. THE DEPARTMENT OF TRANSPORTATION MAKES NO REPRESENTATIVE AS TO THE ABSENCE OF UNDERGROUND TANKS, STRUCTURES, FEATURES OR SIMILAR IMPEDIMENTS TO THE COMPLETION OF WORK COMPLETED HEREUNDER/ SHOULD PERMITTEE FIND SOME PREVIOUSLY UNKNOWN UNDERGROUND IMPEDIMENTS TO ITS WORK, THE DEPARTMENT OF TRANSPORTATION SHALL HAVE NO OBLIGATION TO CURE, REMOVE, REMEDY, OR OTHERWISE DEAL WITH SUCH PREVIOUSLY UNKNOWN UNDERGROUND IMPEDIMENTS. THE PERMITTEE IS REQUIRED TO REMOVE, MODIFY, OR OTHERWISE DEAL WITH SUCH UNDERGROUND TANKS, STRUCTURES, FEATURES OR IMPEDIMENTS IN A MANNER WHICH MEETS ACCEPTABLE ENGINEERING PRACTICE AND IS APPROVED BY THE DEPARTMENT OF TRANSPORTATION.
11. CULVERT PIPES WHICH ARE REPLACED WITHIN THE NYSDOT RIGHT-OF-WAYSHALL BE INSTALLED WITH WITH CMP PIPES.
12. CONTRACTOR IS RESPONSIBLE FOR RESTORING ALL DISTURBED SIGNS, IN ORIGINAL OR BETTER CONDITION, TO THEIR ORIGINAL LOCATION WITH THE CORRECT SIGNAGE ON ALL VILLAGE, COUNTY, AND STATE ROADS.

NYSDOT REGION 8 EXCAVATION SUPPORT SYSTEM REQUIREMENTS

1. ANY EXCAVATION 5 FEET OR MORE IN DEPTH SHALL UTILIZE A SHIELDS AND SHORING OR SHEETING SYSTEM WHICH PROVIDES DIRECT CONTACT AND SUPPORT OF THE EXCAVATION SIDES. THE SHEETING SYSTEM SHALL ACCOMMODATE ANY ASSOCIATED SURCHARGE LOADS AND SHALL BE SUBMITTED TO NYSDOT'S REGIONAL GEOTECHNICAL ENGINEER FOR REVIEW AND APPROVAL PRIOR TO PERMIT ISSUANCE.
2. A SLOPING (LAYBACK) OPTION WILL NOT BE ALLOWED.
3. SHIELDS AND SHORING PR SHEETING SYSTEM REQUIREMENTS DO NOT PERTAIN TO TEST PITS WHICH A 18" OR LEES IN DIAMETER.

GENERAL NOTES FOR UTILITY WORK AROUND EXISTING TREES

1. WHEN TRENCHING WITHIN 10 FEET OF EXISTING TREES 6 INCHES AND OVER D.B.H., VEGETATION PROTECTION BARRIER SHALL BE INSTALLED AT THE LIMITS OF WORK TO A MINIMUM OF 4 FEET FROM TREE CENTER.
2. WHEN TRENCHING NEXT TO TREES, AND ROOTS 2 INCHES OR LARGER MUST BE CUT, SHOVEL BY HAND NEAR ROOTS AND SAW THE ROOTS. ACCIDENTLY BROEKN ROOTS SHALL BE SAWN 2 INCHES BEHIND THE RAGGED END.
3. WHEN TRENCHING NEXT TO TREES, DO NOT PILE SOIL BETWEEN THE TRENCH AND THE TREE. PLACE SOIL ON THE FAR SIDE OF THE TRENCH. WHEN THIS IS NOT POSSIBLE, PLACE SOIL ON PLYWOOD, A TARP OR A 2 INCH LAYER OF MULCH.
4. THE CONTRACTOR SHALL TUNNEL UNDER TREES WHEN THE EDGE OF THE TRENCH WILL FALL WITHIN 8 FEET OR CLOSER TO TREES 6 INCHES AND OVER D.B.H. THE TUNNELING SHALL BE A MINIMUM OF 4 FEET LONG ON EACH SIDE OF THE TREE AND A MINIMUM OF 3 FEET DEEP. TUNNELING SHALL BE BY MEANS OF JACKING, PUSHING, OR OTHER METHODS APPROVED BY THE ENGINEER.
5. ANY TREE WHOSE ROOTS MUST BE CUT OR WHERE TUNNELING TAKES PLACE; FERTILIZER SHALL BE APPLIED USING A METHOD NO.1 (HOLES MADE IN SOIL 58 INCHES DEEP AND 16 INCHES APART IN THE OUTER TWO-THIRDS OF THE CANOPY), FERTILIZER TYPE NO. 3 SHALL BE APPLIED AT THE RATE OF 1 POUND PER 6 INCHES D.B.H. AND EVENLY DISTRIBUTED IN THE LOWER 12 INCHES OF EACH HOLE.
6. FERTILIZER SHALL BE APPLIED IN THE SPRING OF LATE FALL. IF APPLIED EARLY FALL, USE A FERTILIZER VOID OF ANY OF ANY NITROGEN SUCH AS 0-12-12.

SANITARY SEWER NOTES

1. THE SANITARY SEWER PIPE MATERIAL TO BE USED FOR TRENCHLESS INSTALLATION SHALL BE DECIDED BY THE VILLAGE OF COLD SPRING. THE TRENCH INSTALLATION METHOD TO BE USED SHALL BE THE METHOD MOST APPROPRIATE FOR THE PIPE MATERIAL THAT IS SELECTED. REFER TO THE TECHNICAL SPECIFICATIONS FOR THE ALTERNATE PIPE MATERIALS AND TRENCHLESS INSTALLATION METHODS.
2. SANITARY SEWER PIPE MATERIAL INSTALLED IN THESE AREAS SHALL BE COMPATIBLE WITH PIPE MATERIAL SELECTED FOR TRENCHLESS INSTALLATION, AS FOLLOWS:
   - 2.1 SDR 35 PVC PIPE SHALL BE USED IF SDR 35 PVC RESTRAINED JOINT PIPE WITH STEEL CASING IS USED FOR TRENCHLESS INSTALLATION VIA THE BORING AND PIPE-JACKING TECHNIQUE.
   - 2.2 SDR 35 PVC PIPE SHALL BE USED FOR TRENCHLESS INSTALLATION VIA THE HORIZONTAL DIRECTIONAL DRILLING TECHNIQUE.

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Seal/Signature: STATE OF NEW YORK — JOSEPH C. RITINA — LICENSED PROFESSIONAL ENGINEER
Joseph C. Ritina, P.E.
NYS Lic. No. 64431

Revisions:

No.	Date	Comments
1.	2-19-15	Preform Schedule
2.	3-13-15	Revisions per NYSDOT
3.	4-23-15	Revisions per comments from R&A
4.	4-23-15	Revisions per comments from PCDOH
5.	4-27-15	Revisions per comments from PCDOH meeting
6.	6-9-15	Revisions per comments from NYSDOT

SCALE: 1" = 20'
DRAWN BY: EL
DATE: 2/17/15

NYSDOT
HDD BORE PLAN

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Putnam County, New York
Village Of Cold Spring

C - 108

C:\USERS\EL\STEVE'S DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\CAD-14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REV 6.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\ELISTER\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\C3D-14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REV.5.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



LOCATION MAP

NOT TO SCALE



DRIVEWAY 1 - SIGHT DISTANCE LOOKING EAST PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'

DRIVEWAY 2 - SIGHT DISTANCE LOOKING WEST PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



DRIVEWAY 2 - SIGHT DISTANCE LOOKING EAST PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



DRVIEWAY 3 - SIGHT DISTANCE LOOKING WEST PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



DRIVEWAY 3 - SIGHT DISTANCE LOOKING EAST PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



Note:

1. The design speed was used to develop site distances shown are based on a prevailing speed of 30 MPH in accordance with Table 2-1 of "A Policy on Geometric Design of Highways and Streets, 2004, Fifth Edition".
2. Sight distances were obtained from AASHTO, "A Policy on Geometric Design of Highways and Streets, 2004, Fifth Edition".

OFFICE COPY

SCALE: 1"=30'-0"

0 15 30 60

Call 811 Before You Dig, Drill or Blast!
SAFE DIG
CALL US TOLL FREE: 811 or 1-800-962-7962
It's fast, it's free and it's the law!
Non-law members may also call directly.
Non-law members may include, but not limited to: Municipalities, water districts, sewer districts, private companies, railroads, etc.
www.digalertnewyork.com

C-109

SITE/SUBDIVISION PLAN
PREPARED FOR

Butterfield Redevelopment Project

1756 NYS ROUTE 9D

Village Of Cold Spring — Putnam County, New York

SIGHT DISTANCE PLAN AND PROFILES

SCALE: 1" = 30'

DRAWN BY: EL

DATE: 6/8/15

Revisions:

No.	Date	Comments:
1	6-9-15	Revisions per comments from NYSDOT

Engineer:
STATE OF NEW YORK
JOSEPH CARLO RIINA
No. 64431
LICENSED PROFESSIONAL ENGINEER
Joseph C. Riina, P.E.
NYS Lic. No. 64431

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED



TREE PLANTING NTS



NOTES:
1. PLACE PLANTS ON FIRMLY TAMPED SOIL MIXTURE. PLANTS THAT SETTLE SHALL BE RE-PLANTED.
2. SET CROWN OF ROOT BALL LEVEL WITH FINISH GRADE.
3. MAINTAIN MINIMUM OF 4" PLANTING MIXTURE BELOW EACH INDIVIDUAL PLANT.
4. MULCH ENTIRE AREA OF GROUNDCOVER OR PERENNIALS.
5. MULCH CAREFULLY AROUND EACH PLANT. DO NOT COVER CROWNS OF PLANTS WITH MULCH.

GROUNDCOVER/ PERENNIAL PLANTING BED NTS



PLANT BED EDGE NTS

SHRUB PLANTING NTS



REFUSE ENCLOSURE NTS



STONE WALL NTS



NOTES:
1. ALL STAKES SHALL BE DRIVEN OUTSIDE THE EDGE OF THE ROOT BALL.
2. WIRE OR CABLE SIZES SHALL BE AS FOLLOWS: -TREES UP TO 2.5" CALIPER - 14 GAUGE -TREES 2-1/2" TO 3" CALIPER - 12 GAUGE
3. TIGHTEN WIRE OR CABLE ONLY ENOUGH TO KEEP FROM SLIPPING. ALLOW FOR SOME TRUNK MOVEMENT. PLASTIC HOSE SHALL BE LONG ENOUGH TO ACCOMMODATE 1-1/2" OF GROWTH AND BUFFER ALL BRANCHES FROM THE WIRE.
4. TUCK ANY LOOSE ENDS OF THE WIRE OR CABLE INTO THE WIRE WRAP SO THAT NO SHARP WIRE ENDS ARE EXPOSED.
5. INSTALL THREE (3) WIRES PER TREE, SPACED EVENLY AROUND THE TRUNK.
6. REMOVE STAKES AT THE END OF THE FIRST GROWING SEASON AFTER PLANTING.

TREE STAKING NTS



6 FT LONG GARDEN BENCH



SCREEN FENCE

THIS DRAWING AND DETAILS ON IT, AS AN INSTRUMENT OF SERVICE, IS THE PROPERTY OF THE LANDSCAPE ARCHITECT AND MAY BE USED FOR THIS SPECIFIC PROJECT AND SHALL NOT BE LOANED, COPIED OR REPRODUCED WITHOUT CONSENT OF THE LANDSCAPE ARCHITECT.

CONSULTANTS:

REVISIONS:

NO	DATE	REVISION	BY
2	1-9-15	REVISIONS PER B&L REVIEW COMMENTS	BG
1	12-3-14	REVISIONS PER B&L REVIEW COMMENTS	BG



PROFESSIONAL SEAL:



PREPARED BY:

Blades & Goven
LANDSCAPE ARCHITECTS
40 THORPE STREET
FAIRFIELD CT 06824
PHONE: 203-254-8320
FAX: 203-254-8426

PROJECT TITLE:

BUTTERFIELD SITE

1756 NEW YORK ROAD
TOWN OF COLD SPRING
PUTNAM COUNTY
NEW YORK

DRAWING TITLE:

LANDSCAPE PLAN

SCALE: 1'=30'

DATE: 10-22-14

DRAWN BY: BG

PROJECT NO: XX-XX

SHEET:

OFFICE COPY

L-401



PLANT LIST

SYMBOL	QTY	BOTANICAL NAME	COMMON NAME	SIZE	ROOT	NOTES
TREES						
ARB'	6	ACER RUBRUM 'BOWHALL6'	BOWHALL MAPLE	3-31/2" CAL	B+B	SINGLE STEM
ARCG'	13	ACER RUBRUM 'OCTOBER GLORY'	OCTOBER GLORY MAPLE	3-31/2" CAL	B+B	SINGLE STEM
PA 'B'	1	PLATANUS ACERIFOLIA 'BLOODGOOD'	BLOODGOOD PLANE TREE	3-31/2" CAL	B+B	SINGLE STEM
CB 'F'	4	CARPINUS BETULUS 'FASTIGIATA'	COLUMNAR NORWAY SPRUCE	8-10 FT HT	B+B	SINGLE STEM
PXT	8	PRUNUS YOSHINO	YOSHINO CHERRY	8-10 FT HT	B+B	
CC	12	CERCIS CANADENSIS	REDBUD	8-10 FT HT	B+B	
PO	1	PICEA OMORIKA	SERBIAN SPRUCE	8-10 FT HT	B+B	
PFF'	26	PICEA PUNGENS FASTIGIATA	FASTIGIATE BLUE SPRUCE	8-10 FT HT	B+B	
JT	4	JUNIPERUS CHINENSIS TORULOSA	HOLLYWOOD JUNIPER	8-10 FT HT	B+B	
TP 'GG'	44	THUJA PLICATA 'GREEN GIANT'	GREEN GIANT ARBORVITAE	8-10 FT HT	B+B	
PAC	30	PICEA ABIES CUPRESSINA	COLUMNAR NORWAY SPRUCE	8-10 FT HT	B+B	
HYD ES	12	HYDRANGEA MACROPHYLLA 'BAILMER'	ENDLESS SUMMER HYDRANGEA	18" - 24" SPR.	B+B	
HYD	38	HYDRANGEA M. 'TWIST 4 SHOUT'	LACECAP HYDRANGEA	18" - 24" SPR.	B+B	
IC 'S'	52	ILEX X CRENATA 'STEED6'	STEED6 UPRIGHT HOLLY	36" HT	B+B	
ICG	81	ILEX CRENATA CONVEXA	DWARF JAPANESE HOLLY	2 GAL.	CAN	
IGC	22	ILEX GLABRA COMPACT	COMPACT INKBERRY	2 GAL.	CAN	
MP	2	MYRICA PENSYLVANICA	BAYBERRY	5 GAL	CAN	
RKO R	41	ROSA 'RADRAZZ1'	RED KNOCK OUT ROSE	3 GAL.	CAN	
RKO P	73	ROSA 'RADCON'	PINK KNOCK OUT ROSE	3 GAL.	CAN	
S 'LP'	11	SPIRAEA JAPONICA 'LITTLE PRINCESS'	LITTLE PRINCESS SPIREA	3 GAL.	CAN	
CXC	15	CARYOPTERIS CLANDONENSIS 'DARK KNIGHT'	BLUE MIST SPIREA	18-24".	CAN	
CM	300	CAREX MORROWII 'ICE DANCE'	VARIEGATED SEDGE	1 GAL.	CAN	18" O.C.
HSD	35	HEMEROCALLIS 'STELLA D'ORO'	STELLA D'ORO DAYLILY	1 GAL.	CAN	18" O.C.
HAK	144	HAKONECHLOA MACRA AUREOLA	JAPANESE HAKONE GRASS	1 GAL.	CAN	24" O.C.
LIR	1335	LIRIOPE MUSCARI	LILLY TURF	1 GAL.	CAN	15" O.C.
PAH	350	PENNISETUM ALOPECUROIDES 'HAMELN'	DWARF FOUNTAIN GRASS	1 GAL.	CAN	18" O.C.
RFG	185	RUDBECKIA FULGIDA 'GOLDSTRUM'	BLACK EYED SUSAN	1 GAL.	CAN	18" O.C.
NEP	110	NEPETA FAASSENII 'SIX HILLS GIANT'	CATMINT VARIETY	1 GAL.	CAN	18" O.C.
MSG	24	MISCANTHUS SINENSIS 'GRACILLIMUS'	MAIDEN GRASS	1 GAL.	CAN	
CA 'KF'	230	CALAMAGROSIS KARL FOSTER'	FEATHER REED GRASS	2 GAL.	CAN	24" O.C.
RM	30	HYBISCUS MASCHEUTOS	ROSE MALLOW	#2	CAN	
GF	40	LIATRIS SPICATA	GAY FEATHER	#2	CAN	
ECH	150	ECHINACEA PURPUREA 'MAGNUS'	CONEFLOWER	#2	CAN	
H 'SS'	8	HOSTA 'SUM AND SUBSTANCE'	SUM AND SUBSTANCE HOSTA	1 GAL.	CAN	
JPW	15	EUPATORIUM PURPUREUM	JOE PYE WEED	#2	CAN	

WILDFLOWER MEADOW MIX BY NEW ENGLAND WETLAND PLANTS - SEED AT 23LBS /ACRE
SPECIES: CREEPING RED FESCUE, (FESTUCA RUBRA), CANADA WILD RYE, (ELYMUS CANADENSIS), ANNUAL RYEGRASS, (LOLIUM MULTIFLORUM), PERENNIAL RYEGRASS, (LOLIUM PERENNE), BLUE GRAMA, (BOUTELOUA GRACILIS), LITTLE BLUESTEM, (SCHIZACHYRIUM SCOPARIUM), INDIAN GRASS, (SORGHASTRUM NUTANS), ROUGH BENTGRASS, (AGROSTIS SCABRA), UPLAND BENTGRASS, (AGROSTIS PERENNANS).







UNAUTHORIZED USE, MANUFACTURE OR REPRODUCTION IN WHOLE OR IN PART IS PROHIBITED. DRAWING, DESIGN AND OTHER DISCLOSURES ARE THE PROPERTY OF
SENTRY ELECTRIC LLC
FREEPORT, N.Y. 11520

DATE	11-11-2014
DRAWN	M.S.
ENGINEER	S.K.

Sentry Electric LLC
185 Buffalo Avenue, Freeport, New York 11520
Tel 516-379-4660 Fax 516-378-0624
www.sentrylighting.com E-mail: info@sentrylighting.com

Butterfield Square

SCALE 1= 50	DWG NO. 14-218-L101	REV
SHEET 1 OF 4		

THIS DRAWING AND DETAILS ON IT, AS AN INSTRUMENT OF SERVICE, IS THE PROPERTY OF THE LANDSCAPE ARCHITECT AND MAY BE USED FOR THIS SPECIFIC PROJECT AND SHALL NOT BE LOANED, COPIED OR REPRODUCED WITHOUT CONSENT OF THE LANDSCAPE ARCHITECT.

CONSULTANTS:

REVISIONS:

DATE	REVISION	BY
1-9-15	REVISIONS PER B&L REVIEW COMMENTS	BG
12-3-14	REVISIONS PER B&L REVIEW COMMENTS	BG

NORTH

0 15' 30' 60'

SCALE: 1" = 30'

PROFESSIONAL SEAL:



PREPARED BY:

Blades & Goven
LANDSCAPE ARCHITECTS
60 THORPE STREET
FAIRFIELD, CT 06824
PHONE: 203-254-8530
FAX: 203-254-8626

PROJECT TITLE:

BUTTERFIELD SITE

1756 NEW YORK ROAD
TOWN OF COLD SPRING
PUTNAM COUNTY
NEW YORK

DRAWING TITLE:

SITE LIGHTING PLAN

SCALE:	1'=30'
DATE:	10-22-14
DRAWN BY:	BG
PROJECT NO:	XX-XX
SHEET:	L-402

OFFICE COPY

STATISTICS

Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
Parking 1	+	1.5 fc	4.1 fc	0.2 fc	20.5:1	7.5:1
Parking 2	+	1.0 fc	2.6 fc	0.3 fc	8.7:1	3.3:1
Parking 3	+	0.7 fc	2.2 fc	0.3 fc	7.3:1	2.3:1
Parking 4	+	1.2 fc	3.0 fc	0.3 fc	10.0:1	4.0:1
Parking 5	+	1.1 fc	2.5 fc	0.4 fc	6.3:1	2.8:1
Parking 6	+	1.1 fc	2.3 fc	0.5 fc	4.6:1	2.2:1
Parking 7	+	1.5 fc	3.0 fc	0.4 fc	7.5:1	3.8:1
Trespass 1	+	0.6 fc	1.4 fc	0.1 fc	14.0:1	6.0:1
Trespass 2	+	0.4 fc	1.0 fc	0.0 fc	N / A	N / A
Trespass 3	+	0.3 fc	0.7 fc	0.0 fc	N / A	N / A
Trespass 4	+	0.2 fc	0.4 fc	0.0 fc	N / A	N / A
W1	+	1.5 fc	2.9 fc	0.4 fc	7.3:1	3.8:1
W7	+	1.6 fc	2.7 fc	0.5 fc	5.4:1	3.2:1
W8	+	1.2 fc	2.9 fc	0.2 fc	14.5:1	6.0:1
W9	+	1.7 fc	3.2 fc	0.4 fc	8.0:1	4.3:1
W10	+	1.6 fc	2.8 fc	0.0 fc	N / A	N / A
W11	+	0.4 fc	2.0 fc	0.1 fc	20.0:1	4.0:1
W16	+	1.3 fc	2.8 fc	0.0 fc	N / A	N / A

LUMINAIRE SCHEDULE

Symbol	Label	Qty	Catalog Number	Description	Lamp	File	Lumens	LLF	Watts
□	BOL	6	SAL-B-BOL-11LEDXSM-1300-C-0.7A	LED Bollard	XSM-80XX-1300	SAL-W-BOL-11LEDXSM-1300-C-.7A absolute.ies	Absolute	0.91	13
○ +	BC	4	SBCA3-(4)32LEDV18-1.05A-840-2RSP3-GR	Pole mounted Bishops Crook, Type 3	Vero 18, 840	sen838873 SBCA3-(4)32LEDV18-1.05A-840-2RSP3-GR.IES	Absolute	0.91	135.7
□	POST	19	SMAL-49LEDHBM-740-SPR3	Pole mounted post-top, Type 3	Fortimo LED HBMI 6000 49W /740	SMAL-54LEDHBM-SPR3.ies	Absolute	0.91	54
□ +	W-MNT	30	SMAL-49LEDHBM-740-SPR3	Wall mounted post-top, Type 3	Fortimo LED HBMI 6000 49W /740	SMAL-54LEDHBM-SPR3.ies	Absolute	0.91	54



SBCA3 Series luminaire shown with 18 ft. aluminum pole, catalog # SAL-IVP, and LYN30 Arm.



SMAL Series luminaire shown with 12 ft. aluminum pole, catalog # SAL-4H-F.



SAL-B-BOL Bollard



SMAL Series luminaire shown with wall mount bracket, catalog # SAL-WB.

UNAUTHORIZED USE, MANUFACTURE OR REPRODUCTION IN WHOLE OR IN PART IS PROHIBITED. DRAWING, DESIGN AND OTHER DISCLOSURES ARE THE PROPERTY OF
SENTRY ELECTRIC LLC
FREEPORT, N.Y. 11520

Sentry Electric LLC
185 Buffalo Avenue, Freeport, New York 11520
Tel 516-379-4660 Fax 516-378-0624
www.sentrylighting.com E-mail: info@sentrylighting.com

Butterfield Square

DATE	1-9-2015		
DRAWN	M.S.	SCALE 1= 50	DWG NO. 14-218-L104 REV
ENGINEER	S.K.	SHEET 2 OF 3	

UNAUTHORIZED USE, MANUFACTURE OR REPRODUCTION IN WHOLE OR IN PART IS PROHIBITED. DRAWING, DESIGN AND OTHER DISCLOSURES ARE THE PROPERTY OF
SENTRY ELECTRIC LLC
FREEPORT, N.Y. 11520

Sentry Electric LLC
185 Buffalo Avenue, Freeport, New York 11520
Tel 516-379-4660 Fax 516-378-0624
www.sentrylighting.com E-mail: info@sentrylighting.com

Butterfield Square

DATE	1-9-2015		
DRAWN	M.S.	SCALE 1= 50	DWG NO. 14-218-L104 REV
ENGINEER	S.K.	SHEET 3 OF 3	

THIS DRAWING AND DETAILS ON IT, AS AN INSTRUMENT OF SERVICE, IS THE PROPERTY OF THE LANDSCAPE ARCHITECT AND MAY BE USED FOR THIS SPECIFIC PROJECT AND SHALL NOT BE LOANED, COPIED OR REPRODUCED WITHOUT CONSENT OF THE LANDSCAPE ARCHITECT.

CONSULTANTS:

REVISIONS:

DATE	REVISION	BY
1-9-15	REVISIONS PER B&L REVIEW COMMENTS	BG
12-3-14	REVISIONS PER B&L REVIEW COMMENTS	BG

NORTH

0 15' 30' 60'

SCALE: 1" = 30'

PROFESSIONAL SEAL:



PREPARED BY:

Blades & Goven
LANDSCAPE ARCHITECTS
60 THORPE STREET
FAIRFIELD, CT 06824
PHONE: 203-254-8550
FAX: 203-254-8426

PROJECT TITLE:

BUTTERFIELD SITE

1756 NEW YORK ROAD
TOWN OF COLD SPRING
PUTNAM COUNTY
NEW YORK

DRAWING TITLE:

SITE LIGHTING INFORMATION

SCALE: 1'=30'

DATE: 10-22-14

DRAWN BY: BG

PROJECT NO: XX-XX

SHEET:

L-403

OFFICE COPY

ALIGNMENT C PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



BUTTERFIELD ROAD PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



ALIGNMENT A PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



DRIVEWAY TO BLDG 6 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



ALIGNMENT B PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



OFFICE COPY

SCALE: 1"=30'-0"
0 15 30 60

SAFE DIG
Before You Dig, Drill or Blast!
Call 811 or 1-800-962-7962
NY Underground Locating Service
Three business working days notice, but not more

C-301	SITE/SUBDIVISION PLAN PREPARED FOR Butterfield Redevelopment Project 1756 NYS ROUTE 9D Village Of Cold Spring — Putnam County, New York	DRIVEWAY PROFILES

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

Revisions:

No.	Date	Comments:
1	12-3-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Parking Schedule
5	3-13-15	Revisions per NYSDOT
6	3-23-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from PCDOH
8	4-27-15	Revisions per comments from PCDOH meeting

Engineer:
STATE OF NEW YORK — JOSEPH CARLO RIINA — LICENSED PROFESSIONAL ENGINEER — NO. 64431
Joseph C. Riina, P.E.
NYS Lic. No. 64431

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

C:\USERS\ELISTER\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CADIC3D-14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REV.5.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

Sewer Main PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



Water Main PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



WATERMAIN PROFILE Watermain to Hydrant

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



OFFICE COPY

C - 302

SITE/SUBDIVISION PLAN
PREPARED FOR

Butterfield Redevelopment Project

1756 NYS ROUTE 9D

Village Of Cold Spring — Putnam County, New York

UTILITY PROFILES

SCALE: N.T.S

DRAWN BY: EL

DATE: 10/22/14

Revisions:

No.	Date	Comments:
1	12-3-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Parking Schedule
5	3-13-15	Revisions per NYSDOT
6	3-23-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from PCDOH
8	4-27-15	Revisions per comments from PCDOH meeting

Engineer:

STATE OF NEW YORK ★ JOSEPH CARLO RIINA ★ LICENSED PROFESSIONAL ENGINEER ★ NO. 64431

Joseph C. Riina, P.E.
NYS Lic. No. 64431

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

C:\USERS\ELISTER\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\C3D-14-25 BUTTERFIELD REDEVELOPMENT\14-25 SITE PLAN REV.5.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

RWH 2 to DMH-5 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



DI-4 TO EXISTING CB 4 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



CB-10 to DMH-8 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



CB-1 TO EXISTING CB 2 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



CB-5 TO CB-4 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



RWH-1 TO EX CB 3 PROFILE

SCALE: VERT. 1" = 5'
HORIZ. 1" = 50'



OFFICE COPY

C - 303	SITE/SUBDIVISION PLAN PREPARED FOR **Butterfield Redevelopment Project** 1756 NYS ROUTE 9D Village Of Cold Spring — Putnam County, New York	**STORM WATER PROFILES**

SCALE: N.T.S
DRAWN BY: EL
DATE: 10/22/14

Revisions:

No.	Date	Comments:
1	12-3-14	Revisions per comments from B&L
2	1-9-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Parking Schedule
5	3-13-15	Revisions per NYSDOT
6	3-23-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from PCDOH
8	4-27-15	Revisions per comments from PCDOH meeting

Engineer:
STATE OF NEW YORK — JOSEPH CARLO RIINA — LICENSED PROFESSIONAL ENGINEER — NO. 64431
Joseph C. Riina, P.E.
NYS Lic. No. 64431

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED



PERSPECTIVE VIEW



SECTION



PLAN VIEW: JOINING SECTIONS



ELEVATION



SECTION

SYMBOL

NOTES:
1. Filter cloth to be fastened securely to post: steel either t or u type or 2" hardwood posts at top and mid section.
2. When two sections of filter cloth adjoin each other they shall be overlapped by 6 inches and folded. Filter cloth shall be mirafi 100x, stabilinka t140n or approved equal
3. Maintenance shall be performed as needed and material removed when "bulges" develop in the silt fence.
4. Excavate 4 inch trench along the lower perimeter of the site.
5. Unroll a section at a time and position the post against the back (downstream) wall of the trench (net side away from direction of flow).
6. Drive the post into the ground until the netting is approximately 2 inches from the trench bottom.
7. Lay the toe-in flap of fabric onto the undisturbed bottom of the trench, backfill the trench and tamp the soil. Steeper slopes require an intercept trench.
8. Join sections as shown above.

E-1 SILT FENCE DETAIL
NOT TO SCALE



ELEVATION

DIKE-A
(15 Acres or Less)
A - DIKE HEIGHT = 18"
B - DIKE WIDTH = 24"
C - FLOW WIDTH = 4"
D - FLOW DEPTH = 8"



CONSTRUCTION SPECIFICATIONS:
1. All dikes shall be compacted by earth-moving equipment.
2. All dikes shall have positive drainage to an outlet.
3. Top width may be wider and side slopes be flatter if desired to facilitate crossing by construction traffic.
4. Field location should be adjusted as needed to utilized a stabilized safe outlet.
5. Earth dikes shall have an outlet that functions with minimum of erosion. Runoff shall be conveyed to a sediment trapping device such as a sediment basin or trap where either the dike channel or the drainage area above the dike are not adequately stabilized.
6. Stabilization shall be: (a) in accordance with standard specifications for seed and straw mulch if not in seeding season. (b) flow channel as per the chart below.

FLOW CHANNEL STABILIZATION

TYPE OF TREATMENT	TYPE OF GRADE	DIKE - A
1	0.5 - 3.0%	seed & straw mulch

A) Stone to be 2 inch stone or recycled concrete equivalent. In a layer at least 3 nches in thickness and be pressed into the soil with construction equipment.
B) rip-rap to be 4-8 inches in a layer at least 8 inches thickness and pressed into the soil.
C) approved equivalents can be substituted for any of the above materials.
7. Periodic inspection and required maintenance must be provided after each rain fall.

E-4 EARTH DIKE DETAIL
NOT TO SCALE



INSTALLATION NOTES:
1. Pit dimensions are variable.
2. The standpipe should be a perforated 12" to 24" diameter corrugated metal, PVC or HDPE pipe.
3. A base of 2" clean aggregate should be placed in the pit to a depth of 12". After installing the standpipe, the pit surrounding the standpipe should then be backfilled with 2" aggregate.
4. The standpipe should extend 12" - 18" above the lip of the pit.
5. If discharge will be pumped directly to a storm drainage system, the standpipe should be wrapped with filter fabric before installation. If desired, 1/4" - 1/2" hardware cloth may be placed around the standpipe, prior to attaching the filter fabric, this will increase the rate of water seepage into the pipe.
6. The contractor shall comply with all prevailing laws for safety during trenching.

E-8 DEWATERING PIT DETAIL
NOT TO SCALE



INSTALLATION NOTES:
1. Area under embankment shall be cleared, grubbed, and stripped of any vegetation and root mat. The pool area shall be cleared as well.
2. The fill material for the embankment shall be free of roots or other woody vegetation as well as over sized stones, rocks, organic material and other questionable material. The embankment shall be compacted by traversing with equipment while it is being constructed.
3. Sediment shall be removed and trap restored to its original dimensions when the sediment has accumulated to 1/2 the design depth of the trap. Removed sediment shall be deposited in a suitable area and in such a manner that it will not erode.
4. The structure shall be inspected after each rain and repairs made as needed.
5. Construction operations shall be carried out in such a manner that erosion and water pollution is minimized.
6. The structure shall be removed and the area stabilized when the drainage area has been properly stabilized.
7. All cut and fill slopes shall be 1 : 2 or flatter.

E-9 STONE OUTLET SEDIMENT TRAP DETAIL
NOT TO SCALE



SECTION A-A



SYMBOL

PLAN

INSTALLATION NOTES:
1. Stone size - use 3" min. Stone, or reclaimed or recycled concrete equivalent.
2. Length - as required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply.
3. Thickness - not less than six (6) inches.
4. Width - 12 foot minimum, but not less than the full width at points where ingress or egress occur. 24 ft if single entrance to site.
5. Surface water - all surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
6. Maintenance - the entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public right of way this may require periodic top dressing with additional stone as conditions demand and repair and/or cleanouts of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public right of way must be removed immediately.
7. Washing - wheels shall be cleaned to remove sediment prior to entrance onto public right of way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
8. Periodic inspection and needed maintenance shall be provided after each rain

E-2 STABILIZED CONSTRUCTION ENTRANCE DETAIL
NOT TO SCALE



NOTES:
1. Area chosen for stockpiling operations shall be dry and stable.
2. Maximum slope of stockpile shall be 1:2.
3. Upon completion of soil stockpiling, each pile shall be surrounded with either silt fencing or strawbales, then stabilized with vegetation or covered.
4. See detail for installation of silt fence.

SYMBOL

E-5 SOIL STOCKPILE DETAIL
NOT TO SCALE



E-10 TREE PROTECTION PLAN FOR GRADE CHANGE DETAIL
NOT TO SCALE



SYMBOL

NOTES:
1. Contractor shall use the tree trunk armor detail for isolated trees that require protection.
2. As an alternate, the contractor may protect trees in the vicinity of regular heavy traffic / construction areas or clusters of trees to be protected as per the construction fence detail.

E-11 TREE TRUNK ARMOR / TREE PROTECTION DETAIL
NOT TO SCALE



PLAN



SECTION

SYMBOL

E-3 INLET PROTECTION DETAIL
NOT TO SCALE

SECTION

INSTALLATION NOTES:
1. Install the water bar as soon as the right of way is cleared and graded.
2. Disk or strip the sod from the base for the compacted ridge before placing fill.
3. Track the ridge to compact it to the design cross section.
4. The outlet shall be located on an undisturbed area. Field spacing will be adjusted to use the most stable outlet areas. Outlet protection will be provided when natural areas are not adequate.
5. Vehicle crossing shall be stabilized with gravel. Exposed areas shall be immediately seeded and mulched.
6. Periodically inspect water bars for erosion damage and sediment. Check outlet areas and make repairs as needed to restore operation.
7. Item #4 shall be used for the installation of the water bar.

SYMBOL

E-6 WATER BAR DETAIL
NOT TO SCALE



SYMBOL

E-7 TEMPORARY SEDIMENT BASIN OUTLET DETAIL
NOT TO SCALE



Drawing Not To Scale

SLOPE INSTALLATION EARTH ANCHOR (EA) DETAIL

1. Prepare soil before installing high-performance turf reinforcement mats (HP-TRMs), including any necessary application of lime, fertilizer, and seed.
2. Begin at the top of the slope by anchoring the HP-TRMs in a 12" (30 cm) deep x 12" (30cm) wide trench with approximately 30" (76.2 cm) of HP-TRMs extended beyond the up-slope portion of the trench. Anchor the HP-TRMs with an alternating row of staples and anchors approximately 30" (76.2 cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Fold remaining 30" (76.2 cm) portion of HP-TRMs back over compacted soil. Secure HP-TRMs over compacted soil with an alternating row of staples/anchors spaced approximately 18" (45 cm) apart across the width of the HP-TRMs.
3. Roll the HP-TRMs (A) down or (B) horizontally across the slope. HP-TRMs will unroll with appropriate side against the soil surface. All HP-TRMs must be securely fastened to soil surface by placing staples/anchors in appropriate locations as shown in the staple pattern guide.
4. The edges of parallel HP-TRMs must be stapled between earth anchors with approximately 4" (10 cm) overlap depending on the HP-TRM type. For curved sections, adjust the overlap edges of parallel HP-TRMs accordingly with a minimum of 4" (10 cm) overlap to accommodate transitional segments.

*NOTE:
In loose soil conditions, the use of staple or stake lengths greater than 6"(150mm) may be necessary to properly secure the HP-TRMs.

Tensar NORTH AMERICAN GREEN
5401 St. Wendel - Cynthiana Rd. Poseyville, IN 47633 PH: 800-772-2040 www.tensarnagreen.com

Drawn on: 01-28-13



NOTES:
* The performance of ground anchoring devices is highly dependent on numerous site/project specific variables. It is the sole responsibility of the project engineer and/or contractor to select the appropriate anchor type and length. Anchoring shall be selected to hold the mat in intimate contact with the soil subgrade and resist pullout in accordance with the project's design intent.
* Anchor Pattern Guide can vary based on earth anchor and blanket selection.
* If desired, the system can be soil-filled and sodded after TRM installation. Sod should be staples/staked according to plan specifications.

Drawing Not To Scale

Tensar NORTH AMERICAN GREEN
5401 St. Wendel - Cynthiana Rd. Poseyville, IN 47633 PH: 800-772-2040 www.tensarnagreen.com

Disclaimer:
The information presented herein is general design information only. For specific applications, consult an independent professional for further design guidance.

Drawn on: 01-28-13

SLOPE INSTALLATION EARTH ANCHOR (EA) DETAIL

1. Prepare soil before installing high-performance turf reinforcement mats (HP-TRMs), including any necessary application of lime, fertilizer, and seed.
2. Begin at the top of the slope by anchoring the HP-TRMs in a 6" (15 cm) deep x 6" (15cm) wide trench with approximately 12" (30 cm) of HP-TRMs extended beyond the up-slope portion of the trench. Anchor the HP-TRMs with a row of staples and anchors approximately 12" (30 cm) apart in the bottom of the trench. Backfill and compact the trench after stapling. Apply seed to compacted soil and fold remaining 12" (30 cm) portion of HP-TRMs back over seed and compacted soil. Secure HP-TRMs over compacted soil with a row of staples/stakes spaced approximately 12" (30 cm) apart across the width of the HP-TRMs.
3. Roll HP-TRMs (A) down or (B) horizontally across the slope. HP-TRMs will unroll with appropriate side against the soil surface. All HP-TRMs must be securely fastened to soil surface by placing staples/stakes in appropriate locations as shown in the staple pattern guide.
4. The edges of parallel HP-TRMs must be stapled with approximately 2" - 5" (5-12.5cm) overlap depending on the HP-TRM type.
5. Consecutive HP-TRMs spliced down the slope must be end over end (Shingle style) with an approximate 3'(7.5cm) overlap. Staple through overlapped area, approximately 12"(30cm) apart across entire HP-TRM width.

*NOTE:
In loose soil conditions, the use of staple or stake lengths greater than 6"(150mm) may be necessary to properly secure the HP-TRMs.



NOTE:
1. Upon hardening of washout concrete residual, material may be left in place and broken up and buried or broken up for removal and disposal.
2. Once the washout material reaches 6" from the surface, a new pit should be created for additional washout concrete residual.
3. The washout pit shall be located at least 50 ft. from storm drains, open ditches,or waterbodies.
4. Inspections shall be made daily. When 75% capacity has been reached a determination shall be made as to whether materials shall be removed. Upon removal and disposal of materials the liner shall be checked for tears. If so liner shall be replaced. Liquids shall be shall be removed by pumping out and disposed of in a proper manner. Solid washout waste can be broken up and buried on site or disposed of off site.

E-12 CEMENT TRUCK WASHOUT PIT DETAIL
NOT TO SCALE



OFFICE COPY

E-13 RIP-RAP APRON/ENERGY DISSIPATOR DETAIL
NOT TO SCALE

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer: Joseph C. Kling, P.E. NYS Lic. No. 84421

Revisions:

No.	Date	Comments:
1	12-3-14	Revisions per comments from B&L
2	1-15-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Planting Schedule
5	3-13-15	Revisions per NYSDOT
6	3-31-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from RTDOH
8	5-20-15	Revisions per comments from NYSDOT meeting
9	6-5-15	Revisions per comments from NYSDOT

SCALE: NTS

DRAWN BY: EL

DATE: 10/22/14

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

EROSION AND SEDIMENT CONTROL DETAILS

Sheet C-501

C:\USERS\JESTEVENS\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\CSD-14-25 BUTTERFIELD REDEVELOPMENT\14-25_DETAILS UPDATED.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



ELEVATION

PLAN

SYMBOL	DESCRIPTION
GR. MT. OH MT. BR MT. B/B	GROUND MOUNTED OVERHEAD MOUNTED BRIDGE MOUNTED BACK TO BACK
┼ OR ♭	APPROXIMATE LOCATION OF SIGN

TYPICAL INSTALLATION GUIDELINES

SIGN	M.U.T.C.D. NUMBER	SIZE OF SIGN	TYPE OF MOUNT
STOP	R1-1	18" X 18"	GR. MT.
RESERVED PARKING	R7-8	12" X 18"	GR. MT.
BACK IN PARKING ONLY	R7-7	12" X 18"	GR. MT.

SIGN	M.U.T.C.D. NUMBER	SIZE OF SIGN	TYPE OF MOUNT
DO NOT ENTER EXIT ONLY	R7-2	12" X 18"	GR. MT.
ENTER ONLY	R7-3	12" X 18"	GR. MT.
ONE WAY	R6-2	12" X 18"	GR. MT.

SIGN	M.U.T.C.D. NUMBER	SIZE OF SIGN	TYPE OF MOUNT
ADA ROUTE	R7-9a	12" X 18"	GR. MT.
ADA ROUTE	R7-9b	12" X 18"	GR. MT.
ADA ROUTE	R7-9c	12" X 18"	GR. MT.
STOP HERE FOR PEDESTRIANS	R1-5b	12" X 18"	GR. MT.

GENERAL NOTES:
1. All signage shall be in accordance with the latest edition of the national MUTCD and the N.Y.S Supplement (MUTCD), September 2007, including the following:
   A. Letter size and series
   B. Legend and background color
   C. Reflectivity
   D. Size of sign
2. The type of characters as specified in the standard specifications shall be as follows:

MUTCD CODE LETTER	TYPE OF CHARACTER
G, I, R,P,W,M.	TYPE IV TYPE IV OR V.

3. Sign locations as shown on plans are approximate. The Contractor shall relocate existing signs and install new signs in accordance with the MUTCD, latest edition. The Contractor shall contact the Town Engineer to discuss/resolve problem areas.
4. Except where otherwise specified, parking signs shall be placed facing approaching traffic at an angle of between 30 and 45 degrees with the line of traffic flow. Parking signs shall be placed at each end of a regulation (single-headed arrows), and, within the regulation (double-headed arrows), at intervals not to exceed 200 ft
5. Where new signs are installed the Contractor shall affix a label to the back of the sign panel. This label will show the date of installation and identification numbers.
6. Placement of W3-17 sign is prescribed in the General Municipal Law.

R-1 TRAFFIC SIGN DETAIL
NOT TO SCALE



PLAN

TRUNCATED DOME SECTION

DETECTABLE WARNING SURFACE



FIGURE 1



CURB SIDEWALK RAMP TYPE "B"



CURB SIDEWALK RAMP TYPE "A"



SECTION "C - C"



SECTION "A - A"



SECTION "D - D"



SECTION "B - B"

NOTES:

GENERAL:
1. Sidewalk curb ramp type and location are as shown on the plans or as directed.
2. All sidewalk curb ramp types may be used as straight or curved curb sections.
3. Sidewalk curb ramp types may be different at each location within an intersection.

SIDEWALK CURB RAMP CRITERIA:
4. The maximum slope of a sidewalk curb ramp shall be 1:12
5. The maximum width of a sidewalk curb ramp shall be five feet. Exclusive of flared sides.
6. All sidewalk curb ramps shall have flush, smooth transitions to the adjacent street or highway surface.
7. For NYSDOT curb ramps from a state highway shall not exceed the maximum 2% cross-slope.

SURFACE FINISH:
8. The surface of all sidewalk curb ramps shall be stable, firm, and slip resistant (E.G. A coarse broom finish perpendicular to the ramp slope is acceptable on cement concrete curb ramps.)
9. All proposed sidewalk curb ramps shall have a detectable warning surface installed from the back of the curb for a distance of 2 feet in the direction of travel on the ramp and extending the full width of the ramp, excluding the ramp sides or flares. The detectable warning surface shall comply with the requirements of section 4.29.2 of the Americans with Disabilities Act accessibility guidelines (ADAAG).

SIDEWALK CURB RAMP PLACEMENT:
10. At a corner, where the curb radius is 25-feet or less, a single ramp (either type a or b) located diagonally can often serve crosswalks in two directions. However, a single ramp shall only be used where there is a minimum clear space of 48" falling entirely within the projection of the intersection curbs (see figure 1). Where the radius exceeds 25' or the minimum 48" clear space is not achievable, then separate ramps should be provided for each crosswalk.

PAVEMENT MARKINGS AT CROSSWALKS:
11. Sidewalk curb ramps at marked crossings shall be wholly contained within the markings excluding any flared sides.
12. At a corner where a single ramp (either type a or b; located diagonally serves two crosswalks, this shall be a 48" minimum clear space at the ramp bottom wholly contained within the intersection crosswalk markings (see figure 1).
13. Where stop lines are necessary, they shall be located in advance of sidewalk curb ramps.

UTILITIES - DRAINAGE INLETS OR GRATES:
14. Where feasible, provide for drainage inlets or grates immediately upstream from the curb ramps. Reticuline or rectangular drainage grates are to be used in the area of curb ramps.
15. Do not place signal poles, sign posts, utility poles, fire hydrants, etc., within the ramp or side flare areas.

R-2 SIDEWALK CURB-RAMP DETAIL
NOT TO SCALE



NOTE:
1. Handicap parking spaces shall be located as shown on plan.

R-3 TYPICAL PARKING STALL LAYOUT
NOT TO SCALE



PLAN



PLAN



SECTION A-A

R-4 CONCRETE SIDEWALK DETAIL
NOT TO SCALE



SECTION

ELEVATION



R-5 TIMBER GUARDRAIL DETAIL
NOT TO SCALE



R-6 PAINTED CROSS WALK
NOT TO SCALE



NOTES:
1. This detail applies to the installation of new curb along existing roadway.
2. Provide 1/2" expansion joint in curb every ten feet.
3. NYSDOT standard sheet 609-01 shall be used for replacing granite curbing.

R-8 NYSDOT CONCRETE CURB INSTALLATION DETAIL
NOT TO SCALE



R-7 TYPICAL DRIVEWAY SECTION
NOT TO SCALE



OFFICE COPY

R-9 NYSDOT DRIVEWAY ENTRANCE PAVEMENT DETAIL
NOT TO SCALE

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer: STATE OF NEW YORK JOSEPH CARLO RINA 100 LICENSED PROFESSIONAL ENGINEER
Joseph C. Rina, P.E.
NYS Lic. No. 84451

Revisions:

No.	Date	Comments:
1	12-3-14	Revisions per comments from B&L
2	2-5-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Parking Schedule
5	3-13-15	Revisions per NYSDOT
6	3-31-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from NYDOH
8	6-2-15	Revisions per comments from NYDOH meeting
9	6-9-15	Revisions per comments from NYSDOT

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

SITE DETAILS

SITE/SUBDIVISION PLAN
PREPARED FOR

Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

Sheet C-502

C:\USERS\RE-STER\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\C502-14-25 BUTTERFIELD REDEVELOPMENT14-25_DETAILS_UPDATED.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



NOTES:
1. In materials to be considered as unsuitable (i.e. Muck) material is to be replaced 24" below the pipe invert and replaced with item no. 4 bedding.
2. A continuous and uniform bedding shall be provided in the trench for all buried pipe. Backfill material shall be tamped in layers around the pipe and to a sufficient height above the pipe to adequately support and protect the pipe. Stones found in the trench shall be removed for a depth of at least six inches below the bottom of the pipe.
3. See Pavement Replacement Detail for backfill specifications in local and main Village roads.
4. The contractor shall comply with all prevailing laws for safety during trenching.

W-1 WATER MAIN BEDDING DETAIL
NOT TO SCALE



VERTICAL SEPARATION

NOTES:
1. Any deviation from the required minimum separations shall be subject to a review and approval by the Putname County Department of Health prior to construction
2. HORIZONTAL SEPARATION NOTES:
   A Water mains shall be laid at least ten (10) feet horizontally, as measured from edge to edge, from any existing or proposed sewer or drain lines. Should local conditions prevent a lateral separation of ten feet, a water main may be laid closer than ten feet to a sewer if (1) it is laid in a separate trench, or if (2) it is laid in the same trench with the water main located at one side on a bench of undisturbed earth and if in either case the elevation of the crown of the sewer or drain is at least 18 inches below the bottom of the water main
   B When it is impossible to obtain proper horizontal separation, as stipulated above, the sewer or drain shall be constructed of materials and with joints equivalent to the standards for the water main and shall be pressure tested to assure water tightness prior to backfilling.
3. VERTICAL SEPARATION NOTES:
   A Normal conditions: whenever a water main must cross over or under a sewer or drain, the pipes shall be laid to provide a vertical separation between them of at least 18 inches, as measured from the bottom of the higher pipe to the crown of the lower pipe.
   B Unusual conditions: when conditions prevent a vertical separation of 18 inches, the sewer shall be constructed of materials and with joints equivalent to the water main standards and shall be pressure tested to assure water tightness prior to backfilling.
   C Water main crossing over sewers:
      i. Vertical separation of 18 inches must be provided;
      ii. Adequate structural support must be provided for the sewer to prevent excessive deflection of joints and settling;
      iii. Full length of water pipe must be centered at the point of crossing, no joints will be permitted at the point of crossing;



HORIZONTAL SEPARATION

W-4 SEPARATION OF WATER MAINS, SANITARY SEWERS OR STORM SEWERS
NOT TO SCALE



PLAN
TYPICAL FOR 11-1/4°; - 22-1/2°; - 45° BENDS



SECTION A-A



PLAN
90° BEND

PIPE DIAM. IN.	BEND	BLOCK DIMENSIONS A IN.	B IN.	C IN.	CONCRETE VOLUME FT.³
16	90	60	32	32	39.5
	45	46	28	30	19.7
	22.5	30	22	26	10.0
	11.25	20	18	12	3.8
12	90	56	26	20	15.0
	45	38	22	10	7.7
	22.5	20	20	12	3.6
	11.25	18	18	12	3.0
10	90	48	22	16	8.9
	45	28	20	12	4.0
	22.5	18	18	12	2.7
	11.25	16	16	12	2.2
8	90	34	20	12	4.4
	45	20	18	12	2.5
	22.5	14	14	12	1.6
	11.25				(3)
6	90	24	16	12	2.5
	45	14	14	12	1.5
	22.5	12	12	12	1.2
	11.25				(3)

NOTES:
1. Min. 2,500 psi concrete to be used.
2. Block dimensions are minimum and are based upon soil bearing pressure of 2,000 psf and water pressure of 150 psi. Where soil bearing is less or water pressure is greater, a special design will be required.
3. All bolts shall be covered with burlap before pouring concrete.
4. Bend to be set against disturbed earth, backfill to be firmly tamped, or block to be furnished as directed by the engineer.

W-7 THRUST BLOCKING FOR HORIZONTAL BENDS
NOT TO SCALE



W-2 WATER SERVICE CONNECTION DETAIL
NOT TO SCALE



W-5 TAPPING SLEEVE AND GATE VALVE CONNECTION DETAIL
NOT TO SCALE



NOTES:
1. Retainer glands, concrete thrust blocks and tie rods shall be used at all locations where restraints are required.
2. If groundwater is encountered within 7 feet of grade, hydrant drain holes shall be plugged. When the drains are plugged the barrels must be pumped dry after use during freezing weather. Where hydrant drains are not plugged, a gravel pocket or dry well shall be provided unless the natural soils will provide adequate drainage. Hydrant drains shall not be connected to or located within 10 feet of sanitary sewers or storm drains.
3. If hydrant is within 10 feet of sewers, hydrant drain holes shall be plugged.
4. Hydrant shall be painted with two coats of Electro- Farmdhane, plastic finish, No. 44 red paint.
5. All gate valves shall be Mueller or approved equal and shall meet AWWA standard.

W-3 FIRE HYDRANT DETAIL
NOT TO SCALE



PLAN

BRANCH SIZE IN.	BLOCK DIMENSIONS K IN.	L IN.	M IN.	CONCRETE VOLUME FT.³
6	18	16	12	2.4
8	30	18	12	4.0
10	42	20	12	6.3
12	50	24	16	11.3
16	60	36	24	30.0



SECTION A-A

NOTES:
1. Min. 2,500 psi concrete to be used.
2. Block dimensions are minimum and are based upon soil bearing pressure of 2,000 psf and water pressure of 150 psi. Where soil bearing is less or water pressure is greater, a special design will be required.
3. All bolts shall be covered with burlap before pouring concrete.

APPLIS COPY

W-6 THRUST BLOCKING FOR TEES
NOT TO SCALE

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2010 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer: Joseph C. Riina, P.E.
NYS Lic. No. 64431

Revisions:

No.	Date	Comments:
1	12-3-14	Revisions per comments from B&L.
2	1-23-15	Revisions per comments from B&L.
3	2-10-15	Revisions per comments from B&L.
4	2-19-15	Parking Schedule
5	3-13-15	Revisions per comments from NYSDOT
6	3-23-15	Revisions per comments from B&L.
7	4-23-15	Revisions per comments from BCDOH
8	5-21-15	Revisions per comments from Planning meeting
9	6-9-15	Revisions per comments from NYSDOT

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

WATER-UTILITY DETAILS

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Putnam County, New York
Village Of Cold Spring

C-503

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\BUTTERFIELD\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD SERVER\DEVELOPMENT\ENGINEERING\CAD\C503-14-25 BUTTERFIELD REDEVELOPMENT\14-25 DETAILS UPDATED.DWG



NOTES:
1. Manhole steps shall be cast Iron Neenah No. R-1981-0 or Campbell Foundry no. 2588-1 or polypropylene coated steel (see specifications) or approved equal.
2. Unless otherwise specified, sanitary sewer manholes shall have letters "SEWER" and storm manholes shall have letters "DRAIN" cast on cover. The covers shall have vent holes.
3. Manholes shall meet or exceed A.S.T.M. and O.S.H.A. requirements and be rated for H-20 vehicle design loading.
4. All pipes shall be cut flush with inside walls.
5. Where depth of manhole exceeds 10 ft, inside diameter shall be 60 ".
6. All pipe connections to sanitary manholes shall be made water tight with a kron-n-seal precast boot.

D-1 PRECAST CONCRETE SEWER / STORM DRAIN MANHOLE DETAIL

NOT TO SCALE



NOTES:
1. Where depth of catch basin exceeds 10 ft, inside dimensions shall be 48" x 48".
2. Catch basin covers and structures shall meet or exceed A.S.T.M. and O.S.H.A. requirements.
3. Pre-cast sections shall be in accordance with "Pre-cast Reinforced Manhole Sections", A.S.T.M. Designation C-478, latest revision. Minimum compressive strength shall be 4000 psi. Structures shall be rated for H-20 vehicle loading.

D-2 TYPICAL CATCH BASIN DETAIL

NOT TO SCALE



NOTES:
1. Where depth of catch basin exceeds 10 ft, inside dimensions shall be 48" x 48".
2. Top of basin shall be built with precast concrete structural slab designed for H-20 loading.

D-3 PRECAST CATCH BASIN - DRAIN INLET DETAIL

NOT TO SCALE



NOTES:
1. Pipe shall be laid and connected in the bedding which shall consist of:
   A. Compacted existing subsoil when laid above ground water or;
   B. 3/4" crushed stone when laid below ground water.
2. If subsoil is determined to be unsuitable by the Engineer, all unsuitable material shall be removed for at least 2'-6" below the pipe invert or twice the pipe diameter, whichever is greater, and replaced with compacted a 3/4" stone must be used at a 95 percent proctor and to be laid 1 foot over the pipe.
3. The contractor shall comply with all prevailing laws for safety during trenching.

D-4 STORM PIPE BEDDING DETAIL

NOT TO SCALE



NOTE:
1. Precast concrete structure and heavy duty frame and cover shall be rated to support H-20 vehicle design loading.
2. The contractor shall comply with all prevailing laws for safety during trenching.

D-5 TRENCH DRAIN BOX & GRATE DETAIL FOR UNDERDRAIN TO BIO-RETENTION

NOT TO SCALE



NOTES:
1. Clean-outs shall be spaced at minimum 50 ft intervals and/or at all changes in vertical and horizontal alignment.
2. All fittings to be white H.D. As manufactured by GPK Products Inc. or approved equal.

S-1 GRAVITY SEWER LATERAL CLEAN-OUT DETAIL

NOT TO SCALE



S-5 LIGHT POLE BASE DETAIL

NOT TO SCALE



NOTE:
1. Contractor may be required to furnish and install additional steps so as to provide proper ingress and egress to & from manhole.
2. Easement manhole frame & covers shall be set in relation to the surrounding finished grade so as to not collect runoff.
3. All pipe connections to sanitary manholes shall be made water tight with a korn-n-seal precast boot.

S-2 EXISTING LINE TIE-IN "DOGHOUSE" MANHOLE DETAIL

NOT TO SCALE



NOTES:
1. Provide cleanouts as required (see detail).
2. Contractor to follow manufacturer's installation guide.
3. The contractor shall be responsible for protecting all persons during construction from harm in accordance with all applicable codes, rules & regulations, standards and good practices.
4. Contractor to notify Village 48 hours in advance for trench inspection.
5. All fittings to be white H.D. as manufactured by GPK Products Inc. or approved equal.
6. For backfilling requirements of sewer service see "Sewer Main/Sewer Service Trench Detail".

S-3 SEWER CONNECTION TO PROPOSED MAIN-LINE DETAIL

NOT TO SCALE



NOTES:
1. Sewer pipe shall be PVC SDR-35 in all cases except where depth of cover exceeds 10 ft. In cases where cover exceeds 10 ft, sewer pipe shall be a min. PVC SDR-26. When a sewer main is installed in a fill section, the fill shall be compacted to a min. 95% standard proctor and certified to the Town of Yorktown.
2. No rock is to project into within the edges of the trench. In rock excavation pipe shall be a min. of 6" over and away from rock.
3. Backfill shall be placed so as to not disturb the pipe alignment.
4. In areas where adequate cover can not be maintained for sewer main, proper protection shall be provided against freezing and superimposed loading.
5. The contractor shall comply with wall prevailing laws for safety during trenching.

S-4 SEWER MAIN / SEWER SERVICE TRENCH DETAIL

NOT TO SCALE



S-6 ROOF & FOOTING DRAIN CONNECTION DETAIL

NOT TO SCALE

OFFICE COPY

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

STATE OF NEW YORK JOSEPH CARLO RITNA 043644 LICENSED PROFESSIONAL ENGINEER

Engineer: Joseph C. Ritna, P.E. NYS Lic. No. 64451

Revisions:

No.	Date	Comments:
1	1-3-14	Revisions per comments from B&L
2	1-23-14	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Partial Subdivision
5	3-20-15	Revisions per comments from NYSDOT
6	3-23-15	Revisions per comments from B&F
7	4-23-15	Revisions per comments from PCHDH
8	5-20-15	Revisions per comments from Planning meeting
9	6-8-15	Revisions per comments from NYSDOT

SCALE: NTS

DRAWN BY: EL

DATE: 10/22/14

STORM-SANITARY DETAILS

SITE/SUBDIVISION PLAN PREPARED FOR

Butterfield Redevelopment Project

1756 NYS ROUTE 9D

Village Of Cold Spring

Putnam County, New York

Sheet C-504

C:\USERS\ELITE\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\D-14-25 BUTTERFIELD REDEVELOPMENT\11-25 DETAILS UPDATED.DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

Manufactured by: Practical Best Management — 1-800-748-6945 www.crystalstream.com



1. ALL PIPES SHALL BE CONSTRUCTED TO BE FLUSH WITH THE INSIDE WALLS.
2. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL PIPES AND STRUCTURES BETWEEN AND AROUND THE WATER QUALITY VAULTS.
3. ALL VAULT LIFTING CONNECTIONS SHALL BE LOCATED ON THE OUTSIDE OF THE VAULT WALLS.
4. CONCRETE VAULT PRE-CASTER IS RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THE CONCRETE VAULTS. WALL AND SLAB THICKNESSES SHALL BE ALTERED ACCORDINGLY.

LEGEND

① EXPANDED ALUMINUM BASKET W/ 1/4" MESH LINING, 1'-6" H x 1'-6" L x 4'-0" W, Uplft 3'-6" FROM SUMP
② 2ND INTERNAL BAFFLE W/ 1" HOLES DRILLED AT 1 1/4" O.C., 4'-0" H.
④ SPILL PROTECTION RESERVOIR 4'-0" H. WITH A 2'-0" FRONT OUT.
⑤ 3/4"COCONUT FIBER FILTER IN ALUMINUM FRAME 1'-8" LONG.
⑥ 1/4"ALUMINUM PLATE, 9" H., 3'-6" WIDE.

SPECIFICATIONS
1. TOTAL FLOW CAPACITY SHALL BE 6 CFS.
2. WATER QUALITY FLOW OF 0.60 CFS MUST BE TREATED WITH A HYDRAULIC LOADING RATE OF 1 GPM/SQ.FT. OF FILTRATION AREA.
3. SEDIMENT RETENTION CAPACITY SHALL BE 434 CUBIC FEET.
4. OIL/HYDROCARBON RETENTION CAPACITY SHALL BE 519 GALLONS BEFORE OVERFLOW.
5. ALL INSPECTIONS MUST BE APPROVED BY THE ENGINEER AND THE REVIEWING AUTHORITY.

Protected by U.S. Patent No's. 6,797,161; 6,926,163; 6,936,491; 6,955,607; 6,994,785; 7,011,743; 7,037,426

CrystalStream Technologies
THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF PRACTICAL BEST MANAGEMENT, INC. IT IS PROVIDED FOR THE EXCLUSIVE USE OF PRACTICAL BEST MANAGEMENT, INC. AND ITS EMPLOYEES. REPRODUCTION OR USE FOR ANY OTHER PURPOSE OR BY ANY OTHER PERSONS IS STRICTLY PROHIBITED. ANY USE OR REUSE OF THIS DRAWING OR THE DATA CONTAINED HEREON WITHOUT THE EXPRESS WRITTEN PERMISSION OF PRACTICAL BEST MANAGEMENT, INC. IS AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO PRACTICAL BEST MANAGEMENT, INC. ANY MODIFICATION OF THIS DRAWING OR THE DATA CONTAINED HEREON SHALL RENDER IT INVALID UNLESS SUCH MODIFICATION IS APPROVED BY THE ENGINEER NAMED HEREON.

JOB NAME: Butterfield Site -11P
Device No.: CST-11P
NY0-001-010515
DESIGN FIRM: Site Design Consultants
adm-BMsWithinSP 1/7/2015 p.m.d.a.

CRYSTALSTREAM "CRYSTALCLEAN" WATER QUALITY VAULT MODEL "646 "

JURISDICTION: Cold Spring, NY

CRYSTAL STREAM UNIT #1

Manufactured by: Practical Best Management — 1-800-748-6945 www.crystalstream.com



1. ALL PIPES SHALL BE CONSTRUCTED TO BE FLUSH WITH THE INSIDE WALLS.
2. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL PIPES AND STRUCTURES BETWEEN AND AROUND THE WATER QUALITY VAULTS.
3. ALL VAULT LIFTING CONNECTIONS SHALL BE LOCATED ON THE OUTSIDE OF THE VAULT WALLS.
4. CONCRETE VAULT PRE-CASTER IS RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THE CONCRETE VAULTS. WALL AND SLAB THICKNESSES SHALL BE ALTERED ACCORDINGLY.

THE 2.5" X 2.5" FRAME & GRATE SHALL BE EJ V-5630 FRAME & V-5630 GRATE WITH A 30" X 30" CLEAR OPENING OR CST APPROVED EQUAL.

LEGEND

① EXPANDED ALUMINUM BASKET W/ 1/4" MESH LINING, 1'-6" H x 2'-0" L x 4'-0" W, Uplft 3'-6" FROM SUMP
② 2ND INTERNAL BAFFLE W/ 1" HOLES DRILLED AT 1 1/4" O.C., 4'-0" H.
④ SPILL PROTECTION RESERVOIR 4'-0" H. WITH A 1'-0" FRONT OUT.
⑤ 3/4"COCONUT FIBER FILTER IN ALUMINUM FRAME 1'-8" LONG.
⑥ 1/4"ALUMINUM PLATE, 9" H., 3'-6" WIDE.

SPECIFICATIONS
1. TOTAL FLOW CAPACITY SHALL BE 6 CFS.
2. WATER QUALITY FLOW OF 0.60 CFS MUST BE TREATED WITH A HYDRAULIC LOADING RATE OF 1 GPM/SQ.FT. OF FILTRATION AREA.
3. SEDIMENT RETENTION CAPACITY SHALL BE 507 CUBIC FEET.
4. OIL/HYDROCARBON RETENTION CAPACITY SHALL BE 600 GALLONS BEFORE OVERFLOW.
5. ALL INSPECTIONS MUST BE APPROVED BY THE ENGINEER AND THE REVIEWING AUTHORITY.

Protected by U.S. Patent No's. 6,797,161; 6,926,163; 6,936,491; 6,955,607; 6,994,785; 7,011,743; 7,037,426

CrystalStream Technologies
THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF PRACTICAL BEST MANAGEMENT, INC. IT IS PROVIDED FOR THE EXCLUSIVE USE OF PRACTICAL BEST MANAGEMENT, INC. AND ITS EMPLOYEES. REPRODUCTION OR USE FOR ANY OTHER PURPOSE OR BY ANY OTHER PERSONS IS STRICTLY PROHIBITED. ANY USE OR REUSE OF THIS DRAWING OR THE DATA CONTAINED HEREON WITHOUT THE EXPRESS WRITTEN PERMISSION OF PRACTICAL BEST MANAGEMENT, INC. IS AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO PRACTICAL BEST MANAGEMENT, INC. ANY MODIFICATION OF THIS DRAWING OR THE DATA CONTAINED HEREON SHALL RENDER IT INVALID UNLESS SUCH MODIFICATION IS APPROVED BY THE ENGINEER NAMED HEREON.

JOB NAME: Butterfield Site I2P2
Device No.: CST-12P2
NY0-003-01075
DESIGN FIRM: Site Design Consultants
adm-BMsWithinSP2 1/6/2015 p.m.d.a.

CRYSTALSTREAM "CRYSTALCLEAN" WATER QUALITY VAULT MODEL "646 "

JURISDICTION: Cold Spring, NY

CRYSTAL STREAM UNIT #2A

Manufactured by: Practical Best Management — 1-800-748-6945 www.crystalstream.com



1. ALL PIPES SHALL BE CONSTRUCTED TO BE FLUSH WITH THE INSIDE WALLS.
2. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL PIPES AND STRUCTURES BETWEEN AND AROUND THE WATER QUALITY VAULTS.
3. ALL VAULT LIFTING CONNECTIONS SHALL BE LOCATED ON THE OUTSIDE OF THE VAULT WALLS.
4. CONCRETE VAULT PRE-CASTER IS RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THE CONCRETE VAULTS. WALL AND SLAB THICKNESSES SHALL BE ALTERED ACCORDINGLY.

THE 2.5" X 2.5" TRAFFIC GRATE & FRAME SHALL BE EJ V-5630 FRAME & V-5630 GRATE WITH A 30" X 30" CLEAR OPENING OR CST APPROVED EQUAL.

LEGEND

① EXPANDED ALUMINUM BASKET W/ 1/4" MESH LINING, 1'-6" H x 2'-0" L x 4'-0" W, Uplft 3'-6" FROM SUMP
② 2ND INTERNAL BAFFLE W/ 1" HOLES DRILLED AT 1 1/4" O.C., 4'-0" H.
④ SPILL PROTECTION RESERVOIR 4'-0" H. WITH A 2'-0" FRONT OUT.
⑤ 3/4"COCONUT FIBER FILTER IN ALUMINUM FRAME 1'-8" LONG.
⑥ 1/4"ALUMINUM PLATE, 9" H., 3'-6" WIDE.

SPECIFICATIONS
1. TOTAL FLOW CAPACITY SHALL BE 6 CFS.
2. WATER QUALITY FLOW OF 1.31 CFS MUST BE TREATED WITH A HYDRAULIC LOADING RATE OF 1 GPM/SQ.FT. OF FILTRATION AREA.
3. SEDIMENT RETENTION CAPACITY SHALL BE 589 CUBIC FEET.
4. OIL/HYDROCARBON RETENTION CAPACITY SHALL BE 1,161 GALLONS BEFORE OVERFLOW.
5. ALL INSPECTIONS MUST BE APPROVED BY THE ENGINEER AND THE REVIEWING AUTHORITY.

Protected by U.S. Patent No's. 6,797,161; 6,926,163; 6,936,491; 6,955,607; 6,994,785; 7,011,743; 7,037,426

CrystalStream Technologies
THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF PRACTICAL BEST MANAGEMENT, INC. IT IS PROVIDED FOR THE EXCLUSIVE USE OF PRACTICAL BEST MANAGEMENT, INC. AND ITS EMPLOYEES. REPRODUCTION OR USE FOR ANY OTHER PURPOSE OR BY ANY OTHER PERSONS IS STRICTLY PROHIBITED. ANY USE OR REUSE OF THIS DRAWING OR THE DATA CONTAINED HEREON WITHOUT THE EXPRESS WRITTEN PERMISSION OF PRACTICAL BEST MANAGEMENT, INC. IS AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO PRACTICAL BEST MANAGEMENT, INC. ANY MODIFICATION OF THIS DRAWING OR THE DATA CONTAINED HEREON SHALL RENDER IT INVALID UNLESS SUCH MODIFICATION IS APPROVED BY THE ENGINEER NAMED HEREON.

JOB NAME: Butterfield Site I2P1
Device No.: CST-12P1
NY0-002-01075
DESIGN FIRM: Site Design Consultants
adm-BMsWithinSP 1/6/2015 p.m.d.a.

CRYSTALSTREAM "CRYSTALCLEAN" WATER QUALITY VAULT MODEL "646 "

JURISDICTION: Cold Spring, NY

CRYSTAL STREAM UNIT #2B

Manufactured by: Practical Best Management — 1-800-748-6945 www.crystalstream.com



1. ALL PIPES SHALL BE CONSTRUCTED TO BE FLUSH WITH THE INSIDE WALLS.
2. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL PIPES AND STRUCTURES BETWEEN AND AROUND THE WATER QUALITY VAULTS.
3. ALL VAULT LIFTING CONNECTIONS SHALL BE LOCATED ON THE OUTSIDE OF THE VAULT WALLS.
4. CONCRETE VAULT PRE-CASTER IS RESPONSIBLE FOR THE STRUCTURAL INTEGRITY OF THE CONCRETE VAULTS. WALL AND SLAB THICKNESSES SHALL BE ALTERED ACCORDINGLY.

LEGEND

① EXPANDED ALUMINUM BASKET W/ 1/4" MESH LINING, 1'-6" H x 2'-0" L x 4'-0" W Uplft 4'-0" FROM SUMP
② 1ST INTERNAL BAFFLE W/ 1" HOLES DRILLED AT 1-1/4" O.C., 3'-9" H.
③ 2ND INTERNAL BAFFLE W/ 1" HOLES DRILLED AT 1 1/4" O.C., 6'-0" H.
④ SPILL PROTECTION RESERVOIR 4'-6" H. WITH A 1'-5" FRONT OUT.
⑤ 3/4"COCONUT FIBER FILTER IN ALUMINUM FRAME 2'-2" LONG.
⑥ 1/4"ALUMINUM PLATE, 9" H., 3'-6" WIDE.

SPECIFICATIONS
1. TOTAL FLOW CAPACITY SHALL BE 8 CFS.
2. WATER QUALITY FLOW OF 1.31 CFS MUST BE TREATED WITH A HYDRAULIC LOADING RATE OF 1 GPM/SQ.FT. OF FILTRATION AREA.
3. SEDIMENT RETENTION CAPACITY SHALL BE 24 CUBIC FEET.
4. OIL/HYDROCARBON RETENTION CAPACITY SHALL BE 600 GALLONS BEFORE OVERFLOW.
5. ALL INSPECTIONS MUST BE APPROVED BY THE ENGINEER AND THE REVIEWING AUTHORITY.

Protected by U.S. Patent No's. 6,797,161; 6,926,163; 6,936,491; 6,955,607; 6,994,785; 7,011,743; 7,037,426

CrystalStream Technologies
THIS DRAWING IS COPYRIGHTED AND IS THE SOLE PROPERTY OF PRACTICAL BEST MANAGEMENT, INC. IT IS PROVIDED FOR THE EXCLUSIVE USE OF PRACTICAL BEST MANAGEMENT, INC. AND ITS EMPLOYEES. REPRODUCTION OR USE FOR ANY OTHER PURPOSE OR BY ANY OTHER PERSONS IS STRICTLY PROHIBITED. ANY USE OR REUSE OF THIS DRAWING OR THE DATA CONTAINED HEREON WITHOUT THE EXPRESS WRITTEN PERMISSION OF PRACTICAL BEST MANAGEMENT, INC. IS AT THE SOLE RISK OF THE USER AND WITHOUT LIABILITY TO PRACTICAL BEST MANAGEMENT, INC. ANY MODIFICATION OF THIS DRAWING OR THE DATA CONTAINED HEREON SHALL RENDER IT INVALID UNLESS SUCH MODIFICATION IS APPROVED BY THE ENGINEER NAMED HEREON.

JOB NAME: Butterfield Site I3P
Device No.: CST-13P
NY0-004-010715
DESIGN FIRM: Site Design Consultants
adm-BMsWithinSP 1/6/2015 p.m.d.a.

CRYSTALSTREAM "CRYSTALCLEAN" WATER QUALITY VAULT MODEL "846 "

JURISDICTION: Cold Spring, NY

CRYSTAL STREAM UNIT #3

POST CONSTRUCTION CRYSTAL STREAM TECHNOLOGIES INSPECTION AND MAINTENANCE NOTES

3.1 INSPECTION OVERVIEW

THE UNIT IS DESIGNED AND SPECIFIED IN MOST APPLICATIONS TO COMPLY WITH THE NON-POINT SOURCE MANDATES OF THE CLEAN WATER ACT AND THE NPDES REGULATIONS. THESE REGULATIONS STATE THAT ANY BMP (BEST MANAGEMENT PRACTICE) NEEDS TO BE INSPECTED EVERY 90 DAYS AND CLEANED AND MAINTAINED AS NEEDED. MANY LOCAL REGULATIONS HAVE SIMILAR REQUIREMENTS AND ALL FEDERAL, STATE AND LOCAL REQUIREMENTS MUST BE MET. CRYSTALSTREAM TECHNOLOGIES RECOMMENDS VISUAL INSPECTION ON A 30-DAY CYCLE AS WELL AS SEDIMENT DEPTH INSPECTION, DURING THE CONSTRUCTION PHASE. THE UNIT INSPECTION IS DONE TO DETERMINE THE OPERATIONAL STATUS OF THE UNIT AND DETERMINE IF A CLEANING CYCLE IS NECESSARY AS WELL AS TO MEET ANY JURISDICTIONAL ORDINANCE REQUIREMENTS. ALL INSPECTIONS MUST BE DOCUMENTED (APPENDIX 2). WHEN CONSTRUCTION HAS BEEN COMPLETED AND THE SITE HAS STABILIZED, THE CST UNIT SHOULD BE INSPECTED EVERY 90 DAYS FOR THE FIRST YEAR AND CLEANED WHEN SEDIMENT REACHES THE MAXIMUM STORAGE CAPACITY.

3.2 INSPECTION PROCEDURES

AS PER THE FOLLOWING:

3.2.1 THE UNIT SHOULD BE VISUALLY INSPECTED FROM THE SURFACE TO DETERMINE THE INTEGRITY OF ACCESS POINTS. LOOK FOR BROKEN HINGES OR BROKEN OR MISSING HANDLES. A QUALIFIED WELDER SHOULD REPAIR ANY BROKEN HINGES IMMEDIATELY. INSPECT BOLTS ON LID ANGLE IRON AND LOOK FOR LOOSE RED HEADS ON ANGLE IRON. REPLACE RED HEADS AS NEEDED. RE-PAINT THE LID, WITH A RUST RESISTANT PAINT AS NECESSARY.

3.2.2 THE ACCESS SHOULD BE OPENED AND SECURED PROPERLY.

3.2.3 A VISUAL INSPECTION SHOULD BE MADE OF THE TRASH BASKET AT THE FRONT OF THE UNIT TO DETERMINE CAPACITY AND TYPE OF MATERIAL TRAPPED.

3.2.4 A VISUAL INSPECTION SHOULD BE MADE OF THE WATER SURFACE IN THE FRONT OF THE UNIT TO DETERMINE OIL SHEEN OR BLANKET.

3.2.5 A VISUAL INSPECTION SHOULD BE MADE OF THE OIL AND HYDROCARBON RESERVOIR TO DETERMINE AMOUNT OF OIL/WATER TRAPPED AND THE HISTORICAL HIGH-WATER LEVEL IN THE UNIT.

3.2.6 A VISUAL INSPECTION OF THE WATER SURFACE IN THE REAR OF THE UNIT SHOULD BE MADE AND ANY POLLUTANTS NOTED.

3.2.7 INSPECT THE ALUMINUM MESH IN THE TRASH BASKET. REPLACE AS NEEDED.

3.2.8 INSPECT THE BASKET FRAME FOR CRACKS OR DAMAGE. REPAIR AS NEEDED.
A VISUAL INSPECTION SHOULD BE MADE OF THE PIPE CONNECTIONS TO THE UNIT AND ANY MATERIAL DECAY OR IMPROPER INSTALLATION NOTED. PIPES SHOULD BE CUT FLUSH WITH THE INTERIOR WALL OF THE UNIT AND PROPERLY MUDDED IN. IF UPON INSPECTION IT IS NOTED THAT THE PIPES ARE NOT CUT FLUSH, OR ARE NOT MUDDED IN, CONTACT THE CONTRACTOR AND REQUIRE THAT HE CORRECT THIS IMMEDIATELY.

3.2.9 INSPECT BAFFLES TO ENSURE THAT THEY ARE PROPERLY SEATED INTO THE BRACKETS. ALSO
NOTE IF THERE IS ANY DAMAGE TO BAFFLES (BOWING), RESEAT BAFFLES IF NECESSARY.

3.2.10 INSPECT OIL RESERVOIR FOR CRACKS OR DAMAGE. CHECK THE WELDS AROUND THE OIL RESERVOIR FOR WEAR OR DAMAGE AND NOTE ANY REPAIR WORK NECESSARY. A QUALIFIED WELDER MUST PERFORM ALL REPAIR WORK TO THE WELDS ON THE OIL RESERVOIR DURING THE ROUTINE CLEANING.

3.2.11 INSPECT THE RISER FOR CRACKS IN THE CONCRETE WALLS. REPAIR AS REQUIRED DURING THE ROUTINE CLEANING.

3.2.12 A SILT GAUGE SHOULD BE USED TO DETERMINE SEDIMENT DEPTH AS SHOWN IN APPENDIX 1. CHECK THE SILT/SEDIMENT LEVEL BEHIND THE TRASH BASKET AND IN FRONT OF THE OIL RESERVOIR

3.2.13 THE ACCESS FOR CLEANING SHOULD BE EVALUATED AND DOCUMENTED. THE TRUCK CLEANING THESE UNITS REQUIRES A STABLE ROADWAY CAPABLE OF WITHSTANDING 15,000 POUNDS.

3.2.14 ANY CHANGES IN THE AREA TRIBUTARY THAT ARE EVIDENT SHOULD BE NOTED.

3.2.15 REPLACE THE ACCESS POINT COVERS CAREFULLY.

3.2.16 NOTE THE CONDITION OF THE AREA SURROUNDING THE UNIT ON THE INSPECTION REPORT. (EXAMPLE: GRASS, DIRT, ROCKS, SINK HOLES) REPORT ANY HAZARDOUS CONDITIONS TO THE APPROPRIATE SUPERVISOR.

3.2.17 AN INSPECTION REPORT SHOULD BE COMPLETED, WITH A COPY STAYING ON SITE AND A COPY BEING SENT TO THE LOCAL JURISDICTION.

THE INSPECTION PROCEDURES FOR THE TRAFFIC UNITS ARE SIMILAR TO THOSE FOR THE NON- TRAFFIC UNITS WITH THE EXCEPTION OF THE SEDIMENT DEPTH EVALUATIONS AS SHOWN IN APPENDIX 1 AND AN INSPECTION OF THE GRATE AND FRAME AND RING AND COVER. ALSO PROPER PRECAUTIONS SHOULD BE TAKEN IN TRAFFIC SITUATIONS AS SPECIFIED IN THE SAFETY SECTION OF THIS MANUAL.

NOTE: WHEN THERE HAS BEEN AN OBVIOUS GASOLINE SPILL OR OTHER FLAMMABLE/HAZARDOUS MATERIAL IN THE UNIT, IMMEDIATE NOTIFICATION SHOULD BE GIVEN TO THE OWNER AND JURISDICTIONAL AUTHORITIES. THIS MANUAL IS FOR ROUTINE CLEANING OF STORM WATER DEBRIS AND ANY UNUSUAL OCCURRENCES SHOULD BE LEFT TO PROPERLY TRAINED AND EQUIPPED INDIVIDUALS.

4.1 CLEANING OVERVIEW

THE CLEANING OF THE UNIT IS THE ESSENTIAL ELEMENT TO THE OPERATIONAL SUCCESS OF THE CRYSTALSTREAM DEVICE. THE POLLUTANT REMOVAL CAPACITY OF THE DEVICE WILL EVENTUALLY CAUSE THE EQUIPMENT TO FAIL WITHOUT PROPER MAINTENANCE AND ADDITIONALLY NOT ACHIEVE THE GOALS OF THE INSTALLATION. THE CLEANING CYCLE IS DEPENDANT ON A NUMBER OF FACTORS INCLUDING POLLUTANT LOAD, RAINFALL, TIME OF YEAR, BASIN CHANGES, UPSTREAM MITIGATION TACTICS AND INSTALLATION. BASED ON THE VARIETY OF FACTORS, A CLEANING SCHEDULE CAN BE CONSISTENT OR VARY WIDELY ON THE SAME DEVICE. THIS HIGHLIGHTS THE IMPORTANCE OF THE INSPECTION PROCESS IN THE OVERALL MAINTENANCE AND INTEGRITY OF THE UNIT. THE CLEANING IS GENERALLY DONE WITH A TWO-PERSON CREW AND A VACUUM PUMP SYSTEM. THE DURATION OF THE MAINTENANCE WILL DEPEND ON A NUMBER OF FACTORS BUT CAN TYPICALLY BE DONE IN ABOUT 2.5 HOURS WITH PROPERLY TRAINED INDIVIDUALS.

4.2 OPTION 1: CLEANING PROCEDURES - SURFACE CLEANING

IF THE CLEANING OF THE UNIT IS TO BE PREFORMED FROM THE SURFACE, THE OPERATOR SHOULD EXPECT A LONGER CLEANING TIME AND THE POTENTIAL FOR ADDITIONAL DISPOSAL CHARGES. THE FRONT CHAMBER OF THE UNIT WILL CONTAIN THE TRASH AND DEBRIS IN THE TRASH BASKET, ANY FLOATING HYDROCARBONS THAT HAVE NOT BEEN SKIMMED INTO THE OIL/HYDROCARBON RESERVOIR AND ACCUMULATED SEDIMENT ON THE BOTTOM OF THE UNIT.

CLEANING PROCEDURES ARE AS PER THE FOLLOWING:

4.2.1 THE UNIT SHOULD BE VISUALLY INSPECTED FROM THE SURFACE TO DETERMINE THE INTEGRITY OF THE TREAD PLATE LID, ALUMINUM HATCH OR OTHER ACCESS.

4.2.2 A VISUAL INSPECTION OF THE UNIT SHOULD BE DONE TO EVALUATE STRUCTURAL INTEGRITY
AND DETERMINE IF ANY IMPACTED MATERIAL IS PRESENT IN THE DEVICE. IF THERE HAS BEEN A HAZARDOUS SPILL SEE SECTION 4.6

NOTE: WHEN THERE HAS BEEN AN OBVIOUS GASOLINE SPILL OR OTHER FLAMMABLE/HAZARDOUS MATERIAL IN THE UNIT, IMMEDIATE NOTIFICATION SHOULD BE GIVEN TO THE OWNER AND JURISDICTIONAL AUTHORITIES. THIS MANUAL IS FOR ROUTINE CLEANING OF STORM WATER DEBRIS AND ANY UNUSUAL OCCURRENCES SHOULD BE LEFT TO PROPERLY TRAINED AND EQUIPPED INDIVIDUALS.

4.2.3 THE TRASH BASKET SHOULD BE CLEANED BY EITHER USING A TRASH NETTING SYSTEM OR VACUUM TRUCK. IF CLEANING USING A NETTING SYSTEM, THIS MATERIAL CAN BE DISPOSED OF IN TRASH BAGS IN THE NORMAL MANNER.

4.2.4 THE SURFACE OIL/HYDROCARBON SEPARATION ZONE IN THE FRONT CHAMBER SHOULD BE REMOVED EITHER WITH SORBANTS OR WITH A VACUUM TRUCK.

4.2.5 THE STORMWATER CONTAINED IN THE AREA BETWEEN THE SURFACE WATER AND THE SEDIMENT ACCUMULATION CAN BE DECANTED TO MINIMIZE THE AMOUNT OF DISPOSAL REQUIRED. ANY DOWNSTREAM DISCHARGE NEEDS TO BE AFTER THE SURFACE CLEANING AND ONLY DOWN TO THE LEVEL OF THE BOTTOM OF THE OIL/HYDROCARBON RESERVOIR OR THE TOP OF THE SEDIMENT ACCUMULATION. ANY POLLUTANTS DISCHARGED DOWNSTREAM ARE THE RESPONSIBILITY OF THE CLEANING OPERATOR.

4.2.6 THE OIL/HYDROCARBON RESERVOIR NEEDS TO BE EVACUATED BY THE VACUUM EQUIPMENT.

4.2.7 THE SEDIMENT ACCUMULATED IN THE FRONT AND REAR CHAMBER CAN BE REMOVED BY THE VACUUM EQUIPMENT.

4.2.8 THE UNIT SHOULD BE PRESSURE WASHED DOWN TO REMOVE ANY POLLUTION ATTACHED TO THE BAFFLES, WALLS OR HYDROCARBON RESERVOIR.

4.2.9 ALL PARTS SHOULD BE INSPECTED FOR WEAR AND TEAR AND DOCUMENTED.

4.2.10 A MAINTENANCE REPORT (APPENDIX 3) SHOULD BE COMPLETED, WITH A COPY STAYING ON SITE AND A COPY BEING SENT TO THE LOCAL JURISDICTION.

4.3 OPTION 2: CLEANING PROCEDURES - CONFINED SPACE ENTRY

THE CLEANING PROCEDURES ARE SIMILAR FOR CONFINED SPACE ENTRIES EXCEPT THAT THE OSHA GUIDELINE APPLY AND NEED TO BE FOLLOWED. THE CONFINED SPACE ENTRY ALLOWS THE CREW TO DO A BETTER JOB OF CLEANING THE UNIT AND ALLOWS FOR THE TIME NEEDED AND DISPOSAL COST TO BE REDUCED.

CAUTION! ANY INSPECTION DONE IN A TRAFFIC AREA MUST MEET THE DOT GUIDELINES FOR ROADWAY WORK AND ADDITIONAL SAFETY PROCEDURE WILL BE NECESSARY.

CAUTION ! ALL OSHA CONFINED SPACE REQUIREMENTS SHOULD BE MET WHILE CLEANING THIS UNIT. AS PER THE FOLLOWING:

4.3.1 THE UNIT SHOULD BE VISUALLY INSPECTED FROM THE SURFACE TO DETERMINE THE INTEGRITY OF THE TREAD PLATE LID.

4.3.2 A VISUAL INSPECTION OF THE UNIT SHOULD BE DONE TO EVALUATE STRUCTURAL INTEGRITY
AND DETERMINE IF ANY IMPACTED MATERIAL IS PRESENT IN THE DEVICE. IF THERE HAS BEEN A HAZARDOUS SPILL SEE SECTION 4.6

NOTE: WHEN THERE HAS BEEN AN OBVIOUS GASOLINE SPILL OR OTHER FLAMMABLE/HAZARDOUS MATERIAL IN THE UNIT, IMMEDIATE NOTIFICATION SHOULD BE GIVEN TO THE OWNER AND JURISDICTIONAL AUTHORITIES. THIS MANUAL IS FOR ROUTINE CLEANING OF STORM WATER DEBRIS AND ANY UNUSUAL OCCURRENCES SHOULD BE LEFT TO PROPERLY TRAINED AND EQUIPPED INDIVIDUALS.

4.3.3 A LADDER SHOULD BE INSERTED ON THE FRONT SIDE OF THE UNIT BETWEEN THE BAFFLES AND A SORBANT BLANKET LAID ON THE SURFACE OF THE WATER TO COLLECT ANY FREE OIL FLOATING ON THE SURFACE.

4.3.4 IN MOST UNITS, THE TRASH BASKET AND BAFFLES CAN BE REMOVED TO ALLOW EASIER ACCESS TO THE BOTTOM OF THE UNIT.

4.3.5 INSPECT THE ALUMINUM MESH IN THE TRASH BASKET. REPLACE AS NEEDED.

4.3.6 THE TRASH BASKET SHOULD BE CLEANED AND DIRECTLY DISPOSED OF IN GARBAGE BAGS.

4.3.7 THE STORMWATER CONTAINED IN THE AREA BETWEEN THE SURFACE WATER AND THE SEDIMENT ACCUMULATION CAN BE DECANTED TO MINIMIZE THE AMOUNT OF DISPOSAL REQUIRED. ANY DOWNSTREAM DISCHARGE NEEDS TO BE AFTER THE SURFACE CLEANING AND ONLY DOWN TO THE LEVEL OF THE BOTTOM OF THE OIL/HYDROCARBON RESERVOIR OR THE TOP OF THE SEDIMENT ACCUMULATION. ANY POLLUTANTS DISCHARGED DOWNSTREAM ARE THE RESPONSIBILITY OF THE CLEANING OPERATOR.

4.3.8 THE UNIT SHOULD BE PRESSURE WASHED DOWN TO REMOVE ANY POLLUTION ATTACHED TO THE BAFFLES, WALLS OR HYDROCARBON RESERVOIR.

4.3.9 THE LADDER CAN BE USED TO GET ON TO THE UNIT FLOOR AND REMOVE THE REST OF THE WATER AND SEDIMENT FROM THE BOTTOM OF THE UNIT.

4.3.10 THE WALLS SHOULD BE WIPED DOWN IN THE FRONT WITH A SORBANT BLANKET

4.3.11 THE FRESH COCONUT FIBER MESH SHOULD BE REPLACED IN THE FRAME AND THE FRAME ASSEMBLY RETURNED TO THE UNIT.

4.3.12 ALL PARTS SHOULD BE INSPECTED FOR WEAR AND TEAR AND DOCUMENTED.

4.3.13 REMOVE ALL EQUIPMENT FROM THE UNIT. REPLACE THE MANHOLE COVER AND THE GRATE IN THE CONCRETE LID.

4.3.14 A MAINTENANCE REPORT (APPENDIX 3) SHOULD BE COMPLETED, WITH A COPY STAYING ON SITE AND A COPY BEING SENT TO THE LOCAL JURISDICTION.

CLEANING EQUIPMENT

THE EQUIPMENT NEEDED TO CLEAN THE CRYSTALSTREAM UNIT IS:

- VACUUM TRUCK 750 GALLON
- PRESSURE WASHER
- SUBMERSIBLE PUMP
- GENERATOR
- SORBANT PADS (MYCELX™)
- 16-25 FT. LADDER
- GLOVES
- COCONUT FIBER MESH (ROLANKA INDUSTRIES)
- TRASH BAGS
- CRYSTALSTREAM LID HOOKS
- SEDIMENT/SILT GAUGE
- RUBBER BOOTS
- TESTING EQUIPMENT TO MEET OSHA CONFINED SPACE ENTRY REQUIREMENTS
- CONES
- BARRICADES
- CAUTION TAPE
- HARDHAT
- WATERPROOF SILICON CAULK
- ALUMINUM MESH (FOR TRASH BASKET)
- FLAT SHOVEL
- 20' ELECTRICAL CORD
- 5 GALLON BUCKET W/ROPE
- FIRST AID KIT CONTAINING EYE WASH
- TRIPOD SAFETY HARNESS RECOVERY APPARATUS

CALL CRYSTALSTREAM AT 1-800-748-6945 IF YOU NEED SUPPLIES OR PARTS.

DOCUMENTATION AND DISPOSAL

THE CLEANING OF THE UNIT SHOULD BE DOCUMENTED AND THE CONTENTS OF THE UNIT ESTIMATED AND RECORDED IN A LOG FOR INSPECTIONS. THIS DOCUMENTATION SHOULD MEET FEDERAL, STATE AND LOCAL GUIDELINES.

THE DISPOSAL OF THE TRASH, DEBRIS, WATER



NOTES:
1. All design specifications for Stormtech SC-740 chambers shall be in accordance with the Stormtech design manual.
2. The installation of Stormtech SC-740 chambers shall be in accordance with the latest Stormtech installation instructions.
3. The contractor is advised to review and understand the installation instructions prior to beginning system installation. Call 1-888-892-2694 or visit www.stormtech.com to receive a copy of the latest Stormtech installation instructions.
4. Chambers shall meet the design requirements and load factors specified in Section 12.12 of the latest edition of the AASHTO LRFD bridge design specifications

SWM-1 STORMTECH SC-740 CHAMBER SYSTEM PLAN VIEW DETAIL

NOT TO SCALE





SWM-2 STORMTECH SC-740 INSPECTION PORT/RISER DETAIL

NOT TO SCALE



NOMINAL CHAMBER SPECIFICATIONS	
SIZE (W x H x INSTALLED LENGTH)	51.0" x 30.0" x 85.4"
CHAMBER STORAGE	45.9 CUBIC FEET
MINIMUM INSTALLED STORAGE	74.9 CUBIC FEET
WEIGHT	75 LBS.

SWM-3 STORMTECH SC-740 CHAMBER DETAIL

NOT TO SCALE



NOTE: SEE TABLE BELOW FOR THE PEAK ELEVATIONS

NOTES:
1. All design specifications for Stormtech SC-740 chambers shall be in accordance with the Stormtech design manual.
2. The installation of Stormtech SC-740 chambers shall be in accordance with the latest Stormtech installation instructions.
3. The contractor is advised to review and understand the installation instructions prior to beginning system installation. Call 1-888-892-2694 or visit www.stormtech.com to receive a copy of the latest Stormtech installation instructions.
4. Chambers shall meet the design requirements and load factors specified in Section 12.12 of the latest edition of the AASHTO LRFD bridge design specifications

Stormwater Infiltration Elevations						Peak Elevations			
SYSTEM	*System Inv.*	*Pipe In Size (in)*	*Inv.*	*Pipe Out Size (in)*	*Inv.*	*WQv (ac-ft)*	*1 year*	*10 year*	*100 year*
Infiltrator Sys. #1	111.32	12	112.86	6	113.36	0.168	111.46	111.57	111.69
Infiltrator Sys. #2	121.51	12,12	123.05	6	123.55	0.232	122.83	124.51	124.51
Infiltrator Sys. # 3	129.09	12	130.13	6	131.13	0.316	129.50	131.91	132.09

SWM-4 STORMTECH SC-740 CHAMBER SYSTEM TYPICAL CROSS SECTION

NOT TO SCALE



SWM-5 STORMTECH SC-740 CHAMBER DETENTION SYSTEM INLET/OUTLET DETAIL

NOT TO SCALE



SWM-6 STORMTECH SC-740 CHAMBER DETENTION ISOLATOR ROW DETAIL

NOT TO SCALE



NOTE:
1. Benchmark elevation to be added to outlet structure for measuring sediment accumulations.

BYPASS STRUCTURES	INVERT ELEVATIONS				
SYSTEM	RIM	SUMP	WEIR	PIPE TO INFIL.	BYPASS PIPE
BYPASS 1	121.70	111.67	114.61	112.86	113
BYPASS 2A	129.77	122.37	124.8	123.37	124.5
BYPASS 2B	127.14	122.09	124.8	123.05	123.09
BYPASS 3	136.97	129.1	131.88	130.13	130.16

D-1 BYPASS STRUCTURE DETAIL

NOT TO SCALE



PLAN



Bioretention System Elevations						Peak Elevations			
SYSTEM	*System Inv.*	*Pipe In Size (in)*	*Inv.*	*Pipe Out Size (in)*	*Inv.*	*WQv(ac-ft)*	*1 year*	*10 year*	*100 year*
Bio-Retention Garden	132	6	137	N/A	135	0.150	135.54	135.87	136.41

SWM-7 TYPICAL BIORETENTION DETAIL

NOT TO SCALE



SECTION

PLANTING SPECIFICATIONS:	
- CLASSIFICATION	SM OR ML-UNIFIED SOIL CLASSIFICATION SYSTEM
- PERMEABILITY	1.0 FEET PER DAY OR 0.5% INCHES PER HOUR
- PH RANGE	5.2 TO 7.0%
- ORGANIC MATTER	1.5 TO 4.0%
- MAGNESIUM	35 LBS / ACRE PER MIN.
- PHOSPHORUS	75 LBS / ACRE PER MIN.
- POTASSIUM	85 LBS / ACRE PER MIN.
- SOLUBLE SALTS	≤ 500 PPM
- CLAY	10 TO 25%
- SILT	30 TO 55%
- SAND	35 TO 60%



SYMBOL

NOTE:
1. Grass swale to be seeded with grass mixture per 1000 S.F as follows:
   Kentucky Bluegrass: .60lbs
   Creeping Red Fescue: .50 lbs
   Perennial Ryegrass: .20lbs
2. The foundation area shall be cleared of trees, stumps,sod, loose rock, or other objectionable materials.
3. The cross section shall be excavated to the neat lines and grades shown on the plans. Over excavated areas shall be backfilled with moist soil compacted to the density of the surrounding material.
4. No abrupt deviations from design grade or horizontal alignment shall be permitted.
5. Construction operations shall be done in such a manner that erosion, air and water pollution will be minimized and held within legal limits. All disturbed areas shall be vegetated or otherwise protected against soil erosion.

SWM-8 GRASS SWALE DETAIL

NOT TO SCALE





NOTES
1. 8-30" (200-750 mm) GRATES/SOLID COVERS SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
2. 12-30" (300-750 mm) FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05
3. DRAIN BASIN TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS
4. DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 FOR CORRUGATED HDPE (ADS & HANCOR DUAL WALL) & SDR 35 PVC
5. FOR COMPLETE DESIGN AND PRODUCT INFORMATION: WWW.NYLOPLAST-US.COM
6. TO ORDER CALL: 800-821-6710

SMW-9 NYLOPLAST DRAINAGE BASIN DETAIL

NOT TO SCALE



NOTES:
1. The foundation area shall be cleared of trees, stumps,sod, loose rock, or other objectionable materials.
2. The cross section shall be excavated to the neat lines and grades shown on the plans. Over excavated areas shall be backfilled with moist soil compacted to the density of the surrounding material.
3. Filter and bedding shall be placed to line and grade in the manner specified.
4. No abrupt deviations from design grade or horizontal alignment shall be permitted.
5. Construction operations shall be done in such a manner that erosion, air and water pollution will be minimized and held within legal limits. All disturbed areas shall be vegetated or otherwise protected against soil erosion.

SYMBOL

OFFICE COPY

SWM-10 GRASS LEVEL-LIP SPREADER DETAIL

NOT TO SCALE

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesgnconsultants.com

PROJECT # 14-25

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

STATE OF NEW YORK — JOSEPH CARLO RINA — NO. 64451 — LICENSED PROFESSIONAL ENGINEER

Engineer: Joseph C. Rina, P.E.
NYS Lic. No. 64451

Revisions:

No.	Date	Comments
1	1-24-14	Revisions per comments from B&L
2	1-29-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	3-13-15	Parking Stalls Shifted
5	3-13-15	Revisions per comments from NYSDOT
6	3-23-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from NYSDOT
8	5-21-15	Revisions per comments from Village Engineer
9	6-9-15	Revisions per comments from NYSDOT

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

STORMWATER MANAGEMENT DETAILS

SITE/SUBDIVISION PLAN
PREPARED FOR:
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Putnam County, New York
Village Of Cold Spring

Sheet C-506

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\EL\STERLING\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\CAD-14-25 BUTTERFIELD REDEVELOPMENT14-25_DETAILS_LIPDATED.DWG



RAINWATER HARVESTING #2 36 INCH STORAGE CHAMBER



RAINWATER HARVESTING #1 36 INCH CHAMBER

BILL OF MATERIALS 36" CHAMBERS

*THE COMPONENTS AND QUANTITIES LISTED HEREIN ARE NOT INTENDED TO BE A COMPREHENSIVE MATERIAL LIST. EXTRA COMPONENTS, NOT LISTED HEREIN, MAY BE NECESSARY TO COMPLETE THE CONSTRUCTION OF THE SYSTEM.					
ITEM	QTY.	PART #	DESCRIPTION	MATERIAL	VENDOR
1	1	3632ANC 6	36" DOUBLE MANIFOLD TEE W/24" RISER		See Detail
2	4	3632ANC	36" DOUBLE MANIFOLD TEE		See Detail
3	3	3698ANC	36" X 90 DEGREE MANIFOLD BEND		See Detail
4	17	Stub 1	36" PIPE STICK, SOIL TIGHT		See Detail
5	26	Stub 2	36" PIPE STICK, FIELD CUT, SOIL TIGHT (FIELDCUT)		See Detail
6	1	3698ANC 1	36" X 90 DEGREE MANIFOLD BEND W/8" CLEANOUT		See Detail
7	1	3698ANC 1	36" X 90 DEGREE MANIFOLD BEND W/24" RISER		See Detail
8	1	3632ANC 1	36" TRIPLE MANIFOLD TEE W/8" CLEANOUT		See Detail
9	1	3632ANC 1	36" TRIPLE MANIFOLD TEE W/24" RISER		See Detail
10	5	3698ANC 3	36" X 90 DEGREE MANIFOLD BEND W/8" STUB		See Detail
11	2	3698ANC 3	36" X 90 DEGREE MANIFOLD BEND W/12" STUB		See Detail
12	1	3698ANC 6	36" X 90 DEGREE MANIFOLD BEND W/15" STUB		See Detail
13	1	Stub 3	36" PIPE STICK, SOIL TIGHT W/15" STUB		See Detail
14	1	3632ANC 6	36" DOUBLE MANIFOLD TEE W/24" RISER, W/8" CLEANOUT		See Detail
15	50	3696AA	36" BEVEL COUPLER		STANDARD

36" TRIPLE MANIFOLD TEE W/8" CLEANOUT



36" TRIPLE MANIFOLD TEE W/24" RISER



36" X 90 DEGREE MANIFOLD BEND W/8" STUB



36" X 90 DEGREE MANIFOLD BEND W/12" STUB



36" DOUBLE MANIFOLD TEE



36" X 90 DEGREE MANIFOLD BEND W/8" CLEANOUT



36" X 90 DEGREE MANIFOLD BEND W/24" RISER



36" DOUBLE MANIFOLD TEE W/24" RISER



36" X 90 DEGREE MANIFOLD BEND W/15" STUB



36" X 90 DEGREE MANIFOLD BEND



36" DOUBLE MANIFOLD TEE W/24" RISER, W/8" CLEANOUT



36" PIPE STICK SOIL TIGHT



36" PIPE STICK FIELD CUT



36" PIPE STICK: SOIL TIGHT W/15" STUB



ADS RETENTION/DETENTION PIPE SYSTEM SPECIFICATION

SCOPE
THIS SPECIFICATION DESCRIBES ADS RETENTION/DETENTION PIPE SYSTEMS FOR USE IN NON-PRESSURE GRAVITY-FLOW STORM WATER COLLECTION SYSTEMS UTILIZING A CONTINUOUS OUTFALL STRUCTURE.

PIPE REQUIREMENTS
ADS RETENTION/DETENTION SYSTEMS MAY UTILIZE ANY OF THE VARIOUS PIPE PRODUCTS BELOW:
- N-12® WT IB PIPE (PER AASHTO) SHALL MEET AASHTO M294, TYPE S OR ASTM F2306
- N-12® WT IB PIPE (PER ASTM F2648) SHALL MEET ASTM F2648
- N-12® MEGA GREEN™ WT IB SHALL MEET ASTM F2648

ALL PRODUCTS SHALL HAVE A SMOOTH INTERIOR AND ANNULAR EXTERIOR CORRUGATIONS. WT IB PIPE PRODUCTS ARE ONLY AVAILABLE AS NON-PERFORATED. PRODUCT-SPECIFIC PIPE SPECIFICATIONS ARE AVAILABLE IN THE DRAINAGE HANDBOOK SECTION 1 *SPECIFICATIONS*

JOINT PERFORMANCE
WATERTIGHT (WT IB):
WT IB PIPE SHALL BE JOINED USING A BELL & SPIGOT JOINT. THE JOINT SHALL BE WATERTIGHT ACCORDING TO THE REQUIREMENTS OF ASTM D3212 GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477. 12 - THROUGH 60 - INCH (300 TO 1500MM) DIAMETERS SHALL HAVE A BELL REINFORCED WITH A POLYMER COMPOSITE BAND. THE BELL TOLERANCE DEVICE SHALL BE INSTALLED BY THE MANUFACTURER.

PIPE & FITTING CONNECTIONS SHALL BE WITH A BELL AND SPIGOT CONNECTION UTILIZING A SPUN-ON OR WELDED BELL AND VALLEY OR SADDLE GASKET. THE JOINT SHALL MEET THE WATERTIGHT REQUIREMENTS OF ASTM D3212, AND GASKETS SHALL MEET THE REQUIREMENTS OF ASTM F477. REFER TO TECHNICAL NOTE 7.01 *RAINWATER HARVESTING WITH HDPE CISTERNS.*

FITTINGS
FITTINGS SHALL CONFORM TO ASTM F2306 AND MEET JOINT PERFORMANCE INDICATED ABOVE FOR FITTINGS CONNECTIONS. CUSTOM FITTINGS ARE AVAILABLE AND MAY REQUIRE SPECIAL INSTALLATION CRITERION.

INSTALLATION
INSTALLATION SHALL BE IN ACCORDANCE WITH ASTM D2321 AND ADS RECOMMENDED INSTALLATION GUIDELINES, WITH THE EXCEPTION THAT MINIMUM COVER IN NON-TRAFFIC AREAS FOR 12 - THROUGH 60 - INCH (300 TO 1500MM) DIAMETERS SHALL BE ONE FOOT (0.3M). MINIMUM COVER IN TRAFFIXED AREAS FOR 12 - THROUGH 36 - INCH (300 TO 900MM) DIAMETERS SHALL BE ONE FOOT (0.3M) AND FOR 42 - THROUGH 60 - INCH (1050 TO 1500MM) DIAMETERS, THE MINIMUM COVER SHALL BE 2 FT (0.6M). BACKFILL SHALL CONSIST OF CLASS I MATERIAL ONLY. *MINIMUM COVER HEIGHTS DO NOT ACCOUNT FOR PIPE BUOYANCY. REFER TO ADS TECHNICAL NOTE 5.05 HDPE PIPE FLOTATION FOR BUOYANCY DESIGN CONSIDERATIONS.* MAXIMUM COVER OVER SYSTEM USING STANDARD BACKFILL IS 8-FT *(2.4M); CONTACT A REPRESENTATIVE WHEN MAXIMUM FILL HEIGHT MAY BE EXCEEDED.* ADDITIONAL INSTALLATION REQUIREMENTS ARE PROVIDED IN THE DRAINAGE HANDBOOK SECTION 6 *RETENTION/DETENTION.*



NOMINAL DIAMETER	NOMINAL O.D.	TYPICAL SPACING "C"	TYPICAL SIDE WALL "X"	MIN. H (NON-TRAFFIC)	MIN. H (TRAFFIC)	MAX. H*
36" (900 MM)	42" 1067 MM)	63" (1600 MM)	18" (457 MM)	12" (292 MM)	12" (292 MM)	8' (2.4 M)

* MAXIMUM FILL HEIGHTS OVER MANIFOLD FITTINGS. CONTACT MANUFACTURER'S REPRESENTATIVE FOR INSTALLATION CONSIDERATIONS WHEN COVER EXCEEDS 8-FT.
**60" SYSTEMS REQUIRE CLASS I BACKFILL AROUND ALL FITTINGS.

NOTES:

1. ALL REFERENCES TO CLASS I OR II MATERIAL ARE PER ASTM D2321 "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST EDITION.

2. ALL RETENTION AND DETENTION SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, LATEST EDITION AND THE MANUFACTURER'S PUBLISHED INSTALLATION GUIDELINES.

3. MEASURES SHOULD BE TAKEN TO PREVENT THE MIGRATION OF NATIVE FINES INTO THE BACKFILL MATERIAL, WHEN REQUIRED. SEE ASTM D2321.

4. FILTER FABRIC: A GEOTEXTILE FABRIC MAY BE USED AS SPECIFIED BY THE ENGINEER TO PREVENT THE MIGRATION OF FINES FROM THE NATIVE SOIL INTO THE SELECT BACKFILL MATERIAL.

5. FOUNDATION: WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER, AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.

6. BEDDING: SUITABLE MATERIAL SHALL BE CLASS I OR II. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 4"-24" (100mm-600mm); 6" (150mm) FOR 30"-60" (750mm-900mm).

7. INITIAL BACKFILL: SUITABLE MATERIAL SHALL BE CLASS I OR II IN THE PIPE ZONE EXTENDING NOT LESS THAN 6" ABOVE CROWN OF PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION.

8. COVER: MINIMUM COVER OVER ALL RETENTION/DETENTION SYSTEMS IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12" FROM TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOATATION. FOR TRAFFIC APPLICATIONS, MINIMUM COVER IS 12" UPTO 36" DIAMETER PIPE AND 24" OF COVER FOR 42" - 60" DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT. MAXIMUM FILL HEIGHT LIMITED TO 8-FT OVER FITTINGS FOR STANDARD INSTALLATIONS. CONTACT A SALES REPRESENTATIVE WHEN MAXIMUM FILL HEIGHTS EXCEED 8-FT FOR INSTALLATION CONSIDERATIONS.





SECTION A-A

NOTES:

1) ALL ELEVATIONS, DIMENSIONS AND LOCATIONS OF RISERS, INLETS AND OUTLETS, SHALL BE VERIFIED BY THE ENGINEER PRIOR TO RELEASING FOR FABRICATION.

2) IN SITUATIONS WHERE A FINE-GRAINED BACKFILL MATERIAL IS USED ADJACENT TO THE PIPE SYSTEM, AND ESPECIALLY INVOLVING GROUND WATER CONDITIONS, CONSIDERATION SHOULD BE GIVEN TO THE USE OF GASKETED PIPE JOINTS. AT THE VERY LEAST THE PIPE JOINTS SHOULD BE WRAPPED IN A SUITABLE, NON-WOVEN GEOTEXTILE FABRIC TO PREVENT INFILTRATION OF FINES INTO THE PIPE SYSTEM.

3) CONSIDERATION FOR CONSTRUCTION EQUIPMENT LOADS MUST BE TAKEN INTO ACCOUNT.

4) ALL PIPE DIMENSIONS ARE SUBJECT TO MANUFACTURERS TOLERANCES.

5) ALL RISERS TO BE FIELD EXTENDED OR TRIMMED TO FINAL GRADE.



SECTION B-B

* LOAD BEARING CONCRETE COLLAR SHALL BE CONSTRUCTED IN TRAFFIC AREAS SUCH THAT THE LIVE LOAD IS TRANSMITTED TO THE SURROUNDING SOIL AND NOT DIRECTLY TO THE RISER.



PUMP DETAIL FOR RAINWATER HARVESTING (BY OTHERS)

I.D.	SIZE, (in)	INV., (ft)	DOWNSTREAM I.D.	L. ft	S, %	DOWNSTREAM INV., (ft)
RWH#1	12	130.75	DMH-5	75	15.4	118.97
RWH#2	12	133	CB-6	46	4.50	130.87

THE UNDERSIGNED HERBY APPROVES THE ATTACHED ( ) PAGES.

_____
DATE

DISCLAIMER
THE DESIGN PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

THE PROCEEDING DETAILS WERE GENERATED USING ADS DESIGN PROB, A SOFTWARE PROGRAM DEVELOPED BY ADVANCED DRAINAGE SYSTEMS, INC. ("ADS"). THESE DRAWINGS ARE INTENDED TO DEPICT THE ADS COMPONENTS AS REQUESTED BY THE USER. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEERS RESPONSIBILITY TO ENSURE THE DESIGN PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

OFFICE COPY

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

PROJECT # 14-25

COPYRIGHT ©2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Engineer: JOSEPH GARLO BUNK — NEW YORK — 103 58 — LICENSED PROFESSIONAL ENGINEER
Joseph C. Kling, P.E.
315 58 1 0641

Revisions:		
No.	Date	Comments:
1	12-3-14	Revisions per comments from B&E
2	1-21-15	Revisions per comments from B&E
3	2-10-15	Revisions per comments from B&E
4	2-19-15	Perkins Schedule
5	3-23-15	Revisions per comments from B&E
6	3-23-15	Revisions per comments from B&E
7	4-23-15	Revisions per comments from NYSDOT
8	4-24-15	Revisions per comments from B&E
9	6-5-15	Revisions per comments from NYSDOT

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

RAIN WATER HARVESTING DETAILS

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

Sheet C-507

C:\USERS\BILLSTER\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\CSD-14-25 BUTTERFIELD REDEVELOPMENT14-25_DETAILS (UPDATED).DWG

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



NOTE:
1. DO NOT BACKFILL THE REAR OF THE WALL UNTIL THE THE FRONT FACE OF THE WALL IS BACKFILLED.

NOTE: THIS DETAIL IS PROVIDED FOR BID PURPOSES ONLY. THE CONTRACTOR SHALL PROVIDE SEALED SHOP DRAWINGS PROVIDED BY THE MANUFACTURER AND SIGNED BY A LICENSED NYS PROFESSIONAL ENGINEER

ST-1 TYPICAL GRAVITY WALL SECTION DETAIL

NOT TO SCALE

TYPICAL WALL CHART

WALL HEIGHT	NO. 28" BLOCK COURSES	MINIMUM BURY DEPTH	LEVELING PAD DEPTH
2.0'	2	1.0'	1.0'
3.0'	3	1.5'	1.0'
4.0'	3	0.5'	1.0'
5.0'	4	1.0'	1.0'
6.0'	5	1.5'	1.0'

Comments
1. Hold top of wall elevations.
2. Step walls as required to meet grades shown.
3. This Chart is provided for bid purposes only. The Contractor shall provide a sealed shop drawing provided by the Manufacturer and signed by a licensed NYS Professional Engineer.



FENCE INSTALLATION OPTIONS
REDI-ROCK PC SERIES

NOTE: THIS DETAIL IS PROVIDED FOR BID PURPOSES ONLY. THE CONTRACTOR SHALL PROVIDE SEALED SHOP DRAWINGS PROVIDED BY THE MANUFACTURER AND SIGNED BY A LICENSED NYS PROFESSIONAL ENGINEER

ST-2 FENCE INSTALLATION DETAILS

NOT TO SCALE

GENERAL NOTES:

1. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE TOWN CODE OF PRACTICE AND THE NEW YORK STATE BUILDING CONSTRUCTION CODE.
2. ALL CHANGES MADE TO THESE PLANS SHALL BE APPROVED BY THE ENGINEER AND ANY SUCH CHANGES SHALL BE FILED AS AMENDMENTS TO THE ORIGINAL BUILDING PERMIT.
3. ALL WRITEN DIMENSIONS ON THE DRAWINGS SHALL TAKE PRECEDENCE OVER ANY SCALED DIMENSIONS.
4. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK USING HIS BEST SKILL AND ATTENTION. HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES.
5. THE CONTRACTOR SHALL BE RESPONSIBLE TO THE OWNER FOR THE ACTS AND OMISSIONS OF HIS EMPLOYEES, SUBCONTRACTORS, AND THEIR AGENTS AND EMPLOYEES, AND ANY OTHER PERSONS PERFORMING ANY WORK.
6. THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT HIS WORK AND WILL BE HELD RESPONSIBLE FOR CONSEQUENTIAL DAMAGE DUE TO HIS ACTIVITIES. THE OWNER AND THE ENGINEER SHALL BE HELD HARMLESS.
7. THE CONTRACTOR SHALL SECURE & PAY FOR A BUILDERS RISK POLICY TO COVER THE PERIOD OF CONSTRUCTION. THE ENGINEER & OWNER SHALL BE NAMED AS ADDITIONAL INSURED. ALL CONTRACTORS EMPLOYED AT THE SITE SHALL BE COVERED BY WORKMAN'S COMPENSATION.
8. ENGINEER'S WHOSE SEAL APPEARS HEREON HAS NOT BEEN RETAINED FOR SUPERVISION OF CONSTRUCTION, SUBSEQUENTLY, HE HIS NOT RESPONSIBLE FOR CONSTRUCTION AND THEREFORE ASSUMES NO RESPONSIBILITY FOR CONSTRUCTION PRACTICES, PROCEDURES, AND RESULTS THEREFROM.

CONSTRUCTION NOTES:

1. WALL UNITS SHALL BE REDI-ROCK® AS PRODUCED BY A LICENSED MANUFACTURER.
2. WALL UNITS SHALL BE MADE WITH READY-MIXED CONCRETE IN ACCORDANCE WITH ASTM C94, LATEST REVISION AND SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH f'c = 4,000 PSI.
3. REDI-ROCK WALL UNITS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS AND INSTALLATION MANUAL.
4. ALL CONCRETE WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE AMERICAN CONCRETE INSTITUTE, ACI 318, LATEST EDITION.
5. EXCAVATION IN GENERAL SHALL CONFORM TO THE LINES AND GRADES SHOWN ON THE CONTRACT DRAWINGS
6. FILL MATERIAL SHALL BE PLACED IN LOOSE 8 INCH LIFTS. PRIOR TO COMPACTION, EACH LIFT SHALL BE MOISTENED OR AERATED AS NECESSARY TO PROVIDE OPTIMUM MOISTURE CONTENT. EACH LIFT SHALL BE COMPACTED TO A MINIMUM OF 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY A.S.T.M. D1557 METHOD C. THE CONTRACTOR WILL BE REQUIRED TO HIRE AN INDEPENDENT CERTIFIED TESTING LAB TO PERFORM FIELD DENSITY TESTS. FIELD TESTING SHALL BE PERFORMED IN ACCORDANCE WITH A.S.T.M. D1556 OR D2922. A MINIMUM OF 6 IN-PLACE FIELD DENSITY TESTS SHALL BE PERFORMED ON ALTERNATE LIFTS. FILLING OPERATIONS MAY NOT PROCEED UNTIL IN-PLACE DENSITY TESTS HAVE BEEN PERFORMED AND THE FILL PROPERLY COMPACTED.
7. FILL SHALL CONSIST OF SOUND DURABLE PARTICLES TO THE GRADATION SHOWN IN THE TABLE BELOW. THE MATERIAL SHALL BE GRANULAR AND FREE OF ORGANIC OR OTHER DELETERIOUS MATERIAL. IN GENERAL THE SOIL SHALL BE NON-PLASTIC WITH A PLASTICITY INDEX LESS THAN 6 AND SHALL CONFORM TO THE UNIFIED SOIL CLASSIFICATION SYSTEM FOR AN "SW" SOIL OR THE REQUIREMENTS OF THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION SECTION 203-2 ITEM NO. 203.07 SELECT GRANULAR FILL, HOWEVER THE MAXIMUM SIZE SHALL BE 3 INCHES.

SIEVE SIZE	PERCENT PASSING BY WEIGHT
3 "	100
No. 40	0 - 70
No. 200	0 - 15

IF ON-SITE EXCAVATED MATERIAL IS USED IT MUST CONFORM TO THE SAME MINIMUM REQUIREMENTS SPECIFIED. IN ALL INSTANCES, THE THE CONTRACTOR MUST SUBMIT CERTIFIED LABORATORY TEST REPORTS ON ALL MATERIALS USED FOR BACKFILL. THE FOLLOWING REPORTS SHALL BE PROVIDED AND BE IN ACCORDANCE WITH THE FOLLOWING ASTM SPECIFICATIONS:
- PARTICLE SIZE ANALYSIS - A.S.T.M. D422
- SOIL CLASSIFICATION - A.S.T.M. D2487
- LIQUID & PLASTIC LIMITS - A.S.T.M. D424
- MODIFIED PROCTOR MAXIMUM DENSITY - A.S.T.M. D1557 METHOD C

8. EXCAVATION SHALL BE PERFORMED IN ACCORDANCE WITH THE "CONSTRUCTION SAFETY & HEALTH ACT O.S.H.A. PART 192
9. GEOTEXTILE FABRIC SHALL BE TREVIRA SPUNBOUND NON-WOVEN #1125 OR APPROVED EQUAL. THE GEOTEXTILE SHALL BE INSTALLED PER THE MANUFACTURER'S RECOMMENDATIONS AND GUIDELINES.
10. THE CONTRACTOR SHALL NOT USE LARGE OR HEAVY CONSTRUCTION EQUIPMENT WITHIN 5 FEET OF THE RETAINING WALL. SUITABLE HAND/SMALL COMPACTION EQUIPMENT SHALL BE USED WITHIN 5 FEET OF THE WALL.
11. FOOTINGS CONSTRUCTED ON VIRGIN IN-SITU SOIL SHALL HAVE A MINIMUM ALLOWABLE BEARING CAPACITY OF 3000 PSF.
12. TO INSURE A PROPER BEARING SURFACE FOR THE FOOTINGS CONSTRUCTED ON NATURAL IN-SITU SOIL, THE CONTRACTOR SHALL STRIP ALL TOP SOIL. PRIOR TO CONSTRUCTION OF THE FOOTINGS, THE AREA SHALL BE COMPACTED USING SUITABLE COMPACTION EQUIPMENT. A MINIMUM A 3 PASSES SHALL BE MADE.
13. DURING BACKFILL OPERATIONS, THE CONTRACTOR SHALL BE CAREFUL NOT TO CREATE UNBALANCED LOADING CONDITIONS ON THE WALL. BACKFILL SHOULD BE PLACED AND COMPACTED ON BOTH SIDES OF THE WALL SIMULTANEOUSLY.
14. ALL FOOTINGS SHALL BE LOCATED A MINIMUM OF 3'-6" BELOW ANY ADJACENT FINISHED GRADE.
15. ALL CONCRETE SUPPLIED TO THE PROJECT SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH "f'c = 4000 PSI" AND SHALL CONTAIN A MINIMUM 5% AIR ENTRAINING ADMIXTURE IN ACCORDANCE WITH A.S.T.M. C 260.
16. STEEL REINFORCEMENT SHALL BE OF THE SIZES SPECIFIED AND SHALL HAVE A MIN. YIELD STRENGTH fy = 60, OOO PSI
17. THE CONTRACTOR SHALL PROVIDE EXPANSION JOINTS @ 90'-0" O.C. (MAX.) IN THE WALL.
18. FOOTINGS SHALL NOT BE CONSTRUCTED ON WET OR FROZEN GROUND. UNSUITABLE MATERIAL SHALL BE EXCAVATED AND REPLACED WITH COMPACTED GRANULAR FILL OR 3/4" CRUSHED STONE.

28" SERIES BLOCKS



NOTES:
1. Weights and Center of Gravity (C of G) calculations are based on blocks as shown. Center of Gravity is measured from the back of the block. Half blocks may include a fork lift slot on one side. Actual weights and volumes may vary.
2. Weight shown is based on 143 pcf concrete.

ST-3 REDI ROCK BLOCK DETAILS

NOT TO SCALE



ST-4 REDI ROCK CORNER DETAIL

NOT TO SCALE



BASE LEVELING PAD NOTES:
1. The leveling pad is to be constructed of crushed washed stone or compacted aggregate.
2. The base foundation is to be approved by the site engineer prior to placement of the leveling pad.
3. See "Typical Wall Section Detail" for leveling pad layer depth

ST-5 STANDARD UNIT/BASE PAD ISOMETRIC VIEW DETAIL

NOT TO SCALE

OFFICE COPY

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

C:\USERS\EL\STER\DESKTOP\NEW FOLDER\14-25 BUTTERFIELD REDEVELOPMENT\ENGINEERING\CAD\CSD-14-25 BUTTERFIELD REDEVELOPMENT11-14-25 DETAILS UPDATED.DWG

PROJECT # 14-25

Site Design Consultants
Civil Engineers • Land Planners
251-F Underhill Avenue, Yorktown Heights, NY 10598
(914) 962-4488 - Fax: (914) 962-7386
www.sitedesignconsultants.com

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS, ALL RIGHTS RESERVED

Joseph C. Riina, P.E.
NYS Lic. No. 64451

Revisions:		
No.	Date	Comments:
1	1-9-15	Revisions per comments from B&L
2	1-30-15	Revisions per comments from B&L
3	2-10-15	Revisions per comments from B&L
4	2-19-15	Retains Sheeting
5	3-23-15	Revisions per comments from NYSDOT
6	3-31-15	Revisions per comments from B&L
7	4-23-15	Revisions per comments from PCDOH
8	4-24-15	Revisions per comments from Planning
9	6-9-15	Revisions per comments From NYSDOT

SCALE: NTS
DRAWN BY: EL
DATE: 10/22/14

RETAINING WALL DETAILS

SITE/SUBDIVISION PLAN
PREPARED FOR
Butterfield Redevelopment Project
1756 NYS ROUTE 9D
Village Of Cold Spring
Putnam County, New York

Sheet C-508









HOT MIX ASPHALT CURB

NOTES:

1. USE CURB AND CURB AND GUTTER MEETING THE MATERIAL AND CONSTRUCTION REQUIREMENTS OF SECTION 609 OF THE STANDARD SPECIFICATIONS.
2. CURB ANCHOR NEW CONSTRUCTION. THIS DETAIL SHOWS PLACEMENT OF CURB ANCHORS. PUSH-IN TYPE ANCHORS MAY BE USED SHOWN ON THE STANDARD SHEET FOR LONGITUDINAL TIES.
3. CURB TYPES M150A, VF150A AND M100A REQUIRE CURB ANCHOR. CURB AND GUTTER TYPES VF1500 AND M1000 REQUIRE ANCHORS WHEN PLACED ADJACENT TO CONCRETE PAVEMENT OR SHOULDER.
4. WHEN VERTICAL FACED CURB LESS THAN 9" WIDE IS USED WITH CURB ROCKS C10, C12, AND C15 AND CONCRETE SIDEWALK IS PLACED ADJACENT TO THIS CURB, SEE STANDARD SHEET MISCELLANEOUS CURB DETAILS FOR CURB BOX JOINT.
5. USE WITH CURB BOXES, C06, C10, AND C15.

STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION	
U.S. CUSTOMARY STANDARD SHEET	
CONCRETE CURB, CURB AND GUTTER, AND HOT MIX ASPHALT CURB	
APPROVED SEPTEMBER 19, 2008	ISSUED UNDER EB 08-026
/S/ DANIEL D'ANGELO, P.E. DEPUTY CHIEF ENGINEER DESIGN	609-03

EFFECTIVE DATE: 01/09/09



STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION	
U.S. CUSTOMARY STANDARD SHEET	
STONE CURB AND GRANITE CURB	
APPROVED JUNE 14, 2013	ISSUED UNDER EB 13-007
/S/ RICHARD W. LEE, P.E. ACTING DEPUTY CHIEF ENGINEER DESIGN	609-01

EFFECTIVE DATE: 01/09/14

TABLE 1 RECOMMENDED DRIVEWAY WIDTH "B"		
DRIVEWAY CLASSIFICATION	PERMISSIBLE RANGE OF WIDTH AT 0' TO 5' FROM EDGE OF TRAVELED WAY (NO CURB POSTED SPEED 40 MPH OR LESS)	PERMISSIBLE RANGE OF WIDTH AT 0' TO 5' FROM EDGE OF TRAVELED WAY (NO CURB POSTED 45 MPH OR MORE)
RESIDENTIAL, LESS THAN 50 FT. IN LENGTH	9 TO 12	10 TO 24
RESIDENTIAL, GREATER THAN 50 FT. IN LENGTH	9 TO 12	10 TO 14
MINOR COMMERCIAL, COMBINED TWO-WAY DRIVEWAY	22 TO 30	28 TO 35
MINOR COMMERCIAL, DIVIDED OR ONE-WAY DRIVEWAY	12 TO 24	12 TO 24
MAJOR COMMERCIAL, MULTI-LANE DRIVEWAY	12 TO 15 FT. LANES	14 TO 16 FT LANES

TABLE 2 MAXIMUM SLOPE		
ROADWAY CLASSIFICATION	CHARACTER DRIVEWAY	RESIDENTIAL DRIVEWAY
RURAL	10%	10%
URBAN	6%	8%

TABLE 3 DRIVEWAY MATERIALS AND THICKNESS						
PROPOSED OR EXISTING GRADE	WITHIN DRIVEWAY PAVEMENT LENGTH ("PL")			WITHIN TRANSITION LENGTH ("TL")		
	MATERIAL	THICKNESS FOR RESIDENTIAL (RA)	THICKNESS FOR MINOR COMMERCIAL (CA)	MATERIAL	THICKNESS FOR RESIDENTIAL (RA)	THICKNESS FOR MINOR COMMERCIAL (CA)
DIRT, GRASS, OR GRAVEL	HMA 9M/OHP	3	4	SUBBASE COURSE, EXISTING IF NECESSARY	6	9
	SUBBASE COURSE	6	8			
SNOW	HMA 9M/OHP	3	4	STONE, EXCAVATE AS NECESSARY	8	11
	SUBBASE COURSE	6	8			
HMA RESURFACED	HMA 9M/OHP	1½	1½	NOT APPLICABLE - ALL WORK ON AN EXISTING PAVED DRIVEWAY IS WITHIN THE DRIVEWAY PAVEMENT LENGTH		
	TRENCH AND LEVELING COURSE	AS NECESSARY	AS NECESSARY			
HMA RECONSTRUCTION	HMA 9M/OHP	3	4 (SEE NOTE 3)	NOT APPLICABLE - ALL WORK ON AN EXISTING PAVED DRIVEWAY IS WITHIN THE DRIVEWAY PAVEMENT LENGTH		
	SUBBASE COURSE	6	8 (SEE NOTE 3)			
PORTLAND CEMENT CONCRETE	PORTLAND CEMENT CONCRETE 8M/P	6	6 (SEE NOTE 3)	NOT APPLICABLE - ALL WORK ON AN EXISTING PAVED DRIVEWAY IS WITHIN THE DRIVEWAY PAVEMENT LENGTH		
	SUBBASE COURSE	6	8 (SEE NOTE 3)			
HMA 9M/OHP = HOT MIX ASPHALT SIDEWALKS, DRIVEWAYS, AND BICYCLE PATHS PORTLAND CEMENT CONCRETE				8M/P = PORTLAND CEMENT CONCRETE SIDEWALKS AND DRIVEWAYS		

TABLE 4 DRIVEWAY ENTRANCE TYPE SELECTION						
DRIVEWAY ENTRANCE TYPE	ENTRANCE DESIGNING METHOD	CONDITIONS FOR USE				
		DRIVEWAY CLASSIFICATION (NOTE 1)	CORNER ANGLE	TRAVEL LANE AND SHOULDER WIDTH	CURB	SIDEWALK
TYPE 1	RADIUS	RESIDENTIAL OR MINOR COMMERCIAL	60° TO 120°	ANY	USE WITH OR WITHOUT CURB	USE WITHOUT SIDEWALK
TYPE 2	RADIUS	MINOR COMMERCIAL ONLY	60° TO 120°	ANY	ANY	USE WITH OR WITHOUT SIDEWALK
TYPE 3	TAPER	MINOR COMMERCIAL ONLY	60° TO 120°	18' OR GREATER (NOTE 2)	USE ONLY WITH CURB (NOTE 3)	USE ONLY WITH SIDEWALK ADJACENT TO CURB, OR WITH THE SIDEWALK SEPARATED FROM THE ROADWAY BY A GRASS STRIP WITHOUT SIDEWALK
TYPE 4	TAPER	RESIDENTIAL OR MINOR COMMERCIAL	60° TO 120°	18' OR GREATER (NOTE 2)	USE ONLY WITH CURB (NOTE 3)	USE ONLY WITH SIDEWALK LESS THAN 7' OPEN OR ADJACENT TO THE EDGE OF PAVEMENT

DRIVEWAY ENTRANCE TYPE	CONDITIONS FOR USE				RECOMMENDED USE
	SIDEWALK	ROADWAY POSTED SPEED			
TYPE 1	ANY	ANY			RECOMMENDED FOR ALL LOCATIONS EXCEPT FOR MINOR COMMERCIAL WITH CURBS
TYPE 2	ANY	ANY			RECOMMENDED ONLY FOR MINOR COMMERCIAL WITH CURBS
TYPE 3	USE ONLY WITH SIDEWALK ADJACENT TO CURB, OR WITH THE SIDEWALK SEPARATED FROM THE ROADWAY BY A GRASS STRIP WITHOUT SIDEWALK	ONLY LOW SPEED (45 MPH OR LESS)			ALTERNATIVE ENTRANCE TYPE, TYPICALLY FOR URBAN AREA USE)
TYPE 4	USE ONLY WITH SIDEWALK LESS THAN 7' OPEN OR ADJACENT TO THE EDGE OF PAVEMENT	ONLY LOW SPEED (45 MPH OR LESS)			ALTERNATIVE ENTRANCE TYPE, TYPICALLY FOR URBAN AREA USE)

TABLE 5 MINIMUM LENGTH OF VERTICAL CURVE, L, FOR CHANGE IN GRADE IN DRIVEWAY PROFILE		
CHANGE IN GRADE A=|G2-G1| (%)	CREST, Lc (FT)	SAG, Ls (FT)
4-5	5	5
6-8	8	7
9-10	9	8
11-12	10	9
13-14	11	10
15-16	12	11
17-18	13	12
19-20	14	13

LENGTH OF VERTICAL CURVE BASED ON 25" CURVE RADIUS AND THE ASSUMED PASSENGER VEHICLE AND SINGLE UNIT TRUCK CLEARANCE.

NOTES:

1. TABLE 4 ONLY APPLIES TO RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS. FOR OTHER DRIVEWAY CLASSIFICATIONS (MAJOR, COMMERCIAL, FIELD ENTRANCE, ETC.), REFER TO THE NYS POLICY AND STANDARDS FOR THE DESIGN OF ENTRANCE WAYS TO STATE HIGHWAYS MANUAL.
2. FOR DRIVEWAYS WITH A DRIVEWAY OFFSET LESS THAN 10', THE TAPER METHOD IS NOT GENERALLY RECOMMENDED, UNLESS IT CAN BE FIELD VERIFIED THAT THE DRIVEWAY ENTRANCE WIDTH WILL ACCOMMODATE THE VEHICLES THAT USE THE DRIVEWAY ON A REGULAR BASIS.
3. TYPE 3 AND TYPE 4 DRIVEWAY ENTRANCES CAN BE USED WITHOUT CURB IF A TAPER STYLE ENTRANCE BETTER MATCHES THE HIGHWAY CORRIDOR AESTHETICS OR SPECIFIC SITE CONDITIONS THAN A RADIUS STYLE ENTRANCE.
4. REFER TO SHEET 1 FOR GENERAL NOTES, NOTES REFERENCED BY A LETTER, AND DEFINITIONS OF TERMS.
5. UP TO 109' OF MHA MAY BE REQUIRED FOR HEAVY TRUCKS PER CONSTRUCTION DOCUMENTS.
6. UP TO 125' OF MHA OR PCC MAY BE REQUIRED FOR HEAVY TRUCKS PER CONSTRUCTION DOCUMENTS.
7. UP TO 97' OF PCC MAY BE REQUIRED FOR HEAVY TRUCKS PER CONSTRUCTION DOCUMENTS.

DEFINITION OF TERMS:

DRIVEWAY - EVERY ENTRANCE OR EXIT USED BY VEHICULAR TRAFFIC TO AND FROM LANDS OR BUILDINGS ADJOINING A HIGHWAY.

RESIDENTIAL DRIVEWAY - A DRIVEWAY SERVING NOT MORE THAN TWO FAMILY DWELLINGS OR AN APARTMENT BUILDING FOR FIVE OR FEWER FAMILY UNITS.

COMMERCIAL DRIVEWAY - A DRIVEWAY SERVING A COMMERCIAL ESTABLISHMENT, INDUSTRY, GOVERNMENTAL OR EDUCATIONAL INSTITUTION, PRIVATE AIRLIFT, HOSPITAL, CHURCH, APARTMENT BUILDING, OR OTHER CONSIDERABLE TRAFFIC GENERATOR.

MAJOR COMMERCIAL DRIVEWAY - ANY COMMERCIAL DRIVEWAY WHERE THE ACTUAL OR ANTICIPATED TRAFFIC VOLUME ON A TYPICAL DAY ARE LESS THAN THE VALUES STIPULATED FOR A MAJOR COMMERCIAL DRIVEWAY.

MINOR COMMERCIAL DRIVEWAY - ANY COMMERCIAL DRIVEWAY WHERE THE ACTUAL OR ANTICIPATED TRAFFIC VOLUMES ON A TYPICAL DAY ARE LESS THAN THE VALUES STIPULATED FOR A MAJOR COMMERCIAL DRIVEWAY.

FIELD ENTRANCE - A DRIVEWAY SERVING A FARMYARD, CULTIVATED OR UNCULTIVATED FIELD, TRANSMISSION OR DISTRIBUTION LAND NOT USED FOR INDUSTRIAL, COMMERCIAL, OR RESIDENTIAL PURPOSES.

SIGHT / VISUAL - THE ENGINEER WILL DETERMINE THE AREA CHARACTER BASED ON WITHOUT DRIVEWAY BUSHES AND/OR SHRUBS (SEE CHAPTER 2, SECTION 2.4).

MINIMUM PAVED FLAT (MPF) - THE MINIMUM DISTANCE FROM THE OUTSIDE EDGE OF TRAVEL LANE, "TL", TO THE CONCAVE BOTTOM OF PROFILE AS MEASURED ALONG THE CENTERLINE OF THE DRIVEWAY ENCOMPASS THE SHOULDER WIDTH.

PAVEMENT LENGTH ("PL") - THE DISTANCE FROM THE ROADWAY EDGE OF PAVEMENT TO THE END OF PROPOSED DRIVEWAY PAVEMENT AS MEASURED ALONG THE CENTERLINE OF THE DRIVEWAY (NOTE THAT "PL" IS MEASURED FROM DIFFERENT POINTS THAN "MPL").

TRANSITION LENGTH ("TL") - THE DISTANCE ALONG THE CENTERLINE OF DRIVEWAY BEYOND THE DRIVEWAY PAVEMENT LENGTH ("PL") TO THE END OF PROPOSED DRIVEWAY WORK NECESSARY FOR SMOOTH DRIVEWAY ENTRANCE LAYOUT. OR TRANSITION REQUIRED. THE TRANSITION LENGTH ONLY APPLIES TO NON-PAVEMENT DRIVEWAYS EXAMPLES: DIRT, GRASS, GRAVEL, OR STONE DRIVEWAYS.

DRIVEWAY OFFSET - THE DISTANCE FROM THE INSIDE EDGE OF THE PAVEMENT TRAVEL LANE OR TURNING LANE TO THE ROADWAY EDGE OF PAVEMENT EQUALS QUITEWAY TURNING LANE + PAVED SHOULDER OR CURB OFFSET.

ROADWAY EDGE OF PAVEMENT - THE OUTSIDE EDGE OF THE PAVED HIGHWAY SURFACE.

SUP (SHARED-USE-PATH) - A BICYCLE AND PEDESTRIAN FACILITY, OFTEN WITHIN RIGHT-OF-WAY, SEPARATED FROM MOTORIZED VEHICULAR TRAFFIC BY OPEN SPACE OR BARRIER. REFER TO DOT INSTRUCTIONAL MEMORANDUM 2012-01 FOR THE DEVELOPMENT OF BICYCLE FACILITIES FOR GUIDANCE ON BUFFER WIDTH AND SEPARATION OF SHARED USE PATHS FROM ROADWAYS.

SIDEWALK - A SMOOTH, STABLE AND SLIP RESISTANT EXTERIOR PAVEMENT INTENDED FOR PEDESTRIANS USE ADJACENT TO OR ALONG A ROADWAY WAY.

SHOULDER WIDTH - REFER TO THE PAVED SHOULDER WIDTH. SHOULDER WIDTH ALSO REFERS TO A PAVED SHOULDER, BIKE LANE, CURB OFFSET, OR OTHER PAVED AREAS OUTSIDE OF THE TRAVEL LANE.

GENERAL NOTES FOR DRIVEWAY STANDARD SHEETS:

GENERAL:

A. THE CONCEPTS STANDARD SHEETS APPLY TO FIELD ENTRANCES, RESIDENTIAL DRIVEWAYS AND MINOR COMMERCIAL DRIVEWAYS. MAJOR COMMERCIAL DRIVEWAYS SHALL BE DESIGNED ACCORDANCE AN AASHTO PASSENGER CAR DESIGN VEHICLE. MINOR COMMERCIAL DRIVEWAYS ACCOMMODATE AN AASHTO SINGLE UNIT TRUCK DESIGN VEHICLE.

B. WORK PERFORMED OFF THE RIGHT-OF-WAY REQUIRES A DRIVEWAY RELEASE TO BE ACQUIRED BY THE ENGINEER. A DRIVEWAY RELEASING WILL REQUIRE A TEMPORARY EASEMENT MAP.

C. SEE THE DRIVEWAY TABLE IN THE CONCEPTS PLANS FOR SPECIFIC DRIVEWAY LOCATIONS, DRIVEWAY TYPE, CORNER ANGLES, LENGTHS ("L"), MATERIAL, AND ENTRANCE TYPE.

WIDTH / LENGTH:

D. IF THERE ARE CONSTRAINTS THAT PREVENT THE CONSTRUCTION OF THE DRIVEWAY OPENING AS PER EITHER OF THE LAYOUT METHODS, THE ENGINEER MAY SPECIFY A SMALL CURVE RADIUS OF 5' OR 1'-1/2 BULLNOSE" CURB ALONG LOW SPEED HIGHWAYS, PROVIDED THE DRIVEWAY OPENING WIDTH WILL BEEN AS STANDARD SHEET "DRIVEWAY OPENING LIMITS".

E. FOR RESIDENTIAL DRIVEWAYS, THE MINIMUM PAVING LIMIT SHALL BE 1.5' FROM THE OUTSIDE EDGE OF TRAVEL LANE OR 6' BEHIND ANY SIDEWALK, IF PRESENT, WHICHEVER IS GREATER. FOR MINOR COMMERCIAL DRIVEWAYS THE MINIMUM PAVING LIMIT SHOULD BE 10' FROM THE OUTSIDE EDGE OF TRAVEL LANE OR 6' BEHIND ANY SIDEWALK, IF PRESENT, WHICHEVER IS GREATER. THE PAVING LIMIT MAY EXTEND BEYOND THE MINIMUM PAVING LIMIT FOR NEW DRIVEWAYS AND TO TRANSITION TO EXISTING PAVED DRIVEWAYS. THE PAVING LIMIT WILL BE NOTED IN THE DRIVEWAY TABLE OF THE CONTRACT PLANS.

F. FOR GRADING AND CONSTRUCTION REQUIREMENTS OF TRANSITIONS FROM PLACED ASPHALT CONCRETE TO EXISTING CONCRETE OR CONCRETE SIDEWALKS, REFER TO THE "TC-01.10 EXISTING DRIVEWAY" DETAIL AND TABLE 3 - "DRIVEWAY MATERIALS AND THICKNESS".

G. FOR PORTLAND CEMENT CONCRETE DRIVEWAYS, REFER TO THE 608 SERIES N.Y.S. STANDARD SPECIFICATIONS FOR METAL REINFORCEMENT, JOINT TYPES AND SAWING AND SEALING, ETC.

H. A 9" MINIMUM BUFFER STRIP SHALL BE USED UNLESS OTHERWISE SPECIFIED IN THE CONTRACT PLANS.

SITE CONDITIONS SIDEWALK / CURBS:

I. FOR PCC SIDEWALK WHICH CROSSES A DRIVEWAY SHALL HAVE A MINIMUM THICKNESS OF 8" AND INCLUDE FIBER REINFORCEMENT WITH 3" OF TOP COVER.

J. FOR TYPE 3 AND TYPE 4 DRIVEWAY ENTRANCES, WHERE THERE IS EXISTING SIDEWALK AND THE SIDEWALK ABUTS THE BACK OF CURB AT LESS THAN 2', USE THE TYPE 3 OR 4 SIDEWALK RAMP BY THE "SIDEWALK CURB RAMP DETAILS" STANDARD SHEETS 608-011.

K. FOR GRADE CHANGES GET CHART 4 OF 7 "URBAN & RURAL SECTION DETAILS", VERTICAL CURVES ARE RECOMMENDED TO CONNECT TANGENTS. SEE TABLE 5 - MINIMUM LENGTH OF VERTICAL CURVE" OR SHEET 2 FOR TYPICAL VERTICAL CURVE LENGTHS (L).

L. FOR PCC DRIVEWAYS THE SIDEWALK OR DRIVEWAY CROSSING CROSS SLOPE SHALL BE LESS THAN OR EQUAL TO 2%.

M. WHERE THE EXISTING GRADE OF THE DRIVEWAY PROFILE IS LESS THAN OR EQUAL TO 2% (2.0%), THE DRIVEWAY SHALL BE GRADED TO MATCH THE EXISTING SIDEWALK PROFILE GRADE. FOR PCC DRIVEWAYS, SEE NOTE L.

N. WHERE THE EXISTING GRADE OF THE DRIVEWAY PROFILE EXCEEDS 2% (2.0%), THE DRIVEWAY MAY BE RECONSTRUCTED TO A MINIMUM OF 2' IN WIDTH BEHIND THE SIDEWALK TRANSITION FROM THE EXISTING GRADE OF THE DRIVEWAY PROFILE TO THE SIDEWALK GRADE PROFILE.

O. SIDEWALK PROFILE IN FOR SMALL AGE EXCEED THAT OF STANDARD SIDEWALK, IN WHICH CASE THE SIDEWALK PROFILE SHOULD NOT BE LESSER THAN THE HIGHWAY GRADE.

P. USE DITCHIT STANDARD SHEET 608-05 SHEET 3 FOR SIDEWALKS CROSSING DRIVEWAYS ALONG CURBED HIGHWAYS AND STREETS.

Q. USE 1% REVERSAL AND SUITABLE CURB ACROSS DRIVEWAY ENTRANCES IF THE HIGHWAY RUNOFF WOULD OTHERWISE FLOW OVER THE DRIVEWAY OR IF SIDEWALK IS SLOPED BY THE DRIVEWAY AT A FIELD CONDITION.

R. TO PREVENT DRIVEWAY GRADES FROM EXCESSIVE THE VALUES IN TABLE 2 - MAXIMUM SLOPE OF SHEET 2, IT MAY BE NECESSARY TO DEPRESS THE DRIVEWAY ACROSS THE DRIVEWAY SIDEWALK AREA. WHERE THE DRIVEWAY ENTRANCE IS DEPRESSED, THE SIDEWALK SHALL BE DEPRESSED AT THE SAME GRADE AS THE DRIVEWAY. THE SIDEWALK SHALL RETURN TO ITS NORMAL GRADE AT THE OUTSIDE EDGE OF THE DRIVEWAY. WHERE THE DRIVEWAY IS DEPRESSED, THE LENGTH OF THE RAMP SITUATION THE RAMP LENGTH MAY BE INCREASED TO 12' WITH A RAMP SLOPE THAT EXCEEDS 8%).

S. WHERE DRAINAGE IS CARRIED ALONG THE CURB, CONSTRUCT THE DRIVEWAY WITH A SMOOTH UPGRADE FROM THE CURB TO THE SIDEWALK. WHERE THE DRIVEWAY CROSSES A CURB WITH A SLOPE OF 5% OR MORE, THE DRIVEWAY SHALL BE CONSTRUCTED WITH A DEPRESSED CURB AND SHALL HAVE ADEQUATE SHORT UPGRADE APPROACHES. CURB REVEAL ALONG THE DRIVEWAY OPENING MAY BE SPECIFIED BY THE ENGINEER. TYPICALLY, CURB REVEAL WILL NOT BE CONSTRUCTED IN RURAL AREAS. IF CURB REVEAL IS SPECIFIED FOR A SPECIFIC DRIVEWAY IT WILL BE NOTED IN THE DRIVEWAY TABLE OF THE CONTRACT PLANS IN THE "COMMENTS" COLUMN.

ENTRANCE TYPE:

T. THE ENGINEER MAY DETERMINE TYPE 1, TYPE 2 OR TYPE 4 RESIDENTIAL DRIVEWAYS TO BE TYPE 3 IF THE SIDEWALK IS WITHIN 2' OF THE CURB. IF MINOR COMMERCIAL DRIVEWAYS CONSTRAINS AVAILABLE SPACE, CONSTRUCTABILITY, SAFETY, AND FUNCTIONALITY, THE DRIVEWAY TYPE WILL COMPLY WITH TABLE 4 - "DRIVEWAY ENTRANCE TYPE SELECTION" ON SHEET 2.

U. FOR DRIVEWAYS WITH VARYING WIDTHS AND/OR CURVED ALIGNMENTS, DETERMINE THE DRIVEWAY WIDTH AND CURVED AISLE 10'-0" FROM THE EDGE OF TRAVEL LANE.

V. FOR A 2-WAY DRIVEWAY ENTRANCE OR EXIT, THE DRIVEWAY ENTRANCE WIDENING IS ONLY NECESSARY ON THE RIGHT SIDE OF THE DRIVEWAY AS YOU ENTER THE DRIVEWAY. A TURNING MOVEMENT CAN BE MADE SAFELY AND EASILY. THE WIDENING TABLES IN THE CONTRACT PLANS UNDER "COMMENTS" FOR DOUBLE ROADWAYS, A SMALL CORNER CURB RADIUS OF 2' OR 1'-1/2 BULLNOSE" CURB ALONG LOW SPEED HIGHWAYS SHALL BE CONSTRUCTED TO ELIMINATE A SHARP CORNER NEAR TO THE ROADLINE CURB TO SAFER FOR DISMOUNT OPERATIONS.

MATERIAL:

W. FOR DRIVEWAY MATERIAL REQUIREMENTS, SEE TABLE 3 - "DRIVEWAY MATERIALS AND THICKNESS" ON SHEET 2.

X. FOR FIELD ENTRANCES, THE MATERIAL WITHIN THE PAVEMENT LENGTH ("PL") CAN CONSIST OF GRAVEL OR STONE, AND THEY MAY BE CONNECTED TO THE EDGE OF THE HIGHWAY SHOULDER WITHOUT REMOVING ANY OF THE EXISTING SHOULDER MATERIAL.



FIGURE 1
TYPE 1 DRIVEWAY ENTRANCE
TYPICAL DRIVEWAY/ENTRANCE TYPE
NOTE: SEE RADIUS METHOD OF LAYOUT NOTES ON SHEET 6



NOTES:

1. REFER TO SHEET 1 FOR GENERAL NOTES, NOTES REFERENCED BY A LETTER, AND DEFINITIONS OF TERMS.
2. THE DETAILS SHOW THE PAVEMENT LENGTH ("PL") EXTENDING TO THE MINIMUM PAVING LIMIT ("MPL"). HOWEVER, THE "PL" CAN EXTEND BEYOND THE "MPL" AS SPECIFIED ON THE DRIVEWAY TABLE IN THE CONTRACT DOCUMENTS.
3. A DRIVEWAY TOP-UP SECTION SHOULD EXTEND TO A LOGICAL TERMINI (EXAMPLE SIDEWALK EDGE, WHERE THE DRIVEWAY GRADE MATCHES EXISTING GRADE OR LAYOUT POINT). FOR REFERENCE, A REASONABLE LENGTH FOR TAPERING THE TOP-UP SECTION BACK TO THE EDGE OF DRIVEWAY IS 3 TO 4 TIMES THE LENGTH OF EACH SIDE OF THE DRIVEWAY OPENING. SEE THE "DRIVEWAY TOP-UP DETAILS" NOTES TO MINOR STANDARD SHEET TITLED "MISCELLANEOUS CURB DETAILS" FOR THE CURB TRANSITION.
4. FOR DRIVEWAYS WITH A DRIVEWAY OFFSET LESS THAN 10', THE TAPER METHOD IS NOT GENERALLY RECOMMENDED, UNLESS IT CAN BE FIELD VERIFIED THAT THE DRIVEWAY ENTRANCE WIDTH WILL ACCOMMODATE THE VEHICLES THAT USE THE DRIVEWAY ON A REGULAR BASIS.
5. TYPE 3 AND TYPE 4 DRIVEWAY ENTRANCES CAN BE USED WITHOUT CURB IF A TAPER STYLE ENTRANCE BETTER MATCHES THE HIGHWAY CORRIDOR AESTHETICS OR SPECIFIC SITE CONDITIONS THAN A RADIUS STYLE ENTRANCE.

NOT TO SCALE

STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION	
U.S. CUSTOMARY STANDARD SHEET	
RESIDENTIAL AND MINOR COMMERCIAL DRIVEWAYS (SHEET 3 OF 7) DRIVEWAY ENTRANCE DETAILS	
EFF. LETTING DATE: 05/07/2015 ISSUED WITH EB 15-002	APPROVED JANUARY 1, 2015 /S/ RICHARD LEE, P.E. DEPUTY CHIEF ENGINEER DESIGN
EFF. LETTING DATE: 05/07/2015	ISSUED UNDER EB 15-002 608-03

DRIVEWAY OPENING LAYOUTS:

THERE ARE TWO RECOMMENDED DRIVEWAY OPENING MODELING METHODS: (1) THE RADIUS METHOD, WHICH UTILIZES A CIRCULAR ARC TO MODEL THE DRIVEWAY, AND (2) THE TAPER METHOD, WHICH UTILIZES A STRAIGHT TAPER MODELING CUT AT AN ESTABLISHED FLARE RATE.

THE RADIUS METHOD IS THE TYPICAL METHOD, ALTHOUGH THE TAPER METHOD IS A REASONABLE ALTERNATIVE FOR URBAN AREAS AND OTHER AREAS WHERE IT MIGHT BETTER MATCH THE HIGHWAY CORRIDOR AESTHETICS AND FUNCTIONALITY. SEE TABLE 4 - DRIVEWAY ENTRANCE TYPE SELECTION ON SHEET 2 FOR ADDITIONAL VARIABLES CONCERNING THE SELECTION OF A DRIVEWAY OPENING MODELING METHOD.

RADIUS METHOD OF LAYOUT:

STEP 1. LOCATE AN OFFSET LINE 11' PARALLEL FROM THE INSIDE EDGE OF THE OUTERMOST TRAVEL LANE.

STEP 2. SCRIBE A LINE PARALLEL TO THE OFFSET LINE, OFFSET "R" FEET SEE TABLE 6).

STEP 3. SCRIBE A LINE PARALLEL TO THE EDGE OF DRIVEWAY MEDIAN SIDES OFFSET "R" FEET.

STEP 4. FIND THE CENTER POINT OF THE CORNER RADIUS ARC, WHICH IS LOCATED AT THE INTERSECTION OF THE LINES FROM STEPS 2 AND 3.

STEP 5. FROM THE CENTER POINT, SCRIBE AN ARC WITH RADIUS "R" WHICH IS TANGENT TO BOTH THE OFFSET LINE AND THE EDGE OF DRIVEWAY. THE ARC SHOULD INTERSECT THE LINES AT THE DISTANCES SPECIFIED IN TABLE 7. DISTANCES IN TABLE 7 ARE BASED ON THE INTERSECTION POINT OF THE OFFSET LINE AND THE EDGE OF TRAVEL LANE AND THE PROJECTED EDGE OF DRIVEWAY. THE DISTANCE FROM THE ARC TANGENT POINTS (ARC DISTANCE) ALONG THE OFFSET LINE OR ALONG THE PROJECTED EDGE OF DRIVEWAY.

STEP 6. FIND THE DRIVEWAY OPENING LIMIT POINT WHICH IS WHERE THE ARC INTERSECTS THE ROADWAY EDGE OF PAVEMENT.

STEP 7. REPEAT STEPS 1 - 6 FOR THE OTHER SIDE OF THE DRIVEWAY OPENING.

FIELD LAYOUT NOTES 1

FOR THE RADIUS METHOD OF LAYOUT, IF OBSTRUCTIONS HINDER THE ABILITY TO SCRIBE THE CORNER ANGLE AND FROM THE CENTER POINT/LOCATE POINTS ALONG THE ARC BY USING "R" VALUES FROM TABLE 6 THROUGH 11 ON SHEET 7 AT VARIOUS DRIVEWAY OFFSETS ("R" AS